

PRICE BID OF INTERIOR CIVIL AND FURNITURE WORK OF KAIJ BRANCH					
S. No.	Particulars	Quantity	Unit	Rate	Amount
	A: INTERIOR AND FURNITURE WORK				
1	False Ceiling: Providing & fixing in position 12 mm thick gypsum board false ceiling fixed with 16 gauge galvanized frame supported from and fixed to RCC slab with Anchor bolts. The ceiling should contain approx. 40 % of the ceiling area of 12mm thick Mineral Fibre ceiling Board of Armstrong or equivalent approved make with framework, runners, cross runners & suspenders from the existing ceiling as per the manufacturers details and specification and 600X 600mmX 15mm thick mineral fibre ceiling (600*600 mm) - beuti sky or other approved pattern and stepping. All the joints to be properly sealed with jointing tape and finished with approved jointing material. The item includes making cut-outs and providing necessary frame work for light fitting, grill diffusers and ducts etc. which have to be made with frame of perimeter channels of size 20mm x 30mm x 0.55mm. thick supported suitably and angle bead is to be used at steps to get straight line finish etc. complete. The item rate shall also include preparation of surface with sanding, and 3 coats of Acrylic Emulsion paint in approved shade over a coat of primer / putty including necessary work etc. complete as per Bank Engineer's instruction.	320.00	Sq M		
2	Single window counter : Providing & fixing in position single window counter as per design, made of 18 mm / 19mm thick MR grade ply structure. The work top is to be made of 18 mm / 19mm thick MR grade ply structure. Thereafter, a doublelayer of flexi-ply (12 mm + 6 mm thick) (the bottom of this niche to have provision of cove lighting with LED strips) is to be fixed with necessary fittings to the plywood structure and laminated glass in approved shade. . All exposed external surface finished with 1 mm high gloss laminate and internal surfaces finished with 0.8 mm laminate of approved shade. The work is to be completed with providing of foot rest, key board tray with telescopic arrangement. vertical glass of 12 mm to be fixed at the front of SWO with one horizontal glass (if required) of approx 150mm with itching and crystal finish etc. complete as per instructions of EIC. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy available with Bank's Engineer.(size 1500x900x750 mm)	3	Rmt		
3	Providing and fixing factory made solid core flush door in single leaf 30 mm thick, finished with approved 1mm th. Laminate on both faces with / without glazing and venetians in the positions shown on the drawings or as directed, all necessary beads, moulding and lipping, Stainless Steel fixtures and fastenings with CP / brass mortise lock, Stainless Steel handles on both sides, stoppers and exposed woodwork finished with French-polish complete. (Without door frame).	0	Sqm		
4	Low / medium height partition: Providing and fixing in position low / medium height partition made of 50 x 50 x 1.2mm medium duty aluminium hollow square pipes framed at 0.6 m to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm thick laminate of approved shade & make, both sides including necessary opening / outing for receiving cheques & other papers, and to receive 10 mm th. Float glass including all necessary opening for electric / telephonic conduits etc. as per requirement. (Glass area in the partitions will be deducted in the measurements of partition).	20	Sqm		
5	PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE Same as item no 8 but with 25 X 25 X 1.2 mm thick aluminum section and covered with 6 mm thick MR grade ply both sides with 1 mm thick laminate including 75 mm long SS hinges with countersunk SS screws, approved make Night latch, 75 mm long S.S Handles, Door stoppers, 150 mm S S towerbolt etc complete as directed.	0	Sqm		
6	Glass partition: Providing and fixing 10 mm thick glass with etching as per design for low height partitions held with SS clits (D brackets). All exposed glass edges with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of French polish/ melamine polish.	8	Sqm		
7	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS For Main Entrance Door For Branch and E-Lobby Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings. The door will have patch lock, pti pivot, 100 Kg floor spring & 25 mm	10	Sqm		
8	Same as above item but P & F fully glazed partition with Patch Fitting for front side of Main Entrance [Fixed Portion] For Branch and E-Lobby	20	Sqm		
9	P /F 12mm th Toughened glass between two machines with frosted Film complete as directed. Glass edges shall be diamond polished. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer dimensions shall be measured and paid).complete line & level. The door will have S.S brush finish Signage for pull & push.	0	No.		
10	Providing and fixing in position door closer of approved make (Hyper / Godrej or equivalent).	0	No		

11	Officer and Staff Tables : Providing & fixing in position tables made of 18/19mm MR grade Ply at top, side and front, support along with drawer unit & Key board tray with telescopic arrangement & CPU base resting on foot rest of teak wood member of 75 x 40 mm. 19mm th MR grade ply modesty panel. All external surfaces to be finished with 1 mm thick laminate and internal surface finished with 0.8 mm of approved shade and make. Including powder coated fittings like sliding channels, for key board & drawers, medium duty hinges for shutter, cable manager. S.S. handles in approved design and size and locks wherever directed in approved make. All exposed plywood edges to be finished with 6mm th. Teak wood beading with French polish in approved shade and necessary locks to shutters etc. complete in all respects. Design and detail of the table shall be as per Bank's new uniform colour, layout & elevation policy available with Bank's Engineer.				
a	BM Table -1800x750x750 mm	1	No.		
b	Officer's Tables - 1500x750x750 mm	8	No.		
c	Staff Table -1200x750x750 mm	0	No.		
12	Grahak Mitra Table : Providing & fixing in position Grahak Mitra table of size 1350 mm*750mm*675 mm made of 18 mm MR grade Ply at top, side and front, support along with drawer unit & Key board tray with telescopic arrangement & CPU base resting on foot rest . 18 mm th MR grade ply modesty panel with fixing blue glass. All external surfaces to be finished with 1 mm thick laminate and internal surface finished with 0.8 mm of approved shade and make. including powder coated fittings like sliding channels, for key board & drawers, medium duty hinges for shutter, cable manager. S.S. handles in approved design and size and locks wherever directed in approved make. All exposed plywood edges to be finished with 6mm th. Teak wood beading with french polish in approved shade and necessary locks to shutters etc. complete in all respects (special design may be provided by Architect /engineer as per requirement)	1	No.		
13	Low height & Full height storage with laminate finish: Providing & fixing in position 400mm deep low/full height storage made of 18/19mm MR grade ply at top, front and side with 12 mm MR grade ply at back, all external faces including back to be finished with 1 mm thick multi-colour laminate at outside and inside finished with 0.8 mm laminate with locking and SS handle arrangement of approved make complete with openable type shutter, beading patti etc. All exposed plywood edges to be finished with 6mm th. Teak wood beading with French polish in approved shade complete in all respect.	20	Sqm		
14	Full height glazed/Partly glazed /solid with plywood and laminate : Providing and fixing in position solid/ partly glazed / partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade and make with 6 mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	110	Sqm		
15	Full height solid with plywood and calicum silicate board: Providing and fixing in position solid/ partly glazed / partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and e 12 mm thk. Calcium silicate board on both sides as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	10	Sqm		
16	Full height solid with plywood and laminate/calicum silicate : Providing and fixing in position solid/ partly glazed / partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade one side and one side 12 mm thk. Calcium silicate board on other side as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	0	Sqm		
17	Full height panelled partition for server room: Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 3mm aluminium composite panel of approved shade necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	0	Sq m		
18	Providing and fixing side table Size 900x400x750 mmmade of 18/19 mm thick ply for all top, support and side with 6 mm thick ply at back externally finished with 1.0 mm thick laminate and All internal surfaces to be finished in approved 0.8mm thk laminate , both of approved make including brush finish S S handles, shutters , hinges with necessary teak wood beading including three coats of french polish to teak wood member and necessary locks to shutters etc. all required surface	7	No		

19	Providing and fixing drawer/shutter unit 450mm*600mm size,out 18 mm thick MR grade commercial ply for shutter, side, front and base of drawers ,12 mm thick MR grade comm. Ply for shelf ,side and back running on heavy duty telescopic channels (ebco)make,SS b locking arrangement for both drawers and shutter along with necessary hardware.10 mm thick T>W> bidding/lippoing to edges of MR grade comm.ply finished with 1 mm thick laminate on external surface and 0.8 mm laminate on internal surfaces with finishing etc. complete	2	No		
20	Cheque Writing desk : Providing & fixing writing desk out of 19mm th.MR grade ply & 1 mm th. Laminate complete. Size 3'-0" x 1'-6"	2	No		
21	Notice board : Providing & fixing notice board with approved upholstery. Size 3'-0" x 1'-6"	2	No		
22	Roller blinds : Providing & fixing in roller blinds of approved make (Vista / Aerolux) and shade with all accessories and necessary fittings etc.	20	Sqm		
23	Providing and fixing counter type desk made of 18/19 mm thick ply for top , sides, with a cabinet with a drawer & shutter finished with 4 mm thick veneer to outer facae and 0.8 mm laminate inside, as per specifications including provision for CPU base and footrest	1.2	Rmt		
24	Providing Chairs of approved quality and make				
a	BM Chair (basic cost Rs. 7000)	0	No		
b	Staff chair (basic cost Rs. 5000)	0	No		
c	Visitor chair (basic cost Rs. 3500)	0	No		
25	Providing & fixing Panelling in out of 12 mm thick ply and 1.0 mm thick laminate with aluminium frame 50mmx25mmx1.2 mm in walls with screws and finished with approved shade and make to column with accessories and as per Bank engineer's instructions etc. complete	150	Sqm		
26	Providing & fixing Paneling out of 6 mm thick ply and 1.0 mm thick laminate of approved shade and make to existing columns , tables , partitions,doors along with necessary accessories required if any etc. Complete as directed by engineer in charge	10	Sqm		
27	P/F designer's cladding for central columns	0	sqm		
28	Providing and fixing panelling on External walls, ATM walls and for External Rolling Shutters boxing. Framing shall consist of Both ways horizontally and vertically on the wall/column with Aluminium Sections of 50mmx25mmx1.2mm as directed by Bank /Architect. This framing would be covered with 6mm thk. Comm. Ply (In case of wooden frames), finished with 3mm thick exterior grade multi-coloured "Aluminium Composite Panel". The rate shall be inclusive of necessary scaffolding, cut-outs, fixtures and fittings, sealant etc. complete.	65	sqm		
CIVIL WORK					
31	VITRIFIED TILE FLOORING				
	Providing and laying Double charged vitrified floor tiles (thickness to be specified by the manufacturer)including skirting with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 800x800 mm. (Basic Rate - Rs. 950/-sq.m)	0	sqm		
32	REMOVING OF EXISTING FLOORING				
	The work includes removing existing tile flooring in bank premises & disposing the debris outside the premises to the safe place as directed by all leads,complete	0	sqm		
33	EMULSION PAINT				
	Prepare surface and paint two coats of plastic emulsion paint of approved colour and shade over a coat of primer including Alteck putty after thoroughly scrapping the existing internal walls.	50	sqm		
34	ENAMEL PAINT				
	Prepare surface and applying two coats of Synthetic Enamel paint of approved colour and shade over a coat of anti corresive paint after thoroughly scrapping the existing paint	40	sqm		
35	EXTERNAL PAINT				
	Providing and applying anti-peel paint of approved make & approved brand Exterior Emulsion paint of approved quality, colour and shade to old and new surface in two coats, including exterior acrylic primer coat, scaffolding, preparing the surface etc. complete (HeatReflective Paint).	50	Sq.m		
36	FLUSH DOORS WITH RCC DOOR FRAME				
	Specficvaton same as the flush door item no. 6 but with RCC frame of size 6"x3"	0	Sq.M		
37	VENTILATORS - ALUMINUM LOUVRED				
	Providing and fixing powder coated Aluminium louvred glazed Ventilators with 4 mm thick ground glass, including all necessary fittings & fasteners etc. complete.	0	Sq.m		
38	ALUMINUM SLIDING WINDOW				

	Providing and fixing powder coated Aluminium sliding / up lifting windows and 4 mm thick plain glass, including all necessary fittings & fasteners etc. complete.	0	Sq.m		
39	BRICK JELLY CONCRETE				
	Providing and filling brick jelly concrete in Toilet sunken area with necessary chemical mixing plastering type water proofing treatment etc. complete. Rate should be inclusive of dismantling the existing flooring and brick jelly concrete & clearing the debris away from the site as directed by the Client / Architect.	0	Cumt		
40	HALF BRICK MASONRY				
	Providing & Laying Half brick masonry with of class designation 40 in super structure above plinth level up to floor 3 level including the cost of scaffolding. in super structure including mild steel longitudinal reinforcement of 2 bar of 8 mm diameter at every third course, properly bent and bounded at ends scaffolding, raking out joints 'and watering complete. (G +1 Floor)	0	Sq.m		
41	INTERNAL CEMENT PLASTER				
	Providing internal cement plaster 12mm thick in a single coat in cement mortar 1:6 to concrete or brick surfaces, in all position in two coats to be mixed with liquid integral water-proofing compound-standard acrylic polymer coating, (proportion-as per manufacturer's instructions) including scaffolding & curing complete. (G +1 Floor) (Water-proofing compound make-PERMA- Plasto-proof Std,Roff Hyguard, Monopol 456, Dr. Fixit Pidiite 2K). Item includes removing existing plastering wherever required.	0	Sq.m		
42	GRANITE WORK TO STEPS/STAIRCASE/OTHER WORK				
	Providing and laying Jet black granite stone of 17-18 mm thick for door frame/ dado/ window boxing, staircase treads with full round moulding, 03 nos, grooves and risers, Partition between Urinals, beside kitchen platform. On C.M.1:6 including filling joints with polymer base filler nosing the sharp edges wherever necessary, curing, etc. complete. Sand Factor-0.02	0	Sq.m		
43	S.S. RAILING				
	Providing & fixing SS railing as per drawing out of 50 mm dia. Pipe (14 gauge) with vertical ballusters, handrail, 25mm dia hollow intermediate pipes to staircase with all necessary fastening screws, base plates, material & labour.	0	Rmt		
44	TOILETS FLOORING				
	Providing and laying Double charged vitrified flooring (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Item includes removing existing tiles & skirting, disposing the debris as directed. Size of Tile 600X600 mm. (Basic Rate - Rs. 750/-sq.m)	0	sq.m		
45	WATER PROOF BEDDING				
	Providing water-proof bedding for flooring of Bath and WC 25mm thick in C.M.1:3 including using approved water-proofing compound inspecified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10years guarantee on court fee stamp paper of Rs.500/- including ponding test etc.complete.	0	sq.m		
46	WATERPROOFING				
	Providing waterproof neat cement plaster in W.C. & urinals sunken area in 12 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of 1 kg. per bag of cement of approved make and manufacturer and curing etc. complete. (Excluding Tiles) (As directed by Engineer in charge)	0	sq.m		
47	VITRIFIED TILES ON TOILET/KITCHEN WALLS				
	Providing and laying 1st quality vitrified tiles to walls of toilets (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Item includes removing existing tiles. Size of Tile 600x600 mm. (Basic Rate - Rs. 750/-sq.m)	0	sq.m		
48	KITCHEN PANTRY PLATFORM				
	Providing & fixing Kitchen/Pantry platform 650 mm wide out of 18 mm thk. Black granite supported over 12 mm thk. cement sheet including double moulding on the edges to granite, SS Nirali Sink (550 x 450 with drain board-3 Nos.), with 25 x 50 mm size Aluminium pipes TW inserted, for framing below counter, to hold 18mm thk. MR grade comm.ply shutters on 4" long s.s.hinges. PLY shutters to be finished with 1mm thk Laminate as approved by Bank/Architect with finishing etc. complete. Item includes removing existing platform, tiles, etc, disposing the debris as directed and raising 4" high platform for drinking water cooler with trap, outlet & required piping..	3	Rmt		
49	WATERPROOFING TREATMENT				

	Providing and applying water proofing treatment using acrylic polymer modified cement based water proofing coating with fibre glass mesh mixing at the rate of powder to liquid (2:1) by weight covering 9 to 10 sqm /kg with two coat using Dr. Fixit or alike of chemicals for masonry and concrete surface by brush covering 7 years guarantee on Stamp Papers etc. complete.	0	sq.m		
	Plumbing/Sanitary work (Toilet fittings - Parryware/ Hindware/ Cera/Jaquar make.)				
50	Providing and fixing white vitreous china Orissa pan (Indian WC), with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid	0	No.		
51	Providing and fixing white vitreous china wall hung water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat	0	No.		
52	Providing & fixing 4mm thk mirror in toilet of size 1800mm x 1200mm with polished edges fixed on 32mm mirror holder or as directed by Architect	0	No.		
53	Providing and fixing pedestal wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste coupling of standard pattern, including painting of fittings and brackets and making good the walls wherever required.	0	No.		
54	Providing and fixing white vitreous china flat back or wall corner type lipped front Urinal of 430x260x350mm and 340x410x265mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps	0	No.		
55	Providing & fixing PVC liquid soap holder of approved design and colour with screw	0	No.		
56	Providing and fixing in position C.P. brass Taps & fittings with approved make & design etc. complete. (Parryware/ Hindware/ Cera/Jaquar make.)				
a	15 mm dia. Angular stop cock.	0	No.		
b	15 mm dia. Bibcock 2-way	0	No.		
c	15 mm dia. Pillar cock. (Minimum 150 mm high)	0	No.		
57	Providing and fixing 10cm SWR Nahani Trap with S.S. jali including SWR bend and piece of pipe up to the outside face of the wall complete.	0	No.		
58	Providing and fixing following dia. unplasticised SWR soil/vent / waste pipes with stand working pressure of 4 kg/cm ² soil waste pipes confirming to IS:13592 and IS:4985 including jointing with seal ring confirming to IS :5282 leaving 10mm gap for thermal expansion with necessary fixtures' and fittings such as bends, tee, single junction, double junction, slotted vent offsets, cowl with cap on walls or in the ground including fixing the pipe on walls by means of nails & clamps driven through huge in wood holder/ battens fixed with concrete blocks and supported on gr. floor by C. C. 1:2:4 30 X 30 cm size etc. complete.				
a	110 mm dia.	0	Rmt		
b.	75 mm dia.	0	Rmt		
59	Providing and fixing Towel Rail (CP finish - 0.60m long)	0	No.		
60	Providing and fixing Hand Shower(Health Faucet) with 1 mtr long Easy flex tube-chrome finish & wall hook (ALD-CHR-585-Jaquar/Hindware/Cera/equivalent)	0	No.		
61	Providing and fixing 40 mm dia. PVC soil/vent / waste pipes with necessary fixtures' and fittings such as bends, tee, single junction, double junction on walls or in the ground including fixing the pipe on walls by means of nails & clamps driven through huge in wood holder/ battens fixed with concrete blocks and supported on gr. floor by C. C. 1:2:4 30 X 30 cm size etc. complete.	0	Rmt		
62	Providing and fixing C.P. brass angle valve for basin mixer/geyser points of approved quality conforming to IS:8931 a) 15 mm nominal bore	0	No.		
63	Providing and fixing Stop cock CPVC of approved make including the necessary socket, union, nut complete.				
i	50 mm dia	0	No.		
ii	40 mm dia.	0	No.		
64	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.				
a	50 mm dia	0	Rmt		
b	40 mm dia	0	Rmt		
	Concealed work including cutting chases and making good the walls etc.				
c	25 mm dia	0	Rmt		

d	15 mm dia	0	Rmt		
65	Providing and laying Cast in situ/Ready Mix cement Plain Cement Concrete in M-10 of trap/ granite/quartzite/ gneiss metal for foundation and bedding including bailing out water, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	0	Cu mt		
66	Providing and fixing in position reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams and columns, canopies, staircases, newels, chajjas, lintels, pardis, coping, fins, arches etc. as per detailed design and drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed. (use TMT steel only.)	0	M.T.		
67	Providing & fixing Pantry Platform 750 mm wide out of 20 mm thk. Black granite supported over 12 mm thk. cement board including double moulding on the edges to granite, SS Nirali Sink (550 x 450), with 25 x 50 mm size Aluminium pipes TW inserted for framing below counter, including water supply CPVC pipes & bib-cocks, etc. complete. (Item includes dismantling of existing platform).	0	RMT		
68	Providing and fixing heavy duty inter locking concrete coloured paving blocks of 60 mm thickness of having a strength of 300 kg/sq cm of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc complete.	0	Sq MTR		
69	Providing and fixing granite stone to treads and risers of staircase and entrance including all necessary material and labour.	0	Sq MTR		
70	Providing and laying Ceramic glazed floor tiles(Antiskid) of any size (9-10mm thickness) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 sand) including pointing the joints with white cement and matching pigment, curing etc., complete.(Basic rate of Tile Rs. 650/Sq.m.)	0	SQ MTR		
71	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (6-7mm thickness) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Architect in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete (Basic rate of Tile Rs. 550/Sq.m.)	0	SQ MTR		
72	Providing and applying fibre reinforced elastomeric liquid water-proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof slab in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge. For horizontal surface one coat @1.85 kg per sqm. Single component UV resistant flexible acrylic coating, vapour permeable membrane(1.0 mm thick) & eco-friendly. Application with brush.Curing must be done by only placing a wet hessian at least upto 72 hrs after drying, and thereafter by proper curing with water(Make-Perma- Eazee Coat/Choksey-Acrylic colour membrane/ROFF-Hyguard EX)	0	SQ MTR		
73	Providing and applying water proofing treatment to vertical surface of brick and R.C.C. wall, elevated and overhead R.C.C./ brick water tanks and sumpwell etc. in all directions by using standard acrylic copolymer coating of Roff Hyguard, Monopol 456, Dr. Fixit PidiLite 2K or equivalent in two coats including cleaning the surface by wire brush, washing and drying it, and as directed by Engineer incharge etc. complete	0	SQ MTR		
29	Charges for removing of existing false ceiling, furniture, fixtures and disposal of same as per site conditions and as directed	0	lumpsum		
30	Buy back of dismantled furniture (excluding usable chairs if any) (-)	0	lumpsum		
				TOTAL	
				DISCOUNT IF ANY	
				TOTAL AFTER DISCOUNT	
AMOUNT IN WORDS					

THE RATES ARE EXCLUSIVE OF GST. GST WILL BE PAID AS APPLICABLE