

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK AT DRM RATLAM (M.P)					
S.No.	Description of Item	Unit	QTY	RATE	Amount
A	Interior Works :				
	Mode of Measurements : Area of exposed and finished surfaces will be measured.				
	False Ceilings :				
1	Gypsum Board False Ceiling :				
	Providing, making and fixing Gypsum Board False Ceiling :- 12.5 mm thick G.I. Perimeter Channels of size 0.55mm thick. G.I. intermediate channels of size 45mm from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick intermediate channel at 450-600 mm c/c Two coats of primer + two or more coats of plastic emulsion paint Note -Including all fittings,material, labour,cut outs required for light fixtures, Speakers, screws and joint paper/fibre tape etc. complete.	Sqm	45		
2	Cove in ceiling :				
	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.	Rmt	55		
3	Mineral Fibre Grid Tile Ceiling :				
	Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong, Gyproc or equivalent make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanised Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc or equivalent stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T - section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include all fittings and materials complete including proper installation and provisioning etc. The work is to be completed as per manufacturer's specification .	Sqm	26		
	Partitions :				
	Rate to be included of all kinds of planes/levels, profiles and cut outs, etc. required for light fixtures, trap doors and ACs, boards, provision for light fittings and diffusers have to be made at no extra cost supported with metallic section etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC Works for cabling, AC pipe works, etc.				
4	Full Height Partly Glazed/ Solid Wooden Partitions (Including Door) :				
	Providing and fixing full height partly wooden, partly glazed/ Solid partitions- specifications (Measurement shall be taken up to finished partition level & not of frame work and sal wood member shall go up to slab/beam soffit) Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways 8 mm thk. MR plywood Termite & Borer proof from both the sides 1.0mm thick approved shades of laminate 5 mm thick float glass (for Partly Glazed Partitions) Etching as per approved design including 32mm partly glazed/ fluse door with teak wood Beading 1 mm lamination on both sides 8 mm plain glass, (for partly Glazed Doors) with Frame of 100mm x 50 mm, Note -Including all fittings,material, screw, labour etc. Complete.	Sqm	20		

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK AT DRM RATLAM (M.P)

S.No.	Description of Item	Unit	QTY	RATE	Amount
5	Low Height partitions With / Without Glass : Providing and fixing Half Height (approx-1200 mm ht.) partitions. Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways(Horizontal/Vertical) 8 mm thk. MR plywood Termite & Borer Proof from both the sides 1.0mm thick approved shades of laminate, 12.00 mm thick float glass Etching as per approved design wicket gate wherever required with Godrej Night latch Note -Including all fittings,material, SS hinges, SS tower bolts screw, labour etc. Complete. (Making provision for items like softboards, white boards,etc. as & where required.	Sqm	12		
	Panelling Works (Walls , Columns, etc):				
	Rate to be included of all kinds of levels/planes, profiles and cut outs required for elevation and fixing of light fixtures, trap doors and ACs, provision for light fittings, boards and diffusers have to be made at no extra cost supported metallic sections, etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC contractor for cabling, AC pipe works, etc.				
6	Wall/Column Panelling Providing, making and fixing single skin paneling (Using 8 mm thick MR plywood), plain and/or curved in profile, on walls, front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises, upto 3 mt height and boxing of 0.10 – 0.45 mt. ht., as required, made out of 50 x 25 x 1.0 mm thk weighing 0.467 kg/rmt aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 6 mm thick MR plywood shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling edges / is to be provided with laminate or teak wood decorative beeding of 35mm x 20 mm finished with polish/painting as directed.	Sqm	95		
7	Cabinet for Electric Panel : Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thk MR grade plywood. All visible surfaces shall be laminated with 1 mm thick Laminate on external surfaces of approved made and shades & painting the internal surfaces with 2 or more coats of synthetic enamel paint, including providing teakwood lipping of size 20 x 6 mm on edges. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet).	Sqm	3.5		
8	Main Door – Toughned Glass Providing, making and fixing Toughned Glass Door:- 12mm thk single/double shutter toughened glass doors, Including Floor springs make Hardwvn/ozone/Dorma or equivalent set, Upper patch, lower patch, lock key plate, provision of locking system, etc. One set of 25 mm dia S. S. brush finish pull handles (approx. 300mm length) "C" shaped, of appoved make Including Etching pattern, Note- Including, labour, transport, material, delivered and placed in position at site of work.	Sqm	5		
9	Toughened Glass Fixed Glazing Providing, making and fixing Toughened Glass :- a. 12mm thick toughened clear float glass b. Fixed with " D " brackets/ SS fittings as required. c. Etching film to be done as directed Note-The cost to include all materials, labour, hardware etc.,	Sqm	3		

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK AT DRM RATLAM (M.P)

S.No.	Description of Item	Unit	QTY	RATE	Amount
	Flush Door / Partly Glazed Door with Frame				
10	Providing, making & Fixing of partly Glass/ Flush door at site,-32 mm thk flush door with teak wood Beading at Edges 1 mm lamination on both sides 8 mm plain glass, (for partly Glazed Doors) The cost shall include Frame of 2nd class BTC/ Teak wood Frame of 100mm x 50 mm, Including all fitting like Mortice lock with 2 nos Handels , S.S. 125Mm Heavy duty Hinges 3 Nos. Door stoppers, 2 Nos Tower Bolts 200mm Note- Including all materials, labour, transport, taxes, delivered and placed in position at site of work.	Sqm	2		
	Furnishing Works :				
	Providing multidrawer Godrej or Ebco single lock and approved brass handle for each drawer. Providing circular holes in table top for cables with PVC cable managers of 65 mm dia and cap. On the left side platform at bottom for CPU.The bottom compartment made up of 18mm thick. MR plywood. The exposed edges of the plywood to be provided with TW lipping of size 20x6 mm duly polished. One M S powder coated keyboard tray with mouse tray as manufactured by ebco (KBTM 45) or EGL (KBT-M-001) including sliding channel as per manufacturers specification to be provided below the working platform.				
	Tables :-				
	Providing and supplying table detailed below : 1.-18 mm thick MR Plywood 2.- 1 mm thick laminate on external surfaces and 0.8 mm thick lamination on internal surfaces of approved made 3.- TW half round beading of sect 20 x 12 mm duly polished 4.- Drawer unit of width 350mm (clear internal), consisting of set of 3 nos. of drawer. 5.-Drawer made of 18 mm thk. MR Ply wood for the front and rear 12 mm MR Plywood for sides and 6mm thk MR ply for the bottom sliding & teak wood beading of sect. 20 x 6 mm 6- EBCO Sliding Telescopic Rail +M S powder coated keyboard tray with mouse tray. Note all fittings, fixtures, locking arrangement, handles, etc. Complete.				
11	Executives Branch Manager Table :	Nos.	1		
	same as above but providing and supplying Executives Branch Manager of size -1.80 m x 0.90 m x 0.75 m ht.				
12	Officer / Relationship Manager/ Auditor Tables :	Nos.	1		
	same as item above but providing and supplying Officer / Relationship Manager/ Auditor Tables of size 1.65 - 1.50 m x 0.75 m x 0.75 m ht.				
13	Single Window Operator Counters :				
	Single Window Operator Counters : same as above item & Following specifications and per dimensions specified.:- a. Size- 1500mm - 1350mm x 900mm - 800mm x 750mm height. The top drawer to have cash separation arrangement. b. 18 mm thick MR Plywood c. 1 mm thick laminate d. The table edges shall be double thick, outside surface shall be curved using 3 layers of 6mm flexible plywood e. Finished with 1 mm thick Plain or Textured Laminate Hidden areas like inside of drawers, cabinets, finished with 0.8 mm white laminate.including all fitting labour, material etc complete.	Rmt	4.2		
14	Wall Mounted Writing desk :				
	Providing and fixing half round / rectangular customer voucher holders writing counter of width 900 mm and maximum depth 450 mm fixed to be wall or partition at a height of 1050mm made of 18 mm thk. MR plywood and 12 mm thick glass top, and sides and edges shall be finished with 1 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed . The cost shall be completed with lippings, mouldings, fittings,and accessories etc as per specification. as per the drawing and instruction given by the Bank Engineer.	Nos.	1		

S.No.	Description of Item	Unit	QTY	RATE	Amount
15	Storages / Credenza :				
	Officer Storage/Side Credenza/Back Credenza :				
	Providing, making and placing in position Side Credenza storage:- Size 375mm depth, height of 750 to 900 mm 18 mm MR grade plywood construction with 6mm thk. MR grade plywood backing complete. 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. 4- All drawers shall be fitted with telescopic channels and locking arrangement laminated with 1 mm thick plain external surfaces and 0.8 mm thick white lamination on internal surfaces Note- SS Hinge, SS handles, magnetic catchers Godrej or ebco lock & brass handles all approved make etc.	Sqm	10		
16	Corian Marble Surfaces on Furniture / Partitions :				
	Supplying, Fabrication and Installation of Dupont/Corian of thickness as specified below, applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate, in plain or curved profile. To minimize material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in - Salt(Translucent series), Azure & Diamond Blue, preferably on BM's table, SWO counter, as directed.				
A	12 mm thick	Sqm	9		
B	Deduction for lamination work wherever Corian is been used (area same as Corian).	Sqm	-9		
	Glass Works :				
17	Toughened Glass Dividers For Single Window Counters and Front Partition Glazing / ATM :				
	Providing, making and fixing Toughened Glass :- a. 12mm thick toughened clear float glass b. Fixed with " D " brackets/ SS fittings as required. c. Etching film to be done as directed Note-The cost to include all materials, labour, hardware etc.,	Sqm	10		
18	Drop & Complaint Box :				
	Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.	Nos.	2		
19	NOTICE BOARD :				
	Providing & fixing at site notice board of size 3' x 2' to be made up of kail/pine wood frame of size 2" x1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the design & drawing etc complete.	No.	2		
20	ACP Panelling Works :				
	Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with & ATM with framing:- 1.-M.S. Tube sections of min. 50 mm x 25 mm and 16 gauge, @ 600 mm c/c or less. 2.-thickness of 3 mm minimum. Alubond / Eurobond / Fujibond / Alcobond or equivalent Note- The cost shall include all fittings, scaffoldings, chase making, lifting, cutting, on site adjustments, plaster repairing, etc. complete.	Sqm	28		

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK AT DRM RATLAM (M.P)

S.No.	Description of Item	Unit	QTY	RATE	Amount
21	ALUMINIUM WINDOW Bronze Anodised (SLIDING) : Three track Providing and fixing composite windows with upper portion of 300-500 mm (height) fixed and bottom portion of about 1200 mm to be sliding with 3 track using standard approved section and 5.5mm float glass, to be provided with rubber gaskets, locks, handles, silicon sealants on all edges, Complete as per design and direction of Engineer – in charge. Net sliding shutter to be provided as & where required.	Sqm	4		
22	Aluminium Frame Glass Door for UPS / Server Room : Providing and fixing at site door to be made up approved shade of powder coated aluminum sections (heavy duty) as top & bottom sections with 6.0mm thick plain FLOAT glass in between, the glass panel shall have round polished edges. The external frame of the door shall be of size 100 x 50 x 2.0mm powder coated aluminum Box section section to be fixed in walls / as per site with anchor fasteners and heavy duty mechanical screws. The door shutter shall be in aluminum sections 85.0 x 44.5 x 2.0mm for top, and sides and 114.3x 44.5x 3.0mm in bottom rail, inclusive of with standard aluminum clips to be made strictly as per the drawing. and pivot arrangement ,with SS handles, all necessary fittings, all labour, materials, etc complete. (to be fixed in sever & UPS room)	Sqm	2		
	Hardwares :				
23	Providing and fixing Door closers on doors of make Everite/Ozone/ Hardwyn/ Dorma or equivalent upon approval including all packing, levelling, etc. as required.	Nos.	4		
	TOTAL AMOUNT FOR INTERIOR WORK				
B	CIVIL WORK				
24	Demolishing Brick work manually/ by mechanical means including disposal of unserviceable material outside the site (approx 4-5km) including loading unloading, transportation and as per direction of Engineer - in- charge.	3.00	cum		
25	8" BRICK WALL Brick work with common burnt clay M.K.S. (Modular) local Best available Local Bhatta/ Chimney Bricks of class designation 40 in superstructure above plinth level up to floor 3 level in all shapes and sizes in Including all material, Labour etc Complete. Cement mortar 1:4 (1 cement : 4 coarse sand)	2.00	CUM		
26	4" BRICK WALL 100mm Half brick masonry with common burnt clay Local Best available bhatta/ Chimney Bricks of class designation 40 in superstructure above plinth level up to floor 3 level, including laying of 50mm Thick RCC Band at every 1.20 M apart with 2 nos 8.0mm thick Ms tor Bars including laying, bending all materials, labour etc complete. Cement mortar 1:4 (1 cement : 4 coarse sand)	25.00	SQM		
27	12-15 mm cement plaster (Internal) over the brick wall surfaces inside plaster over double or single brick wall of mix including all material , labour, etc complete.	65.00	SQM		

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK AT DRM RATLAM (M.P)

S.No.	Description of Item	Unit	QTY	RATE	Amount
	<u>DOUBLY CHARGE VITRIFIED TILES FLOORING</u>				
28	Providing and fixing 1st class premium quality, double charged vitrified tiles in floor, skirting of approved size (600mm x 600mm) of make Kajaria, Nitco, Bell, Johnson, Somany etc, or equivalent in first quality conforming to IS:15622 of approved make in all colours shades of any size in floors and skirting over 20 mm thick bed of cement mortar 1:4 and jointing with grey cement slurry @3.3 kg per Sqmt, or fixing the same on existing floor fixed on a screed of approved adhesive viz Carebond or Nitobond or Balendura including pointing in white cement mixed with pigment of matching shade complete.	75	Sqm		
29	Granite Door Frame : Marble Frame :Providing and fixing door frame wide-150 mm (opening size 2.10 m x 0.9 m) made of double layer Baroda green marble frame constructed on the brick work. The exposed edges of granite to be rounded & polished, etc. Necessary holes, etc. to be made for fixing various hardwares, etc.	15	RM		
30	Galvanized iron SHEET FOR SHED Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerincharge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	30	sqm		
31	M.S structure work for Shed & Boundary Gate Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	200	Kgs		
32	M.S. DOOR WITH ANGLE FRAME FOR LOCKER / CASH ROOM Providing and fixing at site m.s. Door with angle frame(35x35x5) including a coat of steel primmer, all materials, contingencies etc complete.	150.00	Kgs		
33	COLLAPSIBLE GATE Providing and fixing in position collapsible steel shutter with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size with top and bottom rails of T-iron 40x40x6mm with 38mm dia, steel pulleys, complete with bolts, nuts, locking arrangements, stoppers handles including painting with two coats of synthetic enamel paint of approved shade over a coat of primer all complete.	6.00	SQM		
34	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x1.25 mm M.S. laths with 1.25 mm thick top cover	3.00	SQM		

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK AT DRM RATLAM (M.P)

S.No.	Description of Item	Unit	QTY	RATE	Amount
	Painting Works :				
	Rates to include cost of all materials, labour, curing, tools & machinery, transportation, scaffolding, ladders and all incidental and operational charges, at all heights, etc., complete and as directed by SBI. All glasses, surfaces to be cleaned of the paint marks/drops due to work/splashes.				
35	Plastic Emulsion Paint :				
	Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/distemper/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing and applying Birla putty nor equivalent. The surface shall then be allowed to dry for atleast 24 hours. It shall be then sand papered to give a smooth & even surface. Holes shall be filled with BIRLA putty, made with plaster of paris. Then first coat of primer to be applied. After this necessary leveling shall be done with putty and second primer coat shall be applied. The plastic emulsion paint of approved shade and make shall be applied in minimum 2 coats (finishing paint) including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete as per the instructions of the Bank / SBI.	Sqm	60		
36	synthetic enamel paint				
	Two coats of approved shade synthetic enamel including one base coat of steel/ wooden primer over the existing wooden/ steel surfaces, with brush after cleaning & scrapping by wire brushing.	Sqm	7		
37	TOILET WORK				
A	Providing & laying VITRIFIED wall tiles for dado in pantry area and on walls in toilets as per specifications of size 600mm X 600mm of make Kajaria, Nitco, Bell, Johnson, Somany etc, or equivalent in first quality of design, colour and make as per approval laid and border in special/dark colours as per approval laid over fresh or existing cement plaster including surface preparation if required to the architects satisfaction, joints to be filled and finished neat with cement grout as per specifications including cutting at traps, mitring of joints if required cleaning applying acid wash curing etc. complete at all levels.	30	SQM		
B	EUROPEAN W.C WITH 10L WATER TANK FOR TOILETS				
	Providing and fixing at site European WC with 10 LTR Water tank of Hindware, Parry / Kohlar, jacuar make, including all the necessary work to water tank, including flushing buttons, all materials, labour necessary accessories etc complete.	2	Nos		
c	WASH BASIN under counter type				
	Providing & Fixing at site Under Table Counter type Wash basin of oval or approved shape size, to be fixed in Black coloured Granite Platform with push button type Long body Bib cocks off Parko, Plumber, Jacquar make including CP heavy duty fittings all accessories such as PVC connection, Angle cock all materials, labour, 'materials, etc complete Excluding cost of Black granite counter top to be paid seperatly.	2	Nos.		
d	URINAL				
	Providing and fixing in position first quality white Jaguar make Push Valve type Urinal (cat. no.URS-WHT-13257,UPS-WHT-13253N) as per approval and making all connections of urinal with other accessories such as flush pipe ,outlet, etc. filling including making chases and holes in floors and walls and repairing the same with cement mortar (1:3) plastering etc. to original condition and painting of fittings etc. complete	2	Nos.		
e	NAHANI TRAP				
	Providing and fixing at site 100mm inlet/75mm outlet nahani trap heavy duty PVC of standard make including stainless steel jali, including all materials, labour etc complete.	4	Nos		

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK AT DRM RATLAM (M.P)

S.No.	Description of Item	Unit	QTY	RATE	Amount
f	Providing & Fixing CP finish Two Way Bib cock with wall flange Jaquar make (Cat. No. FLR 5041N), Plumber or equivalent along with Hand Shower (Health Faucet) (ABS Chrome Plated) with 8mm dia and 1 M long Flexible tube and wall hook (Cat. No. ALD 573) or equivalent upon approval make and design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc.complete	2	Nos.		
g	Providing and fixing in position BIB COCK, Angular Stop Cock with Wall Flange Jaquar make (Cat. No. FLR 5053N), Plumber or equivalent upon approval complete including all required connections and settings for proper functioning to the Engineer's satisfaction.	8	Nos.		
h	TOWEL RING				
	Providing and fixing at site heavy duty Jacquar make towel ring Stainless Steel heavy duty to be fixed at site with metallic Anchor fasteners etc complete.	2	Nos		
	CPVC PIPE				
l	Providing and fixing in position 15mm Class 'B' CPVC pipe of approved ISI branded complete with fittings Tees, Bends etc, except controls such as cocks and valves fitted and fixed to the walls with G.I. Approved clamps or buried underground including making necessary chases and holes in walls and floors or trenching etc. complete with making good or refilling including painting of pipes if required. Makes: Prince, Supreme, Astral	20	M		
j	Providing and fixing in position 20mm Class 'B' CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, except controls such as cocks and valves fitted and fixed to the walls with G.I. Approved clamps or buried under ground including making necessary chases and holes in walls and floors or trenching etc. complete with making good or refilling including painting of pipes if required Makes: Prince, Supreme, Astral	25	M		
k	75 MM PVC PIPE				
	Providing & Fixing at site 75 mm PVC waste/soil pipe of Kissan or equivalent make including all bends, Tees, and necessary accessories to be fixed at site in toilets including all materials, fittings such as TEE, Bends, inspection tees, necessary clamp, fixing the pipes with adhesive cement inclusive labour etc complete. The cost shall include making of necessary connections to existing Manholes, including all labour, materials, etc complete.	15	M		
l	100 MM PVC PIPE				
	Providing & Fixing at site 100mm PVC waste/soil pipe of Kissan or equivalent make including all bends, Tees, and necessary accessories to be fixed at site in toilets including all materials, fittings such as TEE, Bends, inspection tees, necessary clamp, fixing the pipes with adhesive cement inclusive labour etc complete. The cost shall include making of necessary connections to existing Manholes, including all labour, materials, etc complete.	20	M		
m	MIRROR				
	Providing and fixing at site 5.0mm designer mirror to be fixed at site with 12.0mm HDMR Board backing and to 25 x 50mm teak wood frame duly painted to match the tile color including all materials, labour etc complete. Mirror size 750 x 600mm	2	Nos		

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK AT DRM RATLAM (M.P)

S.No.	Description of Item	Unit	QTY	RATE	Amount
38	Granite Works : Providing & constructing Zade Black Granite platform for wash basin counters complete as per specifications with 18-24 mm kota stone stand and kota stone or MS angle/T section supports as required and as instructed, including base stone in kota stone and fixing of 15-18 mm thick mirror polished, machine cut jet black granite with simple full round edge moulding and facia for pantry counter and double thick edges with full round moulded edges and of required size. The granite full round moulding shall be fixed with araldite adhesive to the counter top. The cost shall be inclusive of cutting for sink, basin, taps etc. as and when required.	2	SQM		
39	Flush Door one side Laminate & one side ACP Sheet for Toilet & UPS Room Providing, making & Fixing of Flush door at site,-: 32 mm thk flush door with teak wood Beading at Edges 1 mm lamination on one sides & 3.0mm ACP Sheet Including all fitting like Mortice lock with 2 nos Handels , S.S. 125Mm Heavy duty Hinges 3 Nos. Door stoppers, 2 Nos Tower Bolts 200mm Note- Including all materials, labour, transport, taxes, delivered and placed in position at site of work.	5	SQM		
TOTAL FOR CIVIL WORK					
C. CHAIRS					
40	High back, revolving chair FOR BM with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved,	Nos.	1		
41	Medium back, revolving executive chair with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved,	Nos.	4		
42	Medium back fixed type chairs with cushioned seat and back and molded PVC hand rest Godrej, S-frame type, as per quality and design approved, Note- Makes viz. Godrej Bravo/Featherite/ Wipro/ make or equivalent as approved for BM.	Nos.	5		
TOTAL AMOUNT FOR CHAIR					