SCHEDULE OF QUANTITIES

ELECTRICAL INSTALLATION WORKS

AT EXISTING PREMISES OF RACPC-1 OFFICE

S.	AT EXISTING PREMISES OF RACPC-		
No.	Description	UOM	Qty.
	LIGHTING DB		
	Supply, installation, testing and commissioning of 8 way PPI DB (Compact) with		
1	Incomer: 63 Amps 4P MCB Outgoing: 3 X 1 No.s 2P 32 Amps 30 ma ELCB for each phase 3 x (8 No.s, 10-16A, SP, MCBs)	No.s	1
	to individual Switch Board circuits, BM, CO Ac's, etc as per Banks requirement.		
	RAW POWER DB		
	Supply, installation, testing and commissioning of 6 way PPI DB (Compact) with		
2	Incomer: 63 Amps 4P MCB Outgoing: 3 X 1 No.s 2P 32 Amps 30 ma ELCB for each phase 3 x (6 No.s, 10-16A, SP, MCBs)	No.s	1
	to individual Switch Board circuits, BM, CO Ac's, etc as per Banks requirement. UPS DISTRIBUTION BOARDs		
	Supply, installation, testing and commissioning of 12 way double door		
	SPN DB with		
3	Incomer: 40 Amps, 2P, MCB Outgoing: 8 No.s 10-16 Amps, SP, MCB's	No.s	2
	to individual Switch Board circuits		
	AC POINTS		
4	Supply, installation, testing and commissioning of 25A industrial plug socket in metal clad without MCB	No.s	2
	MCB:		
5	Supply & fixing of 32 Amps 2P MCB in suitable metallic box preferably 4P enclosure (for Local control of Banking Hall ACs)	Nos.	8
6	Supply & fixing of 32 Amps 2P ELCB in existing suitable metallic box (for Local control of Banking Hall AC)		8
7	Supply & fixing of 32 Amps 4P MCB in suitable metallic box preferable 4P enclosure (for Local control of Banking Hall ACs)		4
	CABLE LAYING AND TERMINATIONS :		
8	Supply & Laying of following 1100V grade armored cable having sector / circular shaped aluminum conductor XLPE insulated cores, laid up, PVC tape wrapped inner sheathed, GI strip / wire armored and overall extruded PVC sheathed confirming to IS: 7098, laid along with 2 Runs of 8SWG GI Wire on wall or ceiling using GI clamps and spacers as per route shown at site and further as directed by Bank / Architect.		
а	3.5 x 95 sq.mm AYFY Cable	Mtr.	0

b	3.5 x 70 sq.mm AYFY Cable	Mtr.	0
C	3.5 x 50 sq.mm AYFY Cable	Mtr.	0
d	4 x 35 sq.mm AYFY Cable	Mtr.	0
e	4 x 25 sq.mm AYFY Cable	Mtr.	112
f	4 x 16 sq.mm AYFY Cable	Mtr.	162
	End termination of the following size of cables using flange type cable		
9	glands and heavy duty tinned aluminium crimping type cable sockets		
	including gland earthing.		
a	3.5 x 95 sq.mm AYFY Cable	Nos.	0
b	3.5 x 70 sq.mm AYFY Cable	Nos.	0
C	3.5 x 50 sq.mm AYFY Cable	Nos.	0
d	4 x 35 sq.mm AYFY Cable	Nos.	0
e	4 x 25 sq.mm AYFY Cable	Nos.	4
f	4 x 16 sq.mm AYFY Cable	Nos.	6
	WIRING		
	Circuit / Sub circuit Wiring:		
	Supply and wiring wall / floor etc. / recessed / surface as per colour code with the following size PVC Insulated copper wire along with		
40	· · · · · · · · · · · · · · · · · · ·		
10	given earth wire for phase neutral and earth conductor with standard colour coding, through ISI marked rigid PVC conduit.		
	colour county, through ist marked rigid FVC conduit.		
а	3 runs x 6 sq.mm PVC Copper wire in 2 mm thk, 25 mm dia conduit	Mtr.	144
<u> </u>	(for UPS COS to UPS DBs)		
	DESK/ WORK STATION WIRING		
	Wiring in PVC conduit of IS specification of proper size with 3 nos 2.5		
	sq.mm single core PVC insulated stranded copper wire 1.1KV grade		
	and with all material supply installation and commissioning complete		
	from UPS DB/ LDB(Raw) .The wiring shall be carried out on surface		
	above false ceiling and concealed in the wall by chiseling the existing surface and plastering the same with cement etc. after fixing the pvc		
	conduit with all accessories like saddles screws, bends T-joint etc. 2		
11	coats of painting Matching to the surface including supply installing,		
11	testing, commissioning of modular plate type switch and socket for		
	computer terminal on sheet steel enclosure (cadmium plated),duly		
	fitted with screw to the steel conduit and fixed to the wall partition		
	furniture with all interconnection and proper earthing .All the opening		
	shall be covered with blank plate and be sealed to make the box		
	vermin proof.		
	UPS Primary point for SWC & branch Manager table: 3 no. 6A		
_	sockets fixed below the table, to be controlled by one no. 16 A	0-1	20
а	modular switch above the table / counter. The boxes are to be fixed	Set	36
	on the partitions by suitably chiseling / cutting, making good the damage.		
	UPS Secondary point (Looping from above primary point) for SWC		
	& branch Manager table: 3 no. 6A sockets fixed below the table, to		
	be controlled by one no. 16 A modular switch above the table /		
b	counter . The boxes are to be fixed on the partitions by suitably	Set	18
	chiseling / cutting, making good the damage.		

С	UPS Point for Network/ LAN switch in branch Manager room with 4 no. 6A sockets to be controlled by one no. 16 A modular switch as per site requirement. The boxes are to be fixed on the partitions by suitably chiseling / cutting, making good the damage.	Set	5
12	Wiring in PVC conduit of IS specification of proper size with 3nos 2.5sq.mm single core PVC insulated stranded copper wire 1.1KV grade and with all material supply installation and commissioning complete from UPS DB/ LDB (Raw) .The wiring shall be carried out on surface above false ceiling and concealed in the wall by chiseling the existing surface and plastering the same with cement etc. after fixing the pvc conduit with all accessories like saddles screws, bends T-joint etc. 2 coats of painting Matching to the surface including supply installing, testing, commissioning of modular plate type switch and socket for computer terminal on sheet steel enclosure (cadmium plated),duly fitted with screw to the steel conduit and fixed to the wall partition furniture with all interconnection and proper earthing .All the opening shall be covered with blank plate and be sealed to make the box vermin proof.		
а	Raw power point for SWC and other work stations: 3 no. 6A sockets fixed above the table to be controlled by one no. 16 A modular switch above the table / counter. The boxes are to be fixed on the partitions by suitably chiseling / cutting, making good the damage.		32
b	Raw Power Secondary point (Looping from above primary point) for SWC & branch Manager table: 3 no. 6A sockets fixed above the table, to be controlled by one no. 16 A modular switch above the table / counter. The boxes are to be fixed on the partitions by suitably chiseling / cutting, making good the damage.	Set	24
С	Raw power point: 1 no. 6 / 16 A controlled by 16 A switch. The boxes are to be fixed on the partitions by suitably chiseling / cutting, making good the damage.	Set	9
13	Wiring for light/ fan/ exhaust fan points using 3 X 1.5 sqmm 1.1 kV grade PVC insulated stranded copper conductor wire for phase, neutral and earth in 25 mm dia heavy duty PVC conduit along with associated accessories like MS junction boxes, bends, saddles, screws etc. concealed in wall, floor, under flooring, below false ceiling or on surface as well as suspended from ceiling with 25mm X 3 mm MS flat suspenders duly painted above false ceiling from individual light/ Fan/ Exhaust Fan point outlet etc. to individual modular type switch boards, 6 Amp modular plate type switches etc., as required complete including circuit wiring with 3 X 2.5 sqmm. 1.1 kV grade PVC insulated stranded copper conductor wire and mending good to damage and as per site requirement and as instructed by engineer. All the opening shall be covered with blank plate and be sealed to make the box vermin proof.		
a	2 no. of lights controlled by one switch	Set	54.00
	1 no. of lights by one switch.	Set	5-1.00

С	Wall bracket fans / exhaust fan controlled by 6A switch at switch board and 1 no. 6 A socket in MS box at ceiling level.	Set	21.00
d	Ceiling fans with electronic regulators	Set	27.00
е	6 A plug socket controlled by 6 A switch on the same switch board.	Set	27.00
14	Supply, installation, testing and commissioning of 1.1 kV grade 3 core 2.5 sq. mm flexible copper cable 3 meter length connected at one end with 15 A three pin socket and other end connected permanently to the switch board of safe room / locker room	Set	2
15	AC Point: Supply all materials and wiring through wall floor etc, concealed as per colour code with following rating P V C insulated stranded copper wire in 2mm thk PVC pipe upto end terminations (DB to AC Terminal point). Note: Any Local/ remote control accessories between the circuit shall be omitted for measurement.		
а	3 x 4.0 sq mm (1-phase)	No's	8
b	5 x 4.0 sq.mm (3-phase) TELEPHONE	No's	4
16	Supplying and laying of 2 pair 0.5mm dia telephone cable of tinned copper conductor in PVC conduit of suitable size from crone to each telephone socket and RJ – 11 telephone sockets with suitable mounting box of modular type, including all inter connections as required and directed.		47
17	Supply, installation, testing and commissioning of 30 pair krone connector in a suitable box as required and directed.	No.s	2
18	Supply and laying of ISI marked 25mm dia medium grade PVC conduit concealed/ flushed in wooden partition or wall for data cabling with fish wire and from Work station upto false ceiling level as directed by Banks Engineer.	RM	210
	LIĞHTS & FIXTURES		
19	Supply, installation, testing and commissioning of Recess mounted lumanaire of 2' X 2' flat type modular 36W LED light fixture complete with electronic driver, wiring, heat sink, opal acrylic diffuser etc. suitable for gyp board or metric false ceiling. The fixture shall be provided with atleast three nos. 20mm dia knock out holes on the top side for fixing down rods and wiring purpose.	Nos.	21
20	Supply, installation, testing and commissioning of Recessed decorative LED down lighter of 15W complete with electronic driver, wiring, heat sink, opal acrylic diffuser etc. suitable for gyp board or metric false ceiling.		33
21	Supply, installation, testing and commissioning of 18 W - 22W LED batten (4 ft. length) along with all other connections & accessories rerquired.	No.s	15
22	Supply, installation, testing and commissioning of 9W - 10W LED batten (2 ft) suitable for indoor application.	No.s	7
23	Supply, installation, testing and commissioning of Exhaust fan 300 mm sweep and metal body of Crompton / Bajaj /Usha / Havell's make	No.s	3

24	Supply, installation, testing and commissioning of Ceiling fans of 1200 mm sweep Crompton/ Bajaj/ Usha/ Havell's make	No.s	24
25	Supply, installation, testing and commissioning of Metal body Wall bracket fan 400 mm Crompton/Bajaj/Usha/Havell's make	No.s	21
26	Supply and Installation of 200 mm sweep Portable Table Top fans. (Crompton Greaves / Usha / Havells)	Nos.	30
27	Supply, installation, testing and commissioning of battery operated Call buzzer for Branch Manager chamber along with battery set.	Set	1.00
	MISCELLENEOUS		
28	Marking of Panels, DBs, its switch and fuse ratings, cable size, location etc on DBs, for EB (Red), UPS (Blue) distribution boxes, Switch/Socket Boards etc. with radium sticker / stencil with permanent marker / painting only.	Lot	1
29	Charges for preparation of single line diagram of the whole electrical installation using AutoCAD, lamination and displaying it inside the UPS room.	Lot	1
30	Supply and providing of 1mtr. x 2mtr. size (Approx.) x 2.5-3mm thick electrical grade minimum class B rubber insulation mat in Electrical / UPS Room.	Nos.	1
31	Supplying and fixing of Electric shock treatment chart in Trilingual (Telugu, Hindi and English) of minimum 50cm X 70cm size with water proof laminate and adequate frame including wall fixing arrangements in Electrical/ UPS room.	Nos.	1
32	Removing and Refixixng of Old and existing all type of LED Light fittings including fixtures like exhaust fans, distribution switchgears, control MCBs etc. as per layout plan or Engineer-in-charge instructions.	lot	1
33	Removing of old electrical and Telephone wiring including arranging temporary power connection for work stations in order to continue office functioning as advised by Bank official.	lot	1
	GRAND TOTAL:		

Note:

- 1. GST as applicable shall be paid extra.
- 2. All materials shall be selected by the SBI officials or Engineer-in-charge before execution.
- 3. All the quantities are approx and executed as per site requirement.
- 4. The Bank reserves the right to select any of the brands indicated in the "List of Approvincase of delay in delivery of ordered 'make of item'.
- 5.The contractor cannot claim anything extra if the Bank changes the make but within approved make.
- 6. Bidder shall visit/ inspect the site before quote.

Rate (Rs.)	Amount (Rs.)
	0.00
	0.00
	0.00
	0.00
	0.00
	0.00
	0.00
	0.00
	0.00
	0.00

0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00

0.00 0.00 0.00	
0.00	0.00
0.00	
0.00	
0.00	
0.00	0.00
	0.00
0.00	0.00
0.00 0.00	
0.00 0.00	
0.00	
0.00	
0.00	0.00
	0.00

0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00

0.00
0.00
0.00
0.00
0.00
 0.00
0.00
0.00
0.00
0.00
0.00

'ed Makes"

the list of