

**TENDER & SPECIFICATIONS FOR CONSTRUCTION AND REPAIR WORK OF BROKEN BOUNDARY
WALL AT MAIN BRANCH GPO INDORE**

S. NO	ITEM	QTY	unit	rates	Amount
1	Excavation in Black cotton soil/ hard moorum/ copra including throwing of excavated materials, to nearby site including transportation etc complete	113	Cum		
2	PCC 1:4:8 as base concrtere including curing etc complete.	9.5	Cum		
3	Modular concrete block of size 200X200X400	94.5	Cum		
4	pointing work on on external & internal surface of Boundary wall in 1:4 cement mortar, including all materials, labour etc complete.	252	sqm		
5	75mm PCC 1:2:4 work over the boundary wall to be laid with minimal reinforcement above the exsting boundary wall including all materials, labour etc complete.	3.2	Cum		
6	MS angle framed railing as per the existing pattern to be fixed at site over the Stone wall including two coats of steel priemer and two coats of Paint, including all contingencies etc complete.railing size 2.4 x 1.0 m = 125 Nos	4750	Kgs		
7	Grounting of existing Grill to the base of Stome masonry with help of concrete block 1:2:4 of approx size 200 x 200x 200mm including laying and fixing of Grill etc complete	1	Cum		
8	Painting of external exterior emulsion over the new Boundary wall on both the side including all labour, materials, etc complete.	500	sqm		
9	Painting of external exterior emulsion over the old Boundary wall on both the side including all labour, materials, etc complete.	600	sqm		
	GRAND TOTAL				