

BOQ FOR REPAIRING OF EXTERNAL DRAIN AND ROAD DEVELOPMENT WORK					
AT HAMREN BRANCH AND STAFF QUARTER					
Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
1	Repairing of Quarter outside Plinth protection surface by applying cement mortar 1:4 and neat cement smooth finish of top after P.C.C work (1:3:6) on the surface . The rate shall includes demolishing of existing P.C.C work /preparaton of surface by proper comapaction manually and removing of debris and dumping at location as specified by the local authorities.The rate shall also includes curing work etc	sqm	402		
2	Construction and repairing of external drain in the periphery of quarter with P.C.C (1:3:6)at drain bottom with neat cement plaster (15 mm thick) finished at inner and outer sides with necessary brick masonry work of (10" thickness) wherever required.The rate shall also included the demolishing work wherever required and preparation of surface by proper compaction manually before carrying out the P.C.C work complete in all respect.	RM	466		
3	1st class brick work in steps in cement mortar 1:4 including racking out joints and curing complete as directed in super structure above plinth up to 1st floor level , including necessary earth cutting etc complete (A) 112mm thick brick wall (a) In cement mortar in proportion 1:4. (1 cement:4 sand)	Cum	12		
4	Repairing of Open drain in the peripheri of colony road with P.C.C (1:3:6)at drain bottom with neat cement plaster finish of both sides, with necessary brick massonry work (masonry work rate are separate), where ever required as directed	RM	130		
TOTAL					

Rates are exclusive of GST