

PRICE BID FOR INTERIOR WORKS FOR PROPOSED DOCTOR'S ROOM AND PHARMACY IN SECOND FLOOR, SANGAMAM BUILDING, AO TVM.

Sl No.	Description of work	Quantity	Unit	Rate	Amount
1	Custom Made Full Height Solid Partition:Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beadings. Measurement for the partition area shall be considered from floor level to false ceiling level only.	18	Sq.M		
2	Full height partly solid and partly Glazed partition :- Providing and fixing in position partly panelled and partly glazed partition as per specification in item no.(8) above but with 8 mm thick float glass with etching between 900 mm and 2100 mm level between the solid partition as per size required at site fixed with necessary SS D brackets. The edges of partition is to be finished with 1 mm thick laminate. Measurement for the partition area shall be consider from the floor level to false ceiling level only.	9	Sq.M		
3	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	8	Sq.M		

4	<p>Gypsum Board False Ceiling :- Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete. Rate to include closing of all wall openings with masonry or plywood, above the false ceiling level, as per Engineer's instructions.</p>	29	Sq.M		
5	<p>Providing and fixing Officer's table of size 1500 x 750 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip.12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete.</p>	2	No.		
6	<p>Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 100 x 45 cm as per specification in item no.12 above.</p>	1	Nos.		

7	Low Level Storage :- Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm, 750 mm high behind tables and till false ceiling height for full height storage with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exp[osed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	3	Sq.M		
8	Full height Storage with sliding laminated/glazed door :- Providing and fixing storage to detail as shown in the drg. Size about 450mm wide, till false ceiling height for full height storage with sliding glazed shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exposed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	9	Sq.M		
9	Dismantling existing partitions, tables and cement board partition etc as per requirement as per approved layout, stacking the usable items etc, as directed and disposal of debris away from site.	1	LS		
10	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface.	183	Sq.M		
11	Fire Rated Cement Board Partition:-				
	The partitions are of double skin type. The partition should be firmly fixed on floor/ counter/ wall made out of GI rectangular section of 44.5x83.5x2.5 mm thick of internal frame structure placed horizontally & vertically in 60x60 cm interval as shown in the drawing which is covered with 6 mm thick fire rated cement board on both sides finished with 2 coat putty and 2 coats of plastic emulsion paint with roller brush of approved colour to match the interior over the approved primer.	35	Sqm		

12	Supplying and fixing wash basin (parryware or equivalent make, basic price of wash basin Rs. 3500/No) rates including cost of pillar cock quarter turn, bottle trap are of cabtree or jaguar, waste coupling, waste pipe, angle cock with all necessary fittings etc. complete. The cost of required length of water supply pipe and waste water pipe to be included in the rate itself.	1	Nos		
	TOTAL				
	GST @ 18%				
	GRAND TOTAL				