Sr.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT		
No.	NOTE: ALL CHARIS OR CHASES IN WALLS / COLUMNS / SLABS MADE BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION OF CONDUITS / S.B. / BOXES ETC. THE FILLING OF THE SAME IS IN THE SCOPE OF THE ELECTRICAL CONTRACTOR INCLUDING ALL NECESSITY MATERIAL AND LABOUR.						
	PART - A :::: BRANCH						
A	INTERNAL WIRING: Phase wire must be Red colour for LDB, Yellow colour for PDB & Blue for ACDB, Neutral Wire of Black colour & Green Wire for Earthing. Color code must be maintained. Tagging from DB MCB and Switch board must be done.						
1	SITC of point wiring in concealed in walls, furniture's & for above false ceiling, or on ceiling, on beams shall be fixed with saddles & spacers etc., with conduits taken in slab with 20 mm dia PVC Rigid conduits 1.5 mm thick ISI mark with 2 nos. of 1.5 sq. mm. phase & nutral & 1 nos. of 1.0 sq. mm. earthing with modular switch with company made flush metal box/surface PVC box etc. comp. with nec. main lines for switch board from LDB of mains of 2 nos. of 2.5 sq.mm wire and 1 no.of 1.0 sqmm pvc Insulated copper conductor wire FRLS type laying in with 20 mm/25 mm dia PVC rigid conduits 1.5 mm thick ISI mark .These will be used with point wiring of light, fan, ex. fan, callbell points, etc { Max. 3 Switchboards in one circuit - One Sp MCB }.Phase wire must be Red colour, Nutral Wire must be Black color & Green Wire for Earthing. Color code must be maintained. Tagging from Lighting DB MCB and Switch board must be done.						
1.1	One 5A switch controling one light / fan point.	3	nos				
1.2	One switch controlling Two light points .	2	nos				
1.3	5A socket outlet with 5A switch (on common board) (1 FOR WATER COOLER).	2	nos				
1.4	5A socket outlet with 5A SP switch (as an independent point) [for ex. Fan, wall fan , QMS, Token M/C Display, etc. points.]	2	nos				
2	SITC of 20 A/ 25 A, 230 V, with DP ELCB, 100 mA all enclosed in a prefabricated MS boxes complete to the satisfaction of E.I.C. For SPLIT AC 1.5TR / 2.0 TR unit with necessory require wiring from ACDB of 2 no of 4.0 sqmm wires and 1 no of 2.5 sqmm PVC Insulated copper conductor wire FRLS type laying in with 20 mm/25 mm dia PVC rigid conduits 1.5 mm thick ISI mark. These will be used with point wiring of A.C. points ,etc . Server Room AC Supply need to be given through Main Panel. Color code must be maintained. Tagging from DP MCB and AC point must be done. This point should be installed near Split / window AC in concealed manner. No Looping of Neutral or earthing is allowed. Each point needs to provide seperate circuit. For Cassate AC power supply indoor or outdoor need to be given as per AC vendor's requirement. The height of switchboard must be at reachable point for easily operation.from that point to Split AC,empty conduit + necessary bends must in concealed mode by ele. contractor. THE ENCLOS	6	nos				
В	LIGHTING FIXTURES: (NOTE: ANY OF FIXTURES AND FITINGS SHALL BE RE-CONFIRMED WITH THE ARCHITECTS / CONSULANTS BEFOTE ORDERING THEM.						

Sr. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
3	SITC of (including supply and fixing flexible wires from holder to fixtures hardwares etc.) of The LED lamps should be of same make as fixture make The marking & cutting of fixtures should be in ele. contractor's scope fixtures should be approved by bank's ele. engineer / ele. consultant / architect. from the given make list before installations. LM 79 & LM 80 test reports to be submited. nichia / LUmileds / cree - LED should be used by manufacture. Lighting Luminaire of LED for Office single piece die cost aluminium M24 housing complete with driver unit, mirror optic and other accessories Lamps of about 100 lumen/W injection moulded PC diffusers with high brightness complete unit complying with international standard (LU49, LH801) - opertive on 190V - 270 V 50 Hz with Mini 3 years warranty complete with mounting stystem and lamp dully wired and tested Details as under.				
3.1	SITC of LED 1 \times 36 W (3100 lumens) (2' X 2') RECESS MOUNTED LUMINAIRE with 2KV surge protection, making earthing conection complete to be recessed in false ceiling with all necessary hardwares, hanging - die cast frame arrangement, chains or hook arrangement with ceiling, connected to supply wire with PVC connector. Earthing connection with lugging need to given to body of Fixture, etc. complete. (Crompton Model ORION II Cat Ref No: LCTLRN-36-FO-CDL, CCT 6000 K and CRI > 80, lumen O/P > 3300 lumen, Syatem wattage (LED + Driver) < 40 Watt. or Equivalent in GE/Philips / Havells / Wipro make) .	17	nos		
3.2	SITC of 1 x 12 W Square / Round LED DOWN LIGHT pressure die cast fixture with 2KV surge protection (950 lumens) to be recessed in false ceiling with all necessary hardwares, chains, hook etc. complete.(CROMPTON make cat no. Crompton Model CROM LCDD-15-CDL/TL/ WW ,CCT 6000 K and CRI > 80,Lumen output1450 lumen, System wattage(LED + Driver) 12 Watt or Equivalent in GE / Philips / Havells / Wipro make). Energy Efficient round recessed mounted LED down lighter with premium white powder coating and die cast aluminium housing. as per details above. Die casting material should not be CRCO type material. should be connected to supply wire with PVC connector. Earthing connection with lugging need to given to body of Fixture.	14	nos		
3.3	SITC of Exhaust fan of 300 mm, fresh air vantilator type complete & 6 Amp. 3 pin TOP. (Crompton/ Khaitan / Havells make) [Wooden mounting frame should be fixed in coordination with carpenter - furniture contractor.] - Two Ex. Fan are of heavy duty industrial type for Ups room.	1	nos		
3.4	SITC of 48" Ceiling Fan with fan step socket modular regulator, Max. 3 feet Fan Rode, Anchor Fastner, etc. (WHITE COLOUR - BEE 5 star labeled ceiling fan Alluminium body and copper winding.) (Orient PSPO or Equivalent approved make in Crompton / Havells Model High Breeze Plus BEE 5 Star labeled ceiling fan , Aluminium body , copper winding .).		nos		
3.5	SITC of 1 x 18W led batten light fixture (T-5) with electronic driver and tube complete with necessory hardwares, etc and per watt lumens output must be above 120/watt and 90%lumems maintaiance for 90% of life with input voltage 90-270v ac 50hz operational without affecting the life, input mov.gtd protection in driver for above 270v protection. and 2 years waranty.LED Batten Comprises of Thermally conductive material. Pre-wired with high efficiency electronic driver. High translucent frosted diffuser gets glare free, smooth light distribution. (Cormpton / GE/ Philips / Havells / Wipro make).		nos		
С	COMPUTER POWER SUPPLY & NETWORKING - TELE. SYSTEM.: Phase wire must be Yellow colour for UPS O/P DB, Red colour for PDB, Neutral Wire of Black colour & Green Wire for Earthing. Color code must be maintained. Tagging from DB MCB and Switch board must be done.				

Sr. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
4	SITC of 2 nos. of 6 A, 5 pin Sockets and 1 no. of 6 \ 16 A socket below table outlets with one 16 A switche with indicator Computer power supply with concealed company made metallic boxes or PVC flush box on walls / furniture's / trunking etc complete all respect with necessory wiring of mains of 2 no of 2.5 sq mm and 1 no of 1.5 sqmm pvc insulated copper conductor multi-stranded flexible wire with 20/25 dia. PVC conduits with accessories duly burried under floor with necessary chasing / breaking in floor and to be refinished with all necessary civil material etc. complete from UPSDB to Computer power supply boards.{Maxi. 3 computers in one circuit}. complete with necessary termination etc. complete.[White Colour Outer Plate For These Switchboards]. LOOP POINTS MUST BE OF SAME SIZED WIRES. Phase wire must be Red colour, Nutral Wire must be Black color & Green Wire for Earthing. Color code must be maintained. Tagging from UPS O/P DB MCB and Switch board must be done.	17	nos		
5	SITC of 2 nos. of 6 A, 5 pin Sockets and 1 no. of with one 6 A switches raw power supply with concealed company made metallic boxes or PVC flush box on walls / furniture's / trunking etc complete all respect with necessory wiring of mains of 2 no of 2.5 sq mm and 1 no of 1.5 sqmm pvc insulated copper conductor multi-stranded flexible wire with 20/25 dia. PVC conduits with accessories duly burried under floor with necessary chasing / breaking in floor and to be refinished with all necessary civil material etc. complete from PDB to Computer power supply boards.{Maxi. 3 Raw Power Points in one circuit}. complete with necessary termination etc. complete [Black Colour Outer Plate For These Switchboards].LOOP POINTS MUST BE OF SAME SIZED WIRES. Phase wire must be Red colour, Nutral Wire must be Black color & Green Wire for Earthing. Color code must be maintained. Tagging from PDB MCB and Switch board must be done.	13	nos		
6	SITC of CAT 6, RJ 45 information outlet (I/O) of D-link mke with front modular cover plate, flush box metallic or PVC for trucking system etc. complete with terminations etc complete.with Providing, installing, testing, commissioning of CAT 6 UTP pvc insulated copper conductor data cable of D-link make with 20/25 dia. PVC conduits with accessories duly burried under floor with necessary chasing / breaking in floor and to be refinished with all necessary civil material etc. or to be cleated on wall / ceiling with saddles / spacer etc. necessary termination etc. with ferrule numbering at both ends of each of piece of cable etc. complete as per the requirement from data rack to I/O points below tables. etc. (One for LCD & Two for ATM & one for IP phone in BM cabin). Dual jack plate will not be allowed. Cross Ferruling need to be provided for each point. on Data point tagging must be done).	17	nos		
8	SITC of 24 port patch panel for computers mounting in metal rack. (make: D Link/Digi Link). (1	nos		
9	Supply & fixing the Patch cord 1 mtr. Long (factory built)When supplying , then first ask to BM / Consultant / Architect / Bank Authority.	17	nos		
10	Supply & fixing the Patch cord 2 mtr. Long (factory built)When supplying , then first ask to BM / Consultant / Architect / Bank Authority.	15	nos		

Sr. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
11	SITC of telephone point with Telephone socket outlets of RJ 11 of aapproved make with company made concealed boxes in walls / furniture's etc. complete with Providing, installing, testing, commissioning of 2 pair of 0.51 cross section pvc insulated copper conductor telephone wire of ITI approved with 20/25 dia. PVC conduits with accessories duly burried under floor with necessary chasing / breaking in floor and to be refinished with all necessary civil material etc. or to be cleated on wall / ceiling with saddles / spacer etc. necessary termination etc. complete.from krone box to tele. RJ - 11 sockets below tables. etc for Intercom / fax / direct Tele. facility. Cross Ferruling need to be provided for each point. on Telephone point tagging must be done.	14	nos		
D	DISTRIBUTION BOARD AND PANELS :				
12	SITC of metallic double door type distribution board with all necessary connection complete to be installed concealed in wall / surface mount complete to the satisfaction of the Engineer in charge. The DB should be of same make as MCB make.				
12.1	6 - WAY TPN DB: (ACDB). All MCB should be ' C ' type.	1	nos		
	incoming : 63 A FP MCB - 1 NO . outgoing : 20 A / 25 A DP MCB (4 nos) for HI- WALL SPLIT AC points. outgoing : 25 A FP ELCB, 100 mA - 2 NO .				
12.2	8 - WAY SPN DB : (ATMDB). All MCB should be ' C ' type.	1	nos		
	incoming: 40 A FP MCB - 1 NO. outgoing: 20 A / 25 A DP MCB (1 nos) for HI- WALL SPLIT AC points. outgoing: 20 A / 25 A DP MCB (1 nos) for UPS I/P MCB. outgoing: 10 to 20 A SP MCB (2 nos).				
12.3	4 WAY SPN DB. (For ATM ups points - UPS O/P DB - in ATM AREA.).	1	nos		
	outgoing: 25 A. DP MCB - 1 NO FOR UPS OUTPUT. outgoing: 10 A / 20 A. SP MCB - 2 Nos.				
12.4		4			
12.4	4 WAY SPN DB. (For essential ups points - UPS O/P DB.) - branch GF AREA. outgoing: 25 A. DP MCB - 1 NO FOR UPS OUTPUT. outgoing: 10 A / 20 A. SP MCB - 2 NO FOR essential ups points - DATA RACK / FIRE PANEL / CCTV NVR PTS.	1	nos		
12.5	4 WAY SPN DB . (For UPS O/P DB -AT UPS ROOM).	1	nos		
	outgoing: 40 A. DP MCB - 1 NO FOR UPS OUTPUT. outgoing: 25 A. DP MCB - 1 NO FOR UPS OUTPUT.				
12.6	4 WAY SPN DB . (For UPS DB of ATM -AT UPS ROOM).	1	nos		
12.0	outgoing: 25 A. DP MCB - 1 NO FOR UPS OUTPUT. outgoing: 25 A. DP MCB - 1 NO FOR UPS OUTPUT.	1	1100		
13	SITC of Main panels as per drawing and specifications. Panel should be dust and vermin proof. Panel shall be fabricated from 14/ 16 SWG CRCA sheet metal duly powder coated of approved paints. Panel should be as per the sepecifications of ERDA/CPRI. fabrication, Switch gear installation. Internal wiring and Test Certificate from Manufacturer to be submitted All MCBs must be C Type Characteristic. Panel Drawing Need to be approved by Electrical Consultanat / Bank's Engineer before starting work. READ SLD CARFULLY.				

Sr. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	Supply, installation, testing & commissioning of ESSENTIAL POWER PANEL as per below configuration.	1	nos		
	Incoming feeder: 80 A FP MCCB ESSENTIAL POWER Panel.				
	* 80 A, FP Change over switch (1 No.)				
	* 100 AMP. 500 Volts, 3 phase 50 Hz FP Alu . bus bars of suitable length -Current ratio				
	shall be 1 sq mm = 1.2 A.				
	* Digital AVF Meter with control fuses. C.T. shall be of 15VA class 1 type and shall be				
	resin cast type.				
	* Phase indicator lamps phase wise.				
	* Outgoing feeder:				
	* Timer of L & T make Cat. No. 67DDTO digicom Timer with 16A. 4P contactor /				
	Theben make Cat no. SUL 180 a - T180 0 001 ANALOG Timer with L & T make				
	contactor MNX 18 (operating coil voltage 230V, 50 Hz). (24 hrs) 1 No for signage				
	light.				
	* 25 A DP MCB (1 no - Sign board for branch).				
	* 63 A FP MCB (1 NO - UPSDB).				
	* 40 A FP MCB (1 NO - ATMDB).				
	* 40 A FP MCB (1 NO - SPARE DB).				
E	EARTHING SYSTEM:				
14	SITC and jointing of following wire / strip / earth cable on walls, ceiling etc. With				
14	necessary non rusting clamps, washers, nuts and bolts etc complete.				
141	8 SWG G.I. Wire with 20 mm dia. PVC rigid conduit duly cleated / concealed / burried	25	Deset		
14.1	in floor etc. complete for ELE. PANEL, ALL DBS, ETC.	25	Rmt		
F	CABLES & CABLE TERMINATIONS:				
	Supply, Laying, installation, testing and commissionig of following sizes of PVC				
	insulated PVC sheathed copper / aluminum conductor armoured cable to be laying in				
	existing cable trench or to be laid in existing pipes of with necessary clamps, spacers				
	with cleating on wall ceilling etc. complete to the satisfaction of EIC. All types of cable				
15	excavation works should be in contractor's scope.(LENTH TO BE VERIFY AT SITE)				
	with end termination of following PVC insulated armoured cables incluming supply				
	and fixing of brass single compression type cable glands and crimping type aluminum				
	/ copper lugs suitable for terminations of armoured cables of following overall				
	diameters, incl tightening of all existing cables with lugs & terminations as per				
	requirement				
	3 C X 4.0 sq. mm flexible Cu. cable with 20 mm/25 mm dia PVC rigid conduits 1.5 mm				
15.1	thick ISI mark . (ATM DB TO UPS DP MCB in UPS room to UPS to UPS DP MCB to	80	mtr		
	UPS O/P DB in ATM DB + UPS O/P DB in UPS room to essential UPS O/P DB of				
	branch .).				
G	MISCELLANEOUS ITEMS :				
	SITC of 24 Hr, 7 days A/C timer with 2 nos of TP power contactor of M.D.S, L & T,				
	SEIMENS, THEBEN (indoasian) Make. All enclosed in sheet steel powder coated				
16.1	enclosure of 200 X 200 mm complete with all necessary termination for e lobby AC	1	nos		
	supply. Here Ready made Cyclic Timer Will not be permited to be installed in E				
	lobby near main DB.				
	-				
	SITC of 24 Hr, 7 days A/C timer with 2 nos of DP power contactor of M.D.S, L & T,				
1	SEIMENS, THEBEN (indoasian) Make. All enclosed in sheet steel powder coated				
16.2	enclosure of 200 X 200 mm complete with all necessary termination for UPS room ex		nos		
	fan supply. Here Ready made Cyclic Timer Will not be permited to be installed in				
	ups room.				

Sr. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT			
17	Providing Necessary plug points & light points for tube lights (including necessry wiring) at various locations as required by various contractors for execution of various works / to run equipments such as drill / cutter etc. during the entire execution process. The accessaories used for this purpose shall be of temp. nature (anchor piano or eq.) & the contractor has to take back the same on completion of the project. The supply for this shall be taken from the temporary connection provided at / from nearby general meter under co.ordintion with the LANDLORD. & also providing temporary power supply for computers and data connection for computers with wiring, switchboard, Comp. I/O Points,etc. for smoothly running of the branch with removing & reshifting of the computers , printers, etc. bank hardware accessories.	1	job					
	TOTAL - PART A :::							
	PART - B :::: BUYBACK		<u> </u>		ļ			
18	BUY BACK: FROM premises - Removal of old wiring under tables (all work stations) only - existing ups wiring, raw power wiring, telephone wirings, LAN wirings with conduits & sb of all ups/ raw power / data / tele. points, old casstte ACDB, atm db, wiring in atm area, (2'x2') fixtures, down lighters shall be removed and shall be purchased by the contractor. (Contractor shall last visit site before quoting and the submit the list of material with quantities which are buying and the quoted rate shall be lump sump basis).	1	Job					
	TOTAL - PART A - PART B (BUYBACK) ::::							
	GRAND TOTAL :::							
1	ALL RATES SHOULD BE INCLUDE OF ALL TAXES EXCLUDING GST WHATEVER IS AP	L PLICA	BLE.					
2	THE CONTRACTOR SHOULD DEPUTE ONE PERSON AT SITE FROM START OF WORK TO FINISH FOR GIVING TEMPORARY CONNECTIONS & ATTENDING PROBLEMS.							
3	THE CONTRACTOR SHOULD WORK ACCORDING TO THE FINAL LAYOUT.							
4	THE CONTRACTOR SHOULD SUBMIT & APPROVE MAKE LIST WITH ARCH./ BANK'S ENG BEFORE WORKING & SUBMIT SIGNED COPY WITH FINAL BILL SUBMISSION.	GINEE	R / ELE	E. CONSU	LTANT			
5	THE CONTRACTOR SHOULD CHECK ELE. APPROVED MAKE LIST BEFORE QUOTE.							
6	THE CONTRACTOR SHOULD SUBMIT TEST CERTIFICATE OF PANEL FROM PANEL BUILD TENDER. BUT THE PANEL SHOULD BE MADE AS PER CPRI TERMS & CONDITIONS & ALS ENGINEER / CONSULTANT. THE CONTRACTOR SHOULD FOLLOW THE GA DRAWING OF TENDER.	O APF	PROVED	BY BAN	K'S ELE.			
7	LOWEST BIDDER SHALL BE DECIDED AFTER DEDUCTING THE BUYBACK VALUE.							
8	THE CONTRACTOR SHOULD SUBMIT BANK GUARANTEE OR WARRANTY OF FIXTURES	- LED	FOR MI	N. 3 YEA	RS.			
9	CONTRACTOR SHOULD BE SUBMITTED THE CERTIFICATE OF WIRES THOSE USED FOR THE BRANCH FROM DULY SIGNED BY COMPANY AUTHORISED PERSON PER PROJECT BASIS.							
10	EARTH RESISTANCE SHOULD BE CHECKED & SUBMITTED THE REPORT WITH DULY SIGNED BY ELE. CONTRACOTR AT THE TIME OF BILL CHECKING.							
11	SINGLE LINE DIAGRAM SHOULD BE SUBMITTED AT BRANCH & ONE COPY SHOULD BE ATTACHED NEAR DB / MAIN PANEL.							
12	SHOCK TREATMENT CHART SHOULD BE PEST NEAR DB / MAIN PANEL. STICKERS SHOULD BE PEST ON DBS / MAIN PANEL.							
13	THE CONTRACTOR'S PRESENCE MUST BE COMPULSORY FOR SHIFTING / INSTALLING OF UPS, DATA RACK, EPABX SYSTEMS MUST HELP TO BANK'S VENDORS LIKE PCS (HARDWARE), UPS, DATACRAFT (PORT SWITCH - SOFTWARE), ETC.							
	I	JPPLY						

Sr. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT		
15	THE RATES QUOTED BY THE CONTRACTOR IN THE COLUMN WHERE QUANTITY & UNIT ARE NOT MENTIONED IN THE TENDER ARE NOT NECESSARY BE ACCEPTED , IF LATER THE SAME ARE TO BE FIXED ON SITE.						
16	THE CONTRACTOR SHOULD BE ADVISED NOT TO LAY ANY CONDUIT / CABLE MAIN LINES THROUGH THE CASH ROOM / LOCKER ROOM / RECORD ROOM FOR SECURITY SAFETY AUDITS.						
17	IF THE CONTRACTOR HAS NOT CARRIED OUT ELECTRICAL WORK AS PER STANDARD S CONTRACTOR IS LIABLE TO REMOVE AND REWORK AS PER STANDARD SPECIFICATION IN CONNECTION WITH CIVIL/ FURNITURE/ AC WORK WILL BE BEAR BY CONTRACTOR DONE REWORK THEN WHATEVER BEEN THE COST FOR REWORK WILL BE DEDUCTED F	N ANE	WHAT ONTRA	EVER TH	IE DAMAGE LL NOT		
18	THE CONTRACTOR SHOULD BE ADVISED TO FIX 2 / 3 INCH SIZE PIES FOR HOLES IN OUBE CREATED THE HOLES IN WALL FOR CABLES / EARTH STRIP LAYING WORKS. FILLED END CAPS OF PIPES.						