

NAME OF WORK : PRICE BID OF FURNISHING WORK OF BRANCH & ATM					
FOR STATE BANK OF INDIA NSM BRANCH AT MANDI DABWALI (HR.).					
PART -A (INTERIOR WORKS)					
S.N	Item of Work	Qty	Unit	Rate	Total Amount
1 (a)	<p>Main Entrance ,BM Chamber & ATM's Doors (Toughened Glass 12.0 mm thk. with etching) Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass (J.K/Modi / Triveni / Saint Gobain,Asahi,Glaverbel make) single leaf /Double leaf glazed Toughened door of size approximately, 4'-0" to 3'-0"X 7'-0" all sides edge grinded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accommodate fitting etc. the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant where ever required and SS cover over patch fittings to accommodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete of Godrej/Ozone/ Dorma / Yale/Hafele or approved equivalent make. the rate shall be include frosted film / logo all inclusive, complete in all respect. (Note: In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of Glazing payable will be below the false ceiling only).</p>	9.29	Sq. Mtrs.		
(b)	<p>12mm clear float toughened Glass partition :- Providing and fixing in position 12mm clear float toughened Glass partition (J.K/Modi / Triveni / Saint Gobain,Asahi,Glaverbel make) with patch fittings for the full height glass partitions as per the direction of the engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughen the same. The cost to include all hardware (PATCH FITTINGS etc) required of Godrej/Ozone/ Dorma / Yale/Hafele or approved equivalent make approved equivalent make viz., single corner patch, top and bottom corner patch etc. or as per the direction of the engineer-in-charge, along with frosted film as per design and drawing. The maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per the site requirement. The rate is for a finished item of work etc., complete as directed.The cost to include the cost of bevelling and smoothening of the exposed edges of the glass.</p>	24.62	Sq. Mtrs.		

2	<p>WALL PANELLING :- Wall paneling to be providing in Banking hall made from aluminum frame work using aluminum sections of 44 mm X 25 mm – 18 gauge section un anodized Aluminum of Jindal/ Indal /Hindalco make work Properly fixed to the Wall or Column with proper Spirit level. Frame work to be covered with 8mm thick Plywood of BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply make and 1 mm Thick laminate as per color scheme of the bank of Greenlam ,Aica , Merrino, Archid make. 35mmX 12mm steam beach Lipping to be provided to all the edges Complete job including melamine polish on edge beading/Cornices etc. and painting of grooves in approved colour. All job to be done as per architects satisfaction/ bank direction .</p> <p>BANKING HALL:- Wall paneling Ht : 4'-6", Centre pillars to be cladded upto ceiling bottom "(i.e. + 9'-0 level)</p> <p>(Note: the area under storage or table, side credenza shall not be counted in wall paneling. only visible area will be payable).</p>	105.94	Sq. Mtr		
3(a)	<p>FULL HEIGHT SOLID PARTITIONS:- Providing and fixing full height partitions of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 44 mm X 44 mm X 16 Gauge. of Jindal/ Indal /Hindalco make The aluminum extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rowel plugs / steel plugs . 8 mm thick Ply of BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply make and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank of Greenlam ,Aica , Merrino, Archid make. doors with lock is to be providing as per drawing and fixed with Steam beach molding duly melamine polished/paint. 35mm X 12mm steam beach Lipping to be provided to all the edges of the door. All wood to be painted in wood preservative. The rate include making provision for electrical conduits and switch boxes. All job to be done as per architects satisfaction/ bank direction . Note: (In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of partition payable will be below the false ceiling only).</p>	35.78	Sq. Mtrs.		

b)	FULL HEIGHT PARTLY GLAZED PARTITIONS:- Providing and fixing full height partitions of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 44 mm X 44 mm X 16 Gauge. of Jindal/ Indal /Hindalco make The aluminum extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rowel plugs / steel plugs . 8 mm thick Ply of BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply make and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank of Greenlam ,Aica , Merrino,Archid, make. Glass (10mm thick) with frosted film as per design and doors with lock is to be providing as per drawing and fixed with Steam beach molding duly melamine polished/paint. 35mm X 12mm steam beach Lipping to be provided to all the edges of the door. All wood to be painted in wood preservative. The rate include making provision for electrical conduits and switch boxes. All job to be done as per architects satisfaction/ bank direction . Note: (In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of partition payable will be below the false ceiling only).	13.94	Sq. Mtrs.		
c)	LOW HT. PARTITION FOR COUNTER SEPARATION:-- Providing and fixing full height partitions of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 44 mm X 44 mm X 16 Gauge. of Jindal/ Indal /Hindalco make The aluminum extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rowel plugs / steel plugs . 8 mm thick Ply of BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply make and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank of Greenlam ,Aica , Merrino,Archid,Amulya make. 12mm thick glass to be provided on the Top of Partition. Teak wood beading 1 1/2 " X 3 1/4" (melamine polished) around partition edges complete in all respects. height : 4'-6"	19.51	Sq. Mtrs.		
d)	12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front & Sides.: Providing and fixing 12 mm thick, clear plain toughened glass (J.K/Modi / Triveni / Saint Gobain,Asahi,Glaverbel make) of fixed in vertical position at counter level & to side partitions with frosted film as per drawing, the counter top glass fixed on both sides to toughened glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded and polished complete in all respects.	7.43	Sq. Mtrs.		
4	Hardware				

a	Providing and fixing of Godrej /Harrison night latches in cash cabin doors as per the directions of the Bank.	1.00	Nos		
b	Providing and fixing of Mortice locks of approved make (Godrej /Ozone/Hettich/ Dorma) in UPS, Record Room, etc. as per the directions of the Bank.	4.00	Nos		
c	Providing and fixing hydraulic door closures Silver colour of approved make(Godrej /Ozone/Hettich/ Dorma) & color.	8.00	Nos		
5	Single Level SWO Counters : Providing and fixing at site SWO counters each upto 4'-6" / 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) century, green, Archid ply make with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. Comm. ply BWR grade IS 303 and finished with 6mm thk. flexi ply as base for acrylic sheet as per design with provision for LED Light in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 finished with laminate on top side with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications. Three drawers with autolocks running on both sides mounting Telescopic (channels) of EBCO make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout of Greenlam ,Aica , Merrino, Archid make. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick commercial ply. Non Visible / Inside surface i.e. inside leg-space of table, inside drawers shall be finished with 0.7mm thick laminated white /off white. All exposed Teakwood edges / teak wood lipping beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest, Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front.	4.15	R. mtr.		
a)	Providing & fixing 12 mm thk. Solid Surfaces white Corian acrylic stone (non-absorbent, non-porous solid surface composite material, belonging to the solid surface category) : Glacier White, Du-pont on counter top & required vertical position made to shaped for Single window Counter at transaction level as per drawings/design with provision for LED Light in bottom and approved colour complete in all respect including fixing, buffing and wastage. Make: LG / Samsung / Gravia / Granimum.	6.50	Sq. mtr.		

b)	<p>Single Level Officer's Counter with 1½" thick post-form factory made Tops: Providing Officer's Counter (Size 5'-0" x 2'-6" x 2'-6")made to shape of 1½" thick post-form factory made Tops & ¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) finished of century, green, Archid ply makewith 1.0mm thick horizontal and 1.0mm thick vertical laminate of specified colour and make. Drawer unit (drawer size: 1'-1" x 1'-6"x6", 3Nos.) is located on one side with proper sliding arrangement and auto lock are provided along with storage unit. The counter will have all necessary hardware, laminate band and teakwood/ partal wood beading 1 ½ " X ½" / moulding. Recessed skirting (¾") finished with 1.0mm thick laminate is present below the counter of Greenlam ,Aica , Merrino,Archid make. In front, apron of ¾" board (laminate finished) is provided. Keyboard drawer. CPU shelf 12" x 18"& footrest 3" x 1 ½" etc. to be provided. Laminate colour combination scheme with beading to be followed.All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish. All work is to be done complete in all respects.</p>	1.52	R.mt rs		
6	<p>Lacquered glass panels on SS Studs: Providing & fixing 6 mm thk. Lacquered glass fixed with SS Studs and dow corning make silicone sealant 896 over frame of 19 mm thick commercial ply fixed against the wall as paneling as per drawing with complete satisfaction of the Architect/Bank's Engineer in charge.(Make: saint Gobain/AIS)</p>	4.65	Sq. mtrs		
7	<p>Low storage unit with ¾" thick post-form factory made Tops Providing storage unit of size 18"x2'-6" & 18" x 3'-6" (W x H) of ¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply makewith 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate of Greenlam ,Aica , Merrino,Archid make having one shelf in center. The storage unit will have all necessary hardware, laminate band and teakwood/ partal wood beading ¾ " X ½"/ moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges (dadgo kabzaa) to be used for fixing storage unit shutters. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish .the work to be done complete in all respects.</p>	23.23	Sq. mtrs		
a)	<p>STORAGE UNDER PANTRY PLATFORM:- Providing storage of size 2'-0" x 2'-9" (WXH) under pantry plateform made with ¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of Greenlam ,Aica , Merrino, Archid make with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate having one shelf in center, rest of the specification as per item no-7.</p>	1.95	Sq. mtrs		

8	OVER HEAD STORAGE:- Providing storage of size 16" x 2'-3" (WXH) of ¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply makewith 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate of Greenlam ,Aica , Merrino,Archid,Amulya make having one shelf in center. Top portion of storage shall be tapered with 3". Cedar wood lipping ¾ " X ½" is provided at edge. Open able shutter with clip hinges (etching colour), ball catchers, multi purpose locks(approved make) are to be provided. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish. All work is done complete in all respects to architects satisfaction & as per colour scheme of bank. The storage unit is properly fixed to wall at+ 5'-9" . concealed tube lights (3 Nos.) to be provided along with electrical wires and connections (Note : Electrical fittings given separately in electrical part)	1.73	Sq. mtrs		
9	Wooden boxing for electrical panel: Providing Cabinet unit of size 18"x8'-6" (W x H) of ¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) with 1.0mm thick horizontal laminate.8mm thick bison panel board back side alongwith wall. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partial wood beading / moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges (dadoo kabzaa) to be used for fixing storage unit shutters. All work to be done complete in all respects	4.64	Sq. mtrs		
10	Full height storage unit : Providing storage unit of size 18"x9'-0" (W x H) of¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply makewith 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate of Greenlam ,Aica , Merrino,Archid,Amulya make having shelves @1'-3" C/C. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partial wood beading / moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges (dadoo kabzaa) to be used for fixing storage unit shutters. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish. All work is done complete in all respects. All work to be done complete in all respects.	37.17	Sq. mtrs		
11	PIN UP BOARD :- Made of 12mm thick soft board covered by 25mm x 25mm teak wood beading painted polished to approved colour and soft board covered with blazer/ fabric cloth of approved colour. Texture and sample approved by architect. Notice Board to be fixed to wall space between storage unit (ground placed) and storage unit (wall hung) in manager's Cabin & on top of writing table & in Banking Hall. (basic rate of fabric shall not be less than Rs.65/- per mtr.)	3.71	Sq. mtrs		
12	FALSE CEILING:-				

a	Providing and fixing Gypsum board false ceiling in levels as per the detailed drawing - made up of G.I. frames as specified by Gypsum India limited and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India LTD. Spacing of intermediate channels shall be at 1200c/c, and ceiling section at 457mm c/c. the work includes finishing of joints, applying primer, two or more coats of plastic emulsion paints (white colour) , making cut-out for light fixtures, etc. providing of perimeter channels / beading etc. complete in all respect. Note: Provision of cove shall be given as mentioned in drawings.	109.67	Sq. mtrs.		
b	Providing and fixing Teak wood Veneer false ceiling in levels as per the detailed drawing - made up of G.I. frames as specified by Gypsum India limited and Frame work to be covered with 4 mm thick Veneer of Timex/Furn&Lam/Green make, over 8mm thick Plywood of BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green make and 1 mm Thick laminate as per color scheme suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India LTD. Spacing of intermediate channels shall be at 1200c/c, and ceiling section at 457mm c/c. 35mmX 12mm steam beach Lipping to be provided to all the edges Complete job including melamine polish on edge beading/Cornices etc. and painting of grooves in approved colour. All job to be done as per architects satisfaction/ bank direction the work includes making cut-out for light fixtures, etc. complete in all respect. Note: Provision of cove shall be given as mentioned in drawings.	47.39	Sq. mtrs		
C	Providing and fixing of false ceilings at all heights of 600 mm x 600 mm x 16 mm ARMSTRONG Mineral Fibre ceiling tiles of type Prima Dune Premier-Beveled Tegular Edge RH-99 laid on 15mm exposed grid system. The suspension system shall be the Armstrong Trulok Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions. The framework comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjusters and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 x 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200m cross tees and making arrangement for light fixtures, etc. complete in all respect.	110.13	Sq. mtr's		

13	<p>Chief Manager's table with 1½" thick post-form factory made Tops :- Providing Table for Chief Manager (Size 7'-6" x 3'-0" x 2'-6") made to shape of 1½" thick post-form factory made Tops & ¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply make with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate of Greenlam, Aica, Merrino, Archid make. 12mm thick bevelled glass (approved make) of same size is placed with edges covered with partial wood beading. Drawer unit (drawer size: 1'-1" x 1'-6" x 6", 3Nos.) is located on one side with proper sliding arrangement and auto lock are provided along with storage unit. The counter will have all necessary hardware, laminate band and teakwood/ partial wood beading 1 ½ " X ½" / moulding. Recessed skirting (¾") finished with 1.0mm thick laminate is present below the counter. In front, apron of ¾" board (laminate finished) is provided. Keyboard drawer. CPU shelf 12" x 18" & footrest 3" x 1 ½" etc. to be provided. Laminate colour combination scheme with beading to be followed. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish. All work is to be done complete in all respects.</p>	1.00	Nos		
14	<p>Officer's table with 1½" thick post-form factory made Tops :- Providing Table for Officer's tables (Size 4'-6" x 2'-6" x 2'-6") rest specification as per Item No-13.</p>	7.00	Nos		
a)	<p>Grahak mitra table with 1½" thick post-form factory made Tops :- Providing Table for Grahak mitra tables (Size 5'-0" x 2'-6" x 2'-6") made to shape with 2'-6" wide having working top at + 2'-6" and 12" wide customer top at + 3'-6" with 1½" thick post-form factory made Tops rest specification as per Item No-13.</p>	1.00	Nos		
15	<p>Side credenza with ¾" thick post-form factory made Tops :- Providing and placing side rack (Size 3'-6" x 2'-3" x 1'-4") made of ¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply make with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate of Greenlam, Aica, Merrino, Archid, Amulya make. 4 Drawers (Size 1'-1" x 1'-3" x 4") of ¾" board are placed below. Remaining portion has 2 shutters with 1 shelf. Laminated colour combination scheme to be followed. All necessary hardware eg hinges, screws, multipurpose locks, stoppers, drawer slides, ball catchers to be provided along with teakwood / partial wood beading/ moulding. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish. All works to be done complete in all respects.</p>	8.00	Nos		

16	Writing desk / Customer Voucher Stand / Forms Stand including Cheque Drop & Suggestion Box with 1½" thick post-form factory made Tops :- Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of 2 Nos Cheque Drop & 1 no Suggestion Box made of 19 mm thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish & to be fixed on the wall cost of spacers etc. all inclusive complete.	1.00	No		
a)	Writing desk / Customer Voucher Stand / Forms Stand in ATM including Cheque Drop & Suggestion Box with 1½" thick post-form factory made Tops :- Providing and fixing forms stand of size 3'-0" X 1'-6" X 3'-9" with 3nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer, rest specification as per Item No-16.	1.00	No		
17	SIDE TABLE :- Providing and placing side table of size 2'-0" x 2'-0" x 1'-6" made with 2" x 2" teakwood frame melamine polished with decorative 2 ½" x 1 ½" beading along with 12mm thick Glass on the top. All inside surfaces are painted with 2 coats of synthetic enamel paint over coat of wood primer. All work is done complete in all respects to architects / bank managements satisfactory .	10.00	Nos		
18	Providing and fixing white board of size 3'-0"x3'-0" in CM's chamber clamping on the wall complete in all respect as per directions of the bank/Architect.	1.00	No		
19	Duco Painted HDF Decorative Jali with frame:- Making and fixing in position(As per Approved Sample) Laser cut jali to be made out of HDF(Interior Grade) board of 8MM Thickness with Acrylic frosted sheet and making provision of LED Strip light, fixed inside boxing frame of 6" x6" made of 19 mm thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated)All exposed surfaces to finish with clear gloss duco paint as per approved shade.All work is done complete in all respects to architects / bank managements	3.72	Sq. mtrs.		

20	<p>Dismantling of existing door with frame and Providing and fixing Fire Resistant Door -Fire rated steel door including frame Hrs Metal test certificate will be provided issued from GQMC. (Kutty flush doors & furniture co. Pvt Ltd.paonta sahib, distt. Sirmour,H.P. & GMT, Baddi)</p> <p>Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fasteners).</p> <p>Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m²) and fixing with necessary stainless steel ball bearing hinges of approved make,provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately). Hardware for fixing - Fire rated steel door including frame. Providing and fixing following</p>	1.95	Sq. mtrs.		
21	TEXTURE PAINT: Ground Floor walls to be finished with texture paint of approved make (Rustic) above 4'-6" upto ceiling bottom including scaffolding, cleaning & supply of all materials.	106.88	Sq. mtrs.		
22	Panelling With ACP(Exterior Grade) / Aluminium Composite Panels (With Aluminium Frames) Supplying & fixing 4mm thick Aluminum component sheet of approved make and shade including making of ground of (1"x2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Corning sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5 mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealant) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering,scaffolding, labour, material, complete	25.10	Sq. mtrs.		

23	Panelling With ACP (Interior Grade) / Aluminium Composite Panels (With Aluminium Frames) Supplying & fixing 4mm thick Aluminum component sheet of approved make and shade including making of ground of (1"X2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Coving sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5 mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The rate includes all required shuttering,scafoolding, labour, material, complete	13.95	Sq. mtrs.		
a)	ACP partition and door with ACP sheet on both sides inclusive of all hardware like lock.handle etc. and fittings .	8.37	Sq. mtrs.		
24	SBI logo : Providing,making to shape and size (as per design provided) and fixing to position SBI Bank logo made out of 6 MM thick acrylic sheet with the provision of strip light.the SBI Logo/Letter should be of blue color(pre approved) fixed to position with SS Studs over existing wall with required screws, nut, bolt and hook etc. of size 2'-6" x 2'-0"complete in all respects to the entire satisfaction of the Engg./ Architect.	1.00	No.		
25	Vertical Artifical Garden: Providing & fixing vertical green wall panel of 80 x80 cm panels fixed on existing wall/panelling/partition with required screws, nut, bolt and hook etc.the minimum foilage of mixed artifical plants should not be less than 5" to 8" of make vistafolia or equivalent and mechanism and other fitting fixed in position as per manufacture's specification, complete in all respects to the satisfaction of Architect/Engineer in Charge.	7.44	Sq. mtrs.		
30	3m Vinyle 3d Prints with acrylic sheets:- Providing and fixing 3m Vinyle 3d Print film sandwitched with in 4mm thk acrylic sheets fixed with SS Studs over existing wall/panelling/partition complete in all respects to the entire satisfaction of the Engg./ Architect.	7.44	Sq. mtrs.		
31	TROPHY CASE :- Providing and fixing trophy case using ¾" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) of century, green, Archid ply makewith 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate of Greenlam ,Aica , Merrino,Archid make of approved Shade, Max height of the case upto false ceiling bottom , behind , Sides and top and bottom out of commercial Plyand Laminate. 15" width of glass or wooden shelves of the case to be done using 10 mm thk. polished glass in shelves (The Glass fixed with u brackets). Complete with closing of all joints and accessories complete in all respect as per direction of Architect/Engineer-In-Charge.	2.26	Sq. mtrs.		
	TOTAL OF PART-A (INTERIOR WORKS)			RS.	
	less: Discount (If Any)			RS.	

	G.TOTAL			RS.	
	GST Extra as applicable.				

(IN WORDS) RS

NAME OF CONTRACTOR:
ADDRESS OF CONTRACTOR: