

<b>BOQ FOR REPAIR WORK OF GM-I, CABIN, SBI LHO BUILDING, SECTOR 17 A, CHANDIGARH</b>					
<b>S.No.</b>	<b>Specifications</b>	<b>Qty.</b>	<b>Units</b>	<b>Rate</b>	<b>Amount</b>
1	<b>Mineral Fibre Grid ceiling with Black Silhouett Grid</b>				
	Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.	70	Sq.ft		
2	PU polished with approved sirca/MRF polish, on existing back storage (as approved by Engineer-In-Charge).	120	Sq.ft		
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade as per approved drawing complete in all respect and to the entire satisfaction of the Engineer-in-charge.	400	Sq.ft		
	<b>Wall paneling</b>				
4	Removal of existing wall paneling and Providing & fixing Bison board of 10 mm thick wall panelling consisting of 50x50mm framework made out of kiln seasoned water proof of approved wood. Members to be fixed at 600mmx600mm c/c bothways. bison board of approved make to be fixed to the framwork with surrounding beadding with the help of necessay screw, nails, adhesive etc. as per approved drawing complete in all respect and to the entire satisfaction of the Engineer-in-charge.	80	Sq.ft		

4(i)	Providing & fixing 4 MM Veneer Green/ Century or equivalent makes in approved shade and color with desired grooves / patterns including SS Strips 6-12mm as per drawing to be pasted on the base Bison board of 10 mm thick wall panelling with fevicol adhesive. The base shall be prepared with PVC Sheet in backdrop over existing frame. The Veneer needs to be prepared sanded and sPU polished with approved sirca/MRF polish, Basic rate of Veneer including Taxes Rs.85 /sft	80	Sq.ft		
5	Providing and fixing Float glass (Saint Gobain / TATA / Asahi makes ) top panes of nominal thickness 8 mm (weight not less than 20.00 kg/sqm) over storage with edge moulding (as approved by Engineer-In-Charge).	30	Sq.ft		
6	<b>Plastic Emulsion Paint:</b> Painting & finishing the walls, including surface preparation primer and putty ,finished with three or more coats of plastic emulsion paint, so as to achieve smooth and even finish complete in desired shades and colours (as approved by Engineer-In-Charge).	400	Sq.ft		
<b>Total value of work</b>					

GST will be paid extra

Signature & Seal of Contractor