

## SCHEDULE OF QUANTITIES

Sr.No	Description	Qty	Unit	Rate	Amount
1	Low Height Partitions	30.00	Sq M		
	Providing and fixing in position of low height partitions of the height 1200 mm as per shape shown in the drawing.ie. (750mm solid partition and glass above)				
	Aluminium sections of size 63.5 X 38.1X1.2 mm thk. of INDAL/JINDAL as internal frame structure ,vertically at about 60 cm centers and 3 Nos Horizontally of the same size of frame at floor level, 750 mm and at 1200 mm level. same size at 370 mm level, fixed in position. 8 mm Plywood on both sides of framework finished with 1 mm laminate of approved color and shade with grooves on both sides., 8 mm Plywood of approved quality finished with 1mm Laminate with grooves on both sides of approved color and shade. Top of the partition finished with laminate and 12mm thick glass with etching is fixed over the partition with Dorma make (or) Equivalent make 'D' bracket of SS finish of 12mm thick. Around the partition 75mm thick Dark color laminate is provided as show in the drawing and pattern.				
2	MODULAR PARTITION (120cm(H)) - 65 to 75 mm thick powder coated 1.2mm thick CRCA partitions (Manufactured by Godrej/Metafab/Featherlite/Methodex/any approved makes) with pre punched cutouts to run electric & networking cables. Dual race ways with punch out to fix electrical & data modules for power & data modules for power & data at just below table and skirting level.Partitions are covered with 9mm tiles both sides prelaminate particle board/Fabric cladde Board/glass/soft board as required by using sliding panel method. Level adjusters and all the visible edges of partitions are covered with 2 mm thick powder coated aluminium trims & pvc joinery.	50.00	Sq M		

3	Full Height Partly Solid & Partly Glazed Partition/non glazed partition:	40.00	Sq M		
	Providing and fixing in position of double skin partition, partly paneled and partly glazed as per details shown in the drawing.				
	<u>Frame Work Detail:</u> Aluminium sections of size 63.5 X 38.1X1.2 mm thk. of INDAL/JINDAL as internal frame structure ,vertically at about 60 cm centers and 3 Nos Horizontally of the same size of frame at floor level, 750 mm and at 1200 mm level. same size at 370 mm level, fixed in positionHarwood section of thickness 50 X 50 mm ,vertically at about 60 cm centers varied along columns, wall ends , junctions of walls, as necessary. Horizontally of the same size of frame at floor level, 900 mm,2100 mm, and roof level. 50 X 25 mm at 450 mm level.				
	Lining Work: 8 mm plywood of approved make on both sides of framework from floor level to 900 mm level and 2100 mm level to 6" above false ceiling level finished with 1 mm laminate of approved color and shade. Between 900 mm and 2100 mm level, 8 mm thick clear float glass with etching fixed with necessary Dorma (or) equivalent make 'D' bracket of SS finish of 12mm thick. The glass opening 'jamb' portion finished with laminate.				
	Measurement for the partition area shall be considered from the floor level to false ceiling level only.				
4	Fully glazed Door	11.00	Sq M		

	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings (Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.( DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 32mm dia X 600mm length)				
5	Fully Glazed - Fixed Glass Partition - Patch Fitting	37.00	Sq M		
	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws, 3M Vinyl sticker as per approved, colour, design and pattern, sealants etc.complete.				
6	Partly Glazed And Partly Paneled Doors.	11.00	Sq M		
	II class T.W. frame of size 75 X 50 mm as per the shape and size given in the drawing. 35 mm thick (finished) flush shutter finished with 1mm laminate on both sides with necessary grooves.8mm thick clear float glass of size 250 X 1400 mm fixed with necessary steam beach beading and etching. DORMA Make or equivalent make hardware fittings like locking arrangements,20 mm dia and 300 mm high SS brush steel finish handles, door closer, hinges, tower bolts,etc,. Fixed to the shutters.				
7	FALSE CEILING:				
	NOTE:The false ceiling area will be measured in flat area only.				
7 (a)	Gypsum Board False Ceiling	360.00	Sq M		

	Providing and fixing of M/F suspended false ceiling as the detail given in the drawings. With G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising				
	Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through starp hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional perimeter channels (MF 6A)for light fittings, Air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to from grids with 2 coats of plastic emulsion paint of approved color and one coat of putty over a coat primer etc, complete.				
8	Tables				

	<p>The table top is 25mm thick post formed prelaminated particle board having underside covered with laminate, and other exposed faces are made of 19 mm thick marine plywood (IS 303 grade) finished with 1mm thick laminate . Ready made Keyboard tray made out of powder coated MS sheet exposed edges lipped with PVC edge band 0.5mm thick mounted under the worktop with telescopic sliding channels..Ebco or other approved is to be provided . A foot rest with country wood of 7.5x2.5cm also to be provided. 12mm thick glass to be provided for table top and the edges of the glass to be polished .The inner portion is finished with laminate finish . Drawers are made of 12mm thick marine plywood and exposed faces are finished with 1 mm laminate and inner sides with enamel paint finish as shown in the drawing. Necessary fittings such as telescopic steel slides, godrej lock , handles etc. of approved make are to be provided. One Drawer set contains three number of drawers (with 13-15cm inner depth) are to be provided. One cable manager is to be provided as shown in the drawing. Supplying and installing CPU Trolleys made out of powder coated 1.6 mm thick MS sheet with adjustable width, front &amp; back open &amp; provided with lockable castors .Ebco or other approved Necessary beedings and grooves in laminate to be provided .Edges of plywood</p>				
i	Table of size 220x90x75cm	2.00	Nos		
ii	Table of size 150x75x75cm	9.00	Nos		

9	Tables 150cm(L)X150 cm(L)X65cm (W) - Supplying and fixing L-shaped table made out of 25mm thick interior grade both side prelaminated particle board with exposed top edges lipped with 2mm thick PVC edgeband applied with hot melt glue and other edges with 0.5mm thick PVC edge band all round panel and gromet is provided for wire management. Modesty panel, hardwares like minifix powder coated clipboard screws PVC right angle block, level adjusters etc.. Footrest are made of 18mm prelaminated particle board with 0.5mm thick PVC edge band knock down type bottom bush etc.30cm wide and 15cm height at one and the other end is zero 50cm length fixed on the bottom side of the table etc. complete.	19.00	Nos		
9(a)	DRAWER UNIT - Supplying and fixing drawer unit made out of 19mm thick marine plywood edgebanded with 1mm laminate. 4 drawer pullouts mounted on sliders, with exposed edges lipped with PVC edge band 0.5mm thick central locking system for drawer pullouts (Ebco/equivalent), with bottom bush with necessary shutters to be provided.	19.00	Nos		
9(b)	KEYBOARD TRAYS - Supplying and installing keyboard tray made out of powder coated MS sheet exposed edges lipped with PVC edge band 0.5mm thick mounted under the worktop with telescopic sliding channels. Ebco or other approved	19.00	Nos		
9( c)	CPU TROLLEYS - Supplying and installing CPU trolleys made out of powder coated 1.6mm thick MS sheet with adjustable width, front & back open & provided with lockable castors.Ebco or other approved.	19.00	Nos		
10	Side Tables				

	The side table top with 25mm thick postformed prelaminated particle board, and all other exposed faces are made of 19 mm marine plywood finished with 1mm thick laminate , and inside painted with 2 coats of enamel over a coat of putty and multiwood/teakwood beading on all exposed edges. Godrej metal body locks, all fixtures, nylon brushes etc complete,				
i	Side table of size 120x45x75cm	8.00	Nos		
ii	Side table 185x45x75	2.00	Nos		
11	Low Level Storage :	20.00	Sq M		
	Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm high comprising. 18 mm Plywood for top, bottom, rear, sides and One intermediate with necessary TW reeper.The unit top shall be with 25mm thick Plywood Board of approved make with 1mm thickness flexy laminate of approved color and brand with front side half rounded edge and all the edges and all the three sides with 3mm thick band strip.				
	Exposed faces of Plywood at top and sides of unit to be finished with 1mm thick laminate of approved color and shade.				
	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach molding / beading polished to the satisfaction of the Bank. The inside faces of unit wax and finished with varnish of approved color and shade.				
12	High Level Storages in Record Room :	65.00	Sq M		
	Providing and fixing high level storage to detail as shown in the drg. Size about 450mm wide, and upto ceiling height. 18 mm Plywood for top, bottom, rear, sides, horizontals and One intermediate with necessary TW reeper.The unit top shall be with 25mm thick Plywood Board of approved make with 1mm thickness laminate of approved color and brand with front side half rounded edge and all the edges and all the three sides with 3mm thick band strip.				

	Exposed faces of Plywood at top and sides of unit to be finished with 1mm thick laminate of approved color and shade.				
	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach molding / beading polished to the satisfaction of the Bank. The inside faces of unit wax and finished with varnish of approved color and shade.				
13	Column Paneling	60.00	Sq M		
	Providing and fixing cladding around the columns to detail as per drawing comprising 18mm thick Plywood with necessary stiffner on both ways of required nos and finished with 1 mm thick laminate of approved colour and shade.				
14	Wall paneling	25.00	Sq M		
	Providing and fixing wall paneling to detail as shown in the drawing with 18mm thick Plywood finished with 1mm thick laminate				
15	Providing and fixing zebra blinds Colour and materials selection by the EIC, Rates including material cost and labour charges etc. complete.	40.00	Sq M		
16	<u>Painting</u> - Painting the internal walls with 2 coats of plastic emulsion paint over putty finish and a coat of primer in the banking hall	500.00	Sq M		
17	Conference Table - Providing U-shaped Conference table of length 7m on each side and leg width of 0.65m. A central well of width 60 cm to be provided.The table top is 25mm thick post formed prelaminate particle board having underside covered with laminate, and other exposed faces are made of 19 mm thick marine plywood(IS 303 grade) finished with 1mm thick laminate .	16	RM		



	Ready made Keyboard tray made out of powder coated MS sheet exposed edges lipped with PVC edge band 0.5mm thick mounted under the worktop with telescopic sliding channels..Ebco or other approved is to be provided . A foot rest with country wood of 7.5x2.5cm also to be provided.The inner portion is finished with laminate finish . Necessary fittings such as telescopic steel slides, godrej lock , handles etc. of approved make are to be provided. cable managers to be provided at intermediates as shown in the drawing. Necessary beedings and grooves in laminate to be provided .Edges of plywood finished with PVC edge banding /teakwood lipping.				
18	Demolishing of existing 9" thk.Brick wall mechanically without causing any damage to the existing structure and disposing of the waste at site away from the office at contractor's own risk and cost	15	Sq.M		
19	Providing and laying R.C.C lintel beam with ready mix concrete M 20 including cost of all form work watering, curring etc complete with cost of reinforcement for beam & lintel.	0.15	M3		
20	Anti termite treatment – Providing and applying anti-termite treatment for horizontal and vertical surfaces by drilling 12mm dia holes on the walls just above the skirting level at an interval of 30cm(maximum) then pouring antitermite chemical emulsion into the holes. Filling the holes with cement mortar, spraying anti-termite chemical emulsion at the other infested areas. Rates to include 2 years warranty.(aproximate area of the branch)	400	Sq M		

21	Vitrified Tile Flooring – Providing and fixing best quality doubly charged 60cmX60cm white vitrified tile over existing vitrified tile flooring (only in Banking Hall as per instructions of EIC) after necessary preparatory works over it with T5 grade tile adhesive and pointing with approved quality compound, cleaning the surface after laying including labour charges, transportation of materials etc. complete. Baic price of tile Rs.60/sq.ft.	360	Sq M		
22	Dismantling and disposal of existing wall panelling, counters, false ceiling and old obsolete material as identified by branch etc. at location away from site at contractors own risk and cost.	1	LS		
23	Solid block works of approved qty of size 30x20x20cm & of compressive strength not<35 kg/cm <sup>2</sup> in in C.M. 1:6 in super-structure above plinth level (first floor level) including staging if required watering ,curing etc complete.	7	M3		
24	Plastering with Cement Mortar 1:5, (1 cement 5 sand) 12mm thick one coat floated hard and traveled smooth to inside walls including all staging work watering,curing etc complete.	43	Sq M		
25	Finishing New cement plastered wall with 1 coat of primer and painted with 1 coat of distemper	43	Sq M		
26	Dismantling of flushing cistern of all types(C.I.,PVC,vitrous china), wash basins etc including all fittings and stacking of useful materials near the site and disposal of unserviceable materials from the floor and disposal the waste materials away from the site at contractors own risk and cost.	1	LS		
27	Dismantling the existing toilet wall and floor tiles, kitchen dado etc. laid in cement mortar and base course from second floor and disposing the materials away from the site at contractors own risk and cost.	60	Sq.M		

<b>28</b>	Providing and fixing first quality vitrified wall tiles (minimum basic value should be @ Rs.600/m <sup>2</sup> ) conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades, size as specified by Engineer in charge, in Dados, over 12mm thick bed of cement mortar 1:3 and jointing with grey cement slurry @ 3.3 Kg per sqm, including pointing in white cement mixed with pigment of matching shade complete for bath room walls	40	Sq.M		
<b>29</b>	Providing and laying non- skid vitrified floor tiles of size 600 x 600 mm (thickness to be specified by the manufacturer) (minimum basic value should be @ Rs. 600/m <sup>2</sup> ) of first quality conforming to IS:15622, of approved make, in all colours, shades, size as specified by Engineer in charge, laid over 20 mm thick bed of cement mortar 1:4, including pointing the joints with white cement and matching pigment etc. complete for bath room floor.	20	Sq.M		
<b>30</b>	Providing and applying water proof treatment with Bostik boscolastic as per the manufactures specifications, after necessary surface	20	Sq.M		
<b>31</b>	Supply and fixing 110 mm dia PVC pipe 6 (kg/Cm <sup>2</sup> ) of approved quality confirming to ISI mark with special such as tees bends elbows	15	Rmt		
<b>32</b>	Supply and fixing 160mm dia PVC pipe 6 (kg/Cm <sup>2</sup> ) of approved quality confirming to ISI mark with special such as tees bends elbows	10	Rmt		
<b>33</b>	Supplying laying and jointing 20mm nominal dia.P.V.C. pipe and specials such as tees, bends, elbows, check nuts etc. with clamps including	20	Rmt		
<b>34</b>	Supplying laying and jointing 32mm nominal dia.P.V.C. pipe and specials such as tees, bends, elbows, check nuts etc. with clamps including	15	Rmt		

<b>35</b>	Supplying laying and jointing 50mm nominal dia.P.V.C. pipe and specials such as tees, bends, elbows, check nuts etc. with clamps including	15	Rmt		
<b>36</b>	Supplying and fixing half pedestal wash basin (parryware or equivalent make, basic price of Rs. 4000/No) rates including cost of pillar cock quarter	2	Nos		
<b>37</b>	Supplying and fixing CP health faucet 20 mm jaquar or crab tree including angle valve (basic price of health faucet Rs.1350/No)	2	Nos		
<b>38</b>	Supplying and fixing European W.C.pan parryware or equivalent make with flush valve P-trap,angle cock including all necessary fitting etc complete.(basic price of pan Rs.7000/No)	2	Nos		
	<b>TOTAL (Excluding GST)</b>				

\* GST as applicable to be paid extra