

**TENDER FOR PROPOSED INTERIOR RENOVATION WORK FOR STATE BANK OF INDIA, RACPC AUNDH ,PUNE, MAHARASHTRA.**

	Description	Qty.	Unit	Rate	Amount
<b>A</b>	<b>PARTITIONS / PANELLING( Soild/semi glazed)</b>				
	<b>MAIN FRAME:</b>	<b>8200.00</b>	<b>Sft</b>		
<b>1</b>	Aluminium sections of 16 Gauge of size 2"x2" Aluminium section placed vertically and horizontally at 2' Centre-Centre spacing to form mesh spacing . Extra frame below slab soffit for conduit to run above. All verticals shall be secured to the ceiling.				
<b>2</b>	<b>SKIN</b>	<b>12000.00</b>	<b>Sft</b>		
	12mm Exterior Grade Particle Board shall be screwed to frame work on both sides with joints as shown or directed.				
<b>3</b>	<b>FINISHING:-</b>				
<b>3.1</b>	<b>VENEER(Basic cost upto Rs 2500.00 per sheet)</b>	<b>3000.00</b>	<b>Sft</b>		
	4mm thk natural verner with matching superior approved grade to be fixed to the plywood having joints as shown or directed complete with melamine polish finish.				
<b>3.2</b>	<b>LAMINATE (Basic cost upto Rs 2200 per sheet):-</b>	<b>6500.00</b>	<b>Sft</b>		
	Approved laminate shall be of 1.0 mm thick.				
	Laminate shall be fixed on plywood skins with glue having grooves as shown or directed. Internal surfaces at specified places shall be 1.0 mm thick as directed.				
<b>3.3</b>	<b>FLUTE SHEET ( Basic Cost-3100 /-Sheet)</b>	<b>1200.00</b>	<b>Sft</b>		
	Providing and fixing Flute Sheet size 4 ' X 8' ( shall be anti Bacterial ,Anti scatch and have UV colour Fastness for interior panelling as per design.				
<b>3.4</b>	<b>CHARCOAL WALL PANEL SHEET ( Basic Cost upto Rs 3000/-)</b>	<b>500.00</b>	<b>Sft</b>		
	Providing and fixing 4 mm thick Textured Charcoal (4 mm thick) wall panel Sheet.				
<b>3.5</b>	<b>ACRYLIC SOLID SURFACE (Basic cost upto for 6mm thick of Rs. 1200 / Sq. Fts )</b>	<b>100.00</b>	<b>Sft</b>		
	Further, Acrylic soild surface wherever mentioned in the BOQ (For items of Panelling, Reception Counter, Furniture elements etc) shall be high end, of desired and approved color and adhering to the BOQ specifications. Corian thickness shall be 6mm thk for vertical surfaces & fascias and 6mm thk for horizontal surfaces shall be provided with polish complete in all respect.				
<b>3.6</b>	<b>MIRROR PANELLING(Basic cost upto Rs70/sqft)</b>				
<b>3.7</b>	Providing & Fixing Mirror Panelling using 6 mm thick mirror of approved make over 19mm thick commercial board backing. The mirror to be fixed with T.W beading of size 12.5mm X 19mm, finished with melamine polish complete as per the instructions of EIC. (FOR TOILETS)	<b>100.00</b>	<b>Sft</b>		
<b>4</b>	<b>S S PROFILE PATTI</b>	<b>400</b>	<b>Rft</b>		
	Providing and fixing Metal 12 mm width T /U / L / plain profile finish as per Design				
<b>5</b>	<b>POLYETHYLENE TEREPHTHALATE (PET) Panel Casic cost Upto Rs 105 Per sqft)</b>	<b>300</b>	<b>Sft</b>		
	Providing and fixing PET Panel Acoustical Systems				
<b>5A</b>	V grooving in PET PANEL	<b>50</b>	<b>Sft</b>		
<b>5B</b>	Embossed Design in PET PANEL	<b>300</b>	<b>Sft</b>		
<b>5C</b>	CNC cutting in PET PANE Las per design	<b>100</b>	<b>Sft</b>		
<b>6</b>	<b>LACQUERED GLASS (Basic cost upto Rs 300.00Per Sqft)</b>	<b>60</b>	<b>Sft</b>		
	Providing and fixing Lacquered glass in panelling				
<b>7</b>	Acrylic Emulsion Paint finish	<b>100.00</b>	<b>Sft</b>		
<b>8</b>	Textured Paint finish	<b>30.00</b>	<b>Sft</b>		
<b>9</b>	Providing & fixing approved wallpaper over the Gypsum surface (Basic rate of Rs. 210/ Sq. Fts)	<b>100.00</b>	<b>Sft</b>		
	<b>NOTE:</b>				
<b>A</b>	<b>All exposed ends shall have 6mm Corian Bidding</b>				

<b>B</b>	Laminate shall be fixed on plywood skins with glue having grooves as shown or directed. Internal surfaces at specified places shall be 0.8 mm thick as irected by Bank. The rates quoted for the items of partions & paneling shall be inclusive of providing & fixing M.S. plate & brackets over & above the aluminium frame work as directed & wherever instructed for mounting the TV units & screens etc complete.				
<b>C</b>	IMPORTANT NOTE ON THE DESIGN REQUIREMENTS APPLICABLE IN CASE OF ALL THE ITEMS OF PARTITIONS & PANELLING: - The design & the elevation of the various items under the heads: Partition & Panelling shall be at the complete discretion & directions / instructions of the Engineer in charge on site. Wherever instructed & directed, the rate shall include providing & fixing additional 12/6 mm thk plywood backing over and above the 303 MR grade Commercial plywood so provided in the items of partition / panelling to form raised panel design at regular intervals as directed and to be finished with high end approved 4.0 mm thk veneer with high end melamine polish (proportion of gloss and matt as directed) with uniform shade & texture. Incase of 9mm thk plywood used instead of 6mm thk plywood for the raised panels for the items of Partition or Paneling works, the difference between the cost of 9mm thk plywood and 6mm thk plywood for the actual quantity of plywood used for the said partition or panelling items shall be measuace shall have				
<b>D</b>	The level difference between the said raised panels and recessed panels shall be finished with approved designer moulding to be finished with high end (proportion of gloss and matt as directed) melamine polish and shall also include designer inlays to be finished with high end veneer with high end melamine polish, pattas & bands at various levels etc in veneer and melamine polish and combinations of raised and recessed panels with inlays etc complete to the complete satisfaction of the Bank and Engineer in charge				
<b>E</b>	For all items of Interior Furnishing works & Furniture works, the basic rate of Laminate considered for all the specifications / BOQ items herein shall be Rs. 60 / Sq. Fts plus taxes (GST) whereas the basic rate of Veneer, which shall be high end, uniform and without any variations, 4.0 mm thk considered for all the specifications / BOQ items herein shall be Rs. 100 / Sq. Fts plus taxes (GST). Basic rate for Frosted / Designer film of 3M, Lumar or equivalent approved wherever mentioned separately shall be Rs. 90 / Sq. Fts plus taxes (GST). The basic rate would be the rate offered to the bidder by the vendor / supplier after discounts and excluding the cost towards transportation, freight, loading, unloading etc and also exclusive of taxes (GST). Necessary documentary evidence in the form of challans & Tax invoices, details of payments released to the vendor for the purchase of such materials & including the loading-unloading transport slips needs to be submitted at the time of billing without which the paymeace shall have 1 mm thick white laminat				
<b>F</b>	Further, Corian wherever mentioned in the BOQ (For items of Panelling, Reception Counter, Furniture elements etc) shall be high end, of desired and approved color and adhering to the BOQ specifications. Corian thickness shall be 6mm thk for vertical surfaces & fascias and 12mm thk for horizontal surfaces shall be provided and with a basic rate of Rs. 1200 / Sq. Fts plus taxes (GST) for 6mm thk Corian and Rs. 1500 / Sq. Fts plus taxes (GST) for 12 mm thk Corian.				
<b>G</b>	All other finishing Material shall be fixed as per manufacturars specifications.				
<b>10</b>	<b>FULL HEIGHT GLASS PARTITION.</b>				
	Providing and erecting in position full height fully glazed partiton in Silver Annodized natural Aluminium Modular Glass Partition using standard track section of size 54 mm X 25 mm profile of Kubik-Kwentha 54 series, Dorma - Alexa Series or equivalent approved at top, bottom and sides as per manufacturer's standards and specifications and as directed by the Bank to comply with the standard partition suite design including door in single glazed 10mm thk clear toughened glass to be fixed in the centre of the track section, single door frame size to allow the glazed door of same size, shape, profile as partition &/or upto 35mm thk door of any type i.e. solid flush door or glazed door as per directions and upto any desired height, with sound insulation capacity of minimum of 32 dB including Glass to glass I, T, L joint and connectors, standard assessorias as per manufacturers recommendations & standards, gaskets etc complete. The Clear toughened glass shall be of Saint Gobain / Asahi or equivalent make as approved including designer decorative frosted film of approved make, shade & design on the glass per drawing.	600.00	Sft		

<b>11</b>	<b>GLAZED DOOR</b>				
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings (Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items. (DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 32mm dia X 600mm length) etc Size: 3'0" X 8'0" for each of the door as per drawing.	300.00	Sft		
<b>12</b>	<b>FALSE CEILING</b>				
	General :				
	The filler, paper tapes, finishes and primers suitable for Gypsum boards, shall be as per recommended practises of India Gypsum.				
	Framework grid and suspenders shall be fixed to avoid fouling with services such as ducting, sprinklers, electricals fixtures, etc				
	T.W. framing may be allowed in certain areas for the Gypsum Board ceiling with the approval of the Bank. The same should have three coats of fire resistant paint.				
	Note: All the hardware such as fasteners, hangers, suspenders, etc. required for erection of the false ceiling shall be of INDIA GYPSUM make. And approved by the Bank.				
<b>13</b>	<b>GYPSUM BOARD</b>	<b>10000.00</b>	<b>Sft</b>		
	Metal frame <b>False Ceiling</b> of 12 mm thk. <b>Gypsum Board</b> including vertical drop panels.				
	Providing and Fixing 12 mm Thk. Gypsum board on metallic grid, conforming to IS: 2095: :1982. The metallic grid shall consists of the following :				
	GI Perimeter channels of size 27mm and 0.5mm thk. having one flange of 20mm and another flange of 30mm.				
	GI intermediate channel of size 45mm 0.5mm thk. With two flange of 15mm each at 4'-0" centre to centre.				
	GI Hanger of size 1"x1", 0.5mm thk. A 4'-0" centre to centre distance.				
	GI Cleat and Steel Expansion Fasteners.				
	Ceiling section of 0.5mm thickness having curled wedge of 51.5 mm and two flanges of 26mm each with lips of 10.5mm at 450mm center to center. Connecting clips & 12.5 mm dry wall screws at 230 mm center to center.				
	The metallic grid shall be installed as follows :				
	The perimeter channel along the perimeter of the ceiling with screw fixed to brickwall / partition with the help of rawlplugs and screws.				
	The intermediate channels shall be suspended from the ceiling with steel GI hanger fixed to the slab soffit with GI cleat and steel expansion fasteners. The intermediate channels shall be at 4'-0" centre to centre distance.				
	The ceiling section placed in a direction perpendicular to the intermediate channel at 1'-6" C/C distance shall be fixed to the intermediate channel with the help of connecting clips and 12.5 mm dry wall screws at 230 mm centre to centre distance.				
	Finally, the 12mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisite filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, (as per recommendations of manufacturers, Indian Gypsum or equivalent) including Acrylic Emulsion Paint of approved make and shade and colour.				
	The rate shall include the cut-outs to be made for light fittings, grills, diffusers, speakers, smoke detectors, sprinklers etc. with provision of the frame along perimeter of the cut outs/ opening with channels/ ply to support the ceiling adequately as per the directions of Bank. The rate shall include necessary shapes, designs, patterns in curvature, sloping, dome, oval & elliptical shaped etc including the necessary provisions of coved lighting scheme etc complete as per the designs, drawings .				

13A	Dome 3 m diameter	1	No		
13B	Dome 2 m diameter	2	No		
13C	Stretched lighting Frame-	2	No		
14	<b>MINRAL FIBER FALSE CEILING:</b>	2000.00	Sft		
	Providing and erecting false ceiling of Mineral Fiber ceiling Board Armstrong or equivalent approved make with framework, runners, cross runners & suspenders from the existing ceiling as per the manufacturers details and specification and 600X 600mmX 15mm thk tiles of approved design, texture & in microlook pattern including the grids in black / white silhouette pattern, 15mm as per manufacturers specifications complete including making necessary cut-outs for electrical fixtures, AC diffusers, access etc as per the instruction.				
	Approved premium Tile in Dune RH Microlook category with black silhouette locking supporting system, 15 mm grid.				
15	<b>VEENEER FALSE CEILING</b>	50.00	Sft		
	Providing and erecting false ceiling in veneer with 12 mm thk IS 303 MR grade Commercial Plywood backing on teak wood frame to be anchored to the main ceiling with cross runners tongued and grooved. The ply to be finished with approved 4mm thk veneer & melamine polish etc. complete as per directions.				
16	<b>CLOUDS /DESIGN IN GYPSUM</b>	3000.00	sqft		
	Providing and erecting false ceiling in clouds/Design Gypsum paintable surface (basic rate 800sqft ) PANEL IS 303 MR grade Commercial Plywood backing on teak wood frame to be anchored to the main ceiling with cross runners tongued and grooved, finishing the same with corian of approved shade, colour & texture as directed complete as per drawings & details.				
17	<b>Aluminium U shaped WOODEN FINISHED BAFFLES /BATTENS</b>	2000.00	Sft		
	Providing & Fixing in position 100mm x 50mm Aluminium U shaped <b>Baffles / Battens</b> for false ceiling, cladding etc with with <b>63 % open area</b> as per approved make including all joineries, hardware, fittings, fixtures etc including fixing the same to the backing wall or main RCC ceiling (For false ceilings) with fasteners, clamps, necessary fittings etc complete including polishing the battens with high end melamine polish of desired gloss effect etc complete as per manufacturers standards.				
18	<b>ELE. PANEL CABINATE:</b>	64.00	Sft		
	Providing and fixing electrical panel board area shutter (openable and partly louvered) made out of 19mm thick BWR grade ply boxing, shutters. The Board will have 12mm. thk back of Commercial plywood including 12mm thk bison board top on all internal surfaces and 1.0mm thick laminate finish on front, with app. colour polish to external edges brass hinges, handles etc. as per the details. The shutters should have 12" ht. All. Powder coated louvers on top and bottom for ventilation as per site conditions & directions.				
	<b>SCHEDULE - FURNITURE WORKS</b>				
	N.B: - The plywood considered in this estimate shall be IS 303 Commercial Plywood for all the items of Interior & Furniture works. The rate shall be inclusive of anti termite coating on all sides to plywood, teak wood & all the other wooden components of Asian paints or equivalent approved make.				
19	<b>LOW HEIGHT STORAGE</b>				
	Providing and fixing <b>Low height Storage</b> of ht. 2'-6" or 4'-0" as desired and depth of 18" as specified in the drawings as per specification below.				
	Skeleton - made out of 19 mm. Thk IS 303 Commercial Plywood at end verticals, top and bottom and verticals 450mm to 600mm Centres as shown in drawing and 6 mm thk back ply.				
	SHELVES - 19mm Thk.IS 303 Commercial Plywood top and edges finished in 0.8mm thk. Laminate to accommodate file height removable and supported on pins.				
	SHUTTERS-made out of 19mm thk. IS 303 Commercial Plywoodexternally finished in MDF with PU or 1.5mm thk laminate or 3.0mm thk. Veneer with melamine polish and Internally finished in 0.8 mm thk. Laminate as shown or directed.				

	HINGES - Each shutter shall have 100mm long oxidised brass butt hinges. Minimum 4 nos. hinges for each of the shutter for Full height Storage and 3 Nos. hinges for each of the shutter for Low Height Storage to be provided.				
	BOLTS - Flush tower bolts from inside at top and bottom to the shutters and magnetic catch fixed top and bottom.				
	LOCKS - of approved make 4 -lever brass body dead lock with S.S. Key.				
	HANDLES - 100mm wide handles of C.P brass as approved by the Bank				
	SKIRTING -As instructed by Bank, in plywood finished in approved 1.0 mm thk laminate or 1.0 mm thk veneer with melamine polish.				
	BACK - Unexposed back side of storage to have 6mm thk Commercial ply with polish. However exposed back of the storage shall be finished with 1.0mm thk laminate finish.				
<b>a</b>	Finishing :- All external surface finish with 3.0 mm thk approved veneer with top deco /melamine polish. All exposed surfaces shall have beading patti in veneer with melamine polish. Inside visible surface complete with 0.8mm thk Laminate. Rate shall also include tw moulding for the top duly polished wherever instructed. The top of the storage unit shall have approved 3.0mm thk veneer with melamine polish as shown and directed by the Consultant etc complete.	1000.00	Sft		
<b>a</b>	Finishing :- All external surface finish with 1.0mm thk approved laminate. The top of this storage shall also be finished with approved 1.0mm thk laminate. with top All exposed surfaces shall have beading patti in veneer with melamine polish. Inside visible surface complete with 0.8mm thk Laminate. Rate shall also include tw moulding for the top duly polished wherever instructed. The top of the storage unit shall have approved 3.0mm thk veneer with melamine polish as shown and directed by the Consultant etc complete.	1000.00	Sft		
<b>b</b>	Finishing: - Do - Same specifications & including all items as mentioned above, but Overhead storage of 2'-0" height and length as desired for the server room, UPS room & Pantry to be finished with approved 1.0mm thk approved laminate. The top of this storage shall also be finished with approved 1.0mm thk laminate.	40.00	Sft		
<b>21</b>	<b>TABLE FOR C.M (Maximum 6'-0" X 3'-0")WITH SIDE CREDENZA</b>	5.00	Nos		
	Providing and supplying table for the CMr to be made out of 19mm thk. IS 303 Commercial Plywoodfinished with approved 1.5 mm thick Laminate with 12 mm thick Glass for the top & 1.5mm laminate for all other exposed areas. The top of the table to have t.w. moulding all around. The rate shall be inclusive of providing a keyboard tray on sliding telescopic channels & a pedestal drawer unit made out of 16mm thk IS 303 Commercial Plywoodon side with 2 nos of equal sized drawers on sliding channels & openable shutter below. The side credenza shall be on the other side & shall be paid for seperately under the relevant item. All internal surfaces to be finished in approved 0.8mm thk laminate. All the external surfaces shall be finished with 1.5mm thick laminate including the pedestal drawer unit. Providing and erecting in position Side Credenza for the tables, 2'6" height and 18" deep to be made out of 19mm thk 710 BWP Commercial Plywood. All exposed surfaces shall be in 1.5mm thick laminate and all internal surfoved including designer decorative frosted film of approved make, shade & design on the glass per drawing.wherever instructed with 2 nos of drawers on top and openable shutters below. The openable shutters to be made out of 19mm thk. IS 303 Commercial Plywoodwith all internal surfaces to be finished in 0.8 /1 mm thk approved laminate and externally with 1.5mm thk laminate with melamine including brass hinges, ball catches, 100mm brass handles, brass locks etc complete as per the instruction of the Bank. Rate shall also include 12mm thick glass top.				

	The table and side credenza shall have 12 mm thk clear glass on top with rounded edges. The rate shall also include CPU trolley of reputed manufacturer, keyboard tray as per the approved makes which shall be heavy duty. The necessary hardware such as automatic locking, ball catches, wire managers etc. to be provided as per the instructions of the Bank. The Elevation of the table shall be as directed by Bank on site.				
<b>22</b>	<b>MANAGER 'S TABLE (Maximum 5'-0" X 2'-6") WITH SIDE CREDENZA</b>	5	Nos		
	Providing and supplying table for the MANAGER to be made out of 19mm thk. IS 303 Commercial Plywood finished with approved 3.0mm thk high end veneer with DUCO polish for the top & 3.0 mm thk veneer with melamine polish for all other exposed areas. The top of the table to have t.w. moulding all around. The rate shall be inclusive of providing a keyboard tray on sliding telescopic channels & a pedestal drawer unit made out of 16mm thk IS 303 Commercial Plywood on side with 2 nos of equal sized drawers on sliding channels & openable shutter below. The side credenza shall be on the other side & shall be paid for separately under the relevant item. All internal surfaces to be finished in approved 0.8mm thk laminate. All the external surfaces shall be finished with 3.0mm thk approved high end veneer with melamine polish including the pedestal drawer unit. Providing and erecting in position Side Credenza for the tables, 2'6" height and 18" deep to be made out of 19mm thk 710 BWP Commercial Plywood. All exposed including designer decorative frosted film of approved make, shade & design on the glass per drawing, wherever instructed with 2 nos of drawers on top and openable shutters below. The openable shutters to be made out of 19mm thk. IS 303 Commercial Plywood with all internal surfaces to be finished in 0.8 /1 mm thk approved laminate and externally with 1.5mm thk laminate with melamine including brass hinges, ball catches, 100mm brass handles, brass locks etc complete as per the instruction of the Bank. Rate shall also include 12mm thick glass top.				
	The table shall have 6mm thk clear glass on top with bevelled edges. The rate shall also include CPU trolley of reputed manufacturer, keyboard tray as per the approved makes which shall be heavy duty. The necessary hardware such as automatic locking, ball catches, wire managers etc. to be provided as per the instructions of the Bank. The Elevation of the table shall be as directed by Bank on site.				
<b>23</b>	<b>ASST. WORK STATIONS 5'X 5' WITH TWO PEDESTAL STORAGE</b>	12.00	Nos		
	Providing and supplying work station table for the Asst. Table to be made out of 19mm thk IS 303 Commercial Plywood finished with approved 1.5mm thk laminate for top and all other exposed areas. The top of the table to have corian moulding all around. The rate shall be inclusive of providing a keyboard tray on sliding telescopic channels & a pedestal drawer unit made out of 12/18mm thk Commercial ply on side with 3 nos of equal sized drawers on sliding channels. All internal surfaces to be finished in approved 0.8mm thk laminate.				
	The rate shall also include CPU trolley of reputed manufacturer, keyboard tray as per the approved makes which shall be heavy duty. The necessary hardware such as automatic locking, ball catches, wire managers etc. to be provided as per the instructions of the Bank. The Elevation of the table shall be as directed by Bank on site.				
<b>24</b>	<b>LINEAR WORKSTION WITH PEDESTAL DRAWER UNIT &amp; LOW HEIGHT PARTITION SCREENS</b>	14.00	rft		
	Providing and erecting in position linear work station of 3'-9" to 4'-0" in length and 2'-0" to 2'-3" in width as per the instructions to be made out of 19mm thk. ply for work top with the top to be finished with 1mm thk approved laminate for the top surface with front part of it in 6mm thick corian moulding & 0.8mm/1mm thk approved laminate for all internal surfaces. The work top to be supported on the adjacent low height partitions. (The partitions shall be paid for separately under the relevant item). The rate shall be inclusive of necessary fittings, supporting arrangements to the partitions, heavy duty keyboard tray of standard make, CPU trolleys of approved make & a pedestal drawer unit with castors to be made out of 18/ 16mm thk Commercial ply with 3 nos of equal sized drawers on telescopic channels. 1mm thk approved Laminate. The unit shall have locks, handles, hinges, channels, necessary fittings, fixtures,				

	Hardware, automatic locking arrangement, wire managers etc. The internal surfaces of the drawer unit shall have polish and the internal surfaces of individual drawers shall be finished with 0.8mm thk approved laminate including providing the necessary openings for electrical/computer wiring complete as per the instructions of Bank. Elevation of the table shall be as directed by Bank on site.				
<b>25</b>	<b>MEETING TABLE</b>	3.00	Nos		
	Providing and Supplying 3'-6" dia circular /Square meeting tables with vertical box cylinder type support in 19mm thk ply support to be finished with raised 4.0mm thk approved veneer panels with melamine polish for the entire support section with cross bracing on top if desired to be finished with approved 4.0mm thk veneer with melamine polish including t.w.beading with t.w. moulding as per the instructions of size approx 50 x 40 including beading with top to be in 19mm thk Commercial plywood with 60 X 60mm thk t.w.moulding all round the top to be finished with approved 4.0 mm thk veneer including approved polycoat polish. The table to have a drawer unit with 6" equal sized, 1-2 nos of drawers to be made out of 16mm thk Commercial ply below the table top all around for the entire diameter of the table on telescopic channels with front to be finished with 4.0 mm thk approved veneer with melamine polish and internal surfaces of the drawer shall be finished with 0.8mm thk approved laminate.				

	The other surfaces of the table shall have 4.0mm thk veneer with melamine polish. The entire table to be finished in 4.0mm thk veneer with melamine polish including footrest as per directions of Bank. The rate shall be inclusive of a cut out on the top of the cylinder support to be finished with 4.0mm thk veneer with melamine polish internally to be filled with planters and white pebbles for the entire cut out portion including peripheral moulding to be polished & 12mm thk toughened glass for the cut out portion etc complete.				
<b>26</b>	<b>DINING TABLE ( 5' x 3'-0" )</b>				
	Providing and erecting in position DINING TABLE with metal stand of approx size mentioned above as per layout to be made out of 19mm thick Ply .Top shall have approved ceramic tile finish and all other exposed/internal surfaces shall be finishes with 1.5mm thick laminate	5	Nos		
<b>27</b>	<b>WORKSTATION FOR DCDO (6'/7'-0" x 2'-6" ) WITH SIDE CREDENZA</b>	7.00	Nos		
	Providing and erecting in position work station as per the instructions and drawings to be made out of 19mm thk. Commercial ply for work top and verticals finished with 1.5mm thk approved laminate externally for all the exposed surfacesIncluding the top & 1mm/0.8mm thk approved laminate internally. The top of the table to have Corian nosing mould all around. The rate shall be inclusive of providing a keyboard tray on sliding channels & a drawer unit on side with 3 nos of drawers on channels and erecting in position Side Credenza for the tables, 2'6" height and 18" deep to be made out of 19mm thk 710 BWP Commercial Plywood. All exposed surfaces shall have beading patti in laminate / veneer with melamine polish.				
	Rate shall also include all fittings including brass hinges, ball catches, 100mm brass handles, brass locks etc complete as per the instruction of the Bank. The side credenza however shall be paid for seperately in the relevant item. The rate shall be inclusive of CPU trolley of approved make, necessary fittings, fixtures, hardware such as channels, hinges, ball catches, locking arrangement, wire managers etc including providing the necessary openings for electrical/computer wiring complete as per the instructions of Bank. Elevation of the table shall be as directed by Bank on site.				
<b>28</b>	<b>WORK STATION</b>	<b>30.00</b>	<b>R.Fts</b>		
	Do...Same as above, however Workstation Counter of size 5'-0" X 2'-6" X 2'-6" including all the assessories, fittings, fixtures and in line with specifications for Item No 11A above.				
<b>29</b>	<b>GRAHAK MITRA COUNTER : 12'X2'6"</b>	1.00	No		
	Providing and supplying Grahak Mitra counter of size 12'X 2'6" x 2'6" Made out of 19 mm thick exterior grade IS 303 ply with chamfer edge glass 12mm thk for top on stainless steel hollow pipes 75mm dia & height above table top 1'-0". The front apron to have 19mm thk IS 303 Commercial Plywood hollow box to be finished with approved 12mm thk lacqured Glass including provision of co-lighting behind the glass. The top of the table shall be provided with a 12mm thk glass on the top of the table with pedestal drawer unit with castors comprising of 3 nos of drawers on side to be finished with approved 3.0mm thk approved veneer with melamine polish, CPU trolley of standard make and a shelf for keeping the Monitor below the glass top with heavy duty keyboard tray on sliding channels of standard make including all the necessary hardware, fittings, fixtures.				
	All exposed surfaces of the counter shall be finished with approved 3.0mm thk veneer with melamine polish & internal surfaces shall be finished with 1mm/0.8mm thk laminate including making the necessary openings for wires of telephone boards, PC, grooves, mouldings, etc complete.				
<b>30</b>	<b>DUCO PAINTED MDF JALI WITH FRAME:</b>	21.00	Sft		
	Making and fixing in position as partition screens (as per approved sample) Laser Cut Jaali partition to be made out of MDF board of 6 mm thickness and Backed by Acrylic sheet. All exposed surfaces to be finish with clear gloss Duco paint as per approved shade, fixed fixed on tracks/ studs as directed.				
<b>31</b>	<b>SHIFTING OF OLD FURNITURE</b>	<b>1</b>	<b>LS</b>		
	Removing,shifting and assembling of old furniture carefully at new site(as directed)				
	<b>SUB TOTAL</b>				<b>Rs.</b>
	<b>Discount,if any</b>				<b>Rs.</b>

	TOTAL			Rs.	
	*GST extra as per Actuals				