| BILL OF | QUANTITES FOR AIR-CONDITIONING WORKS FOR SBI | BRANC | H AT MAI | HARAJPUR (| HAZIABAD,U. |
|---------|------------------------------------------------------------------------------------------------------------------|--------------|----------|------------|-------------|
| S. No. | DESCRIPTION OF WORKS | UNIT | QTY | RATE | AMOUNT |
| | SPLIT /CASSETTE TYPE AIR CONDITIONERS | | | | |
| | Supplying, erection, testing and commissioning following | | | | |
| | wall mounted Split/ Root mounted cassette units of (| | | | |
| | Hitachi/ Daikin/O-General/Voltas) with cordless remote | | | | |
| | complete with all necessary fittings duly insulated with 9 | | | | |
| | mm thick nitrile rubber pipe insulation with (evaporator coil | | | | |
| | - copper only), fan and fan motor, machine control panel | | | | |
| | improved Refrigerant Joints, .Air conditioners shall be fitted | | | | |
| 1 | with hermetically sealed type suction cooled reciprocating | | | | |
| ' | or discharge cooled rotary compressor or scroll | | | | |
| | compressor. Compressor unit operating on R32/ R-410. All | | | | |
| | complete as per drawing, approval and instructions of the | | | | |
| | Architect/ Employer (Rates to be inclusive of Copper refrigerant pipe with insulation and Drain pipe up to 3 Mtr | | | | |
| | length). <i>Item to include powder coated outdoor stands</i> | | | | |
| | as per the manufacturer specifications. | | | | |
| | ac per une manuscurer epermouner. | | | | |
| | 1.0 TR wall mounted split unit (Minimum 5-Star rating | Nos. | 0.00 | | |
| а | inverter type) including all necessary fittings and mountings | | | | |
| | as specified by the manufacturer. 1.5 TR wall mounted split unit (Minimum 5-Star rating | Nos. | 2.00 | | |
| b | inverter type) including all necessary fittings and mountings | 1105. | 2.00 | | |
| | as specified by the manufacturer. | | | | |
| | 2 TR wall mounted split unit (Minimum 5-Star rating inverter | | | | |
| С | type) including all necessary fittings and mountings as | Nos. | 1.00 | | |
| | specified by the manufacturer. | | | | |
| | 3.0 T Cassette AC Ceiling suspended Cassette type split | | | | |
| d | unit with 4 way/ round air flow including all necessary | Nos. | 2.00 | | |
| | fittings and mountings as specified by the manufacturer | | | | |
| | (Three phase). 4.0 T Cassette AC Ceiling suspended Cassette type split | | | | |
| | unit with 4 way/ round air flow including all necessary | l | | | |
| е | fittings and mountings as specified by the manufacturer | Nos. | 2.00 | | |
| | (Three phase). | | | | |
| 2 | EXTRA REFRIGERANT PIPING | | | | |
| | EXTRA REFRIGERANT FIFTING | | | | |
| | Supplying and laying of Extra copper refrigerant piping with | | | | |
| | nitrile rubber pipe insulation, both of size as specified by | | | | |
| | the manufacturer suitable for 1.0 TR/1.5/ 2.0 TR Split type | | | | |
| | AC and 2.0 TR/ 3.0/4.0 TR Cassette AC (From Indoor to | | | | |
| а | For 1/1.5/2 T as specified by the manufacturer | Mtr. | 10.00 | | |
| b | For cassette as specified by the manufacturer | Mtr. | 18.00 | | |
| | | | | | |
| 3 | DRAIN PIPING | | | | |
| | Providing and fixing drain piping up to drain as directed by | | | | |
| | the engineer incharge with all accessories e.g. elbows, | | | | |
| | unions, sockets, reducers, reducing tees, nipples etc. | | | | |
| | Complete job including cutting chiseling in walls, floor and | | | | |
| | making good of all chases/ cuts etc. and discharging the | l | | | |
| | drain into a floor trap/ gully as per site conditions with | | | | |
| • | insulation, both as specified by the manufacturer. 25 mm dia PVC drain pipe for Split AC | N/I+r | 25.00 | | |
| a b | 32 mm dia PVC drain pipe for Split AC 32 mm dia PVC drain pipe for Cassette AC | Mtr. Mtr. | 15.00 | | |
| v | oz IIIII dia i vo didiri pipo foi Odosotto AO | IVIU. | 10.00 | | 1 |

| 4 | Providing and fixing Stabilizer with 3 step relay and input voltage range of 140-280 V and output to be 230 V (Blue bird/ Logic state/ Inline/ V-gourd) (copper winding). | | | |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------|--|
| а | 4 KVA (For 1.0/ 1.5 TR Split AC) | Nos. | 2.00 | |
| b | 5 KVA (For 2 TR Split AC) | Nos. | 1.00 | |
| <u> </u> | | | | |
| 5 | Providing and fixing of lockable caging for outdoor unit grouted on wall or on roof with open able shutter made of 10 X 10 mm MS square bars placed vertically @ 5" c/c welded with 40 X 3 mm MS flat all- round. Item includes all necessary hardware, priming coat, synthetic enamel paint, hanger, clamps other accessories etc. All complete as per approval and instructions of the Architect/ employer. | | | |
| а | For 1/1.5/2 TR Hi Wall split units | Nos. | 3.00 | |
| b | For 2/3/4 TR Ceiling mounted cassette unit | Nos. | 4.00 | |
| | | | | |
| 6 | Supplying and laying of Extra Electrical interconnecting control cable from indoor to outdoor of size as specified by the manufacturer suitable for 1.0 TR/ 1.5 TR/ 2.0 TR Split type AC. | Mtr. | 15.00 | |
| 7 | Supplying and laying of Extra Electrical interconnecting control cables from indoor to outdoor of size as specified by the manufacturer suitable for 2.0T/3.0T / 4.0 TR Cassette type AC. | Mtr. | 25.00 | |
| 8 | Supplying, installation and commissioning of automatic 24HRS. programmable TIMER of required capacity to run A.C. alternately (MDS / L&T / Other reputed make). | | 1.00 | |
| 9 | SALVAGE | | | |
| а | Disposal of window AC 1.5 TR as per the reserve cost including removal etc.as pe the direction of Engineer-incharge (RP-2000). | Nos. | -6.00 | |
| b | Disposal of voltage stabilisers installed with window Acs as per the reserve cost including removal etc.as pe the direction of Engineer-in-charge (RP-500). | Nos. | -6.00 | |
| | TOTAL | | | |

Note:- The rates quoted includes all other taxes, duties, loading, unloading, transportation, other expenses etc to site.

only GST will be paid Extra