

Date:

SBI, YERRAGUNTALA BRANCH, ALTERNATIVE PREMISES
ESTIMATE FOR AIR CONDITIONING WORKS

Sl.No.	Description	UOM	Qty.	Rate (Rs.)	Amount (Rs.)
Part A:					
1	Supply of inverter type Cassette type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Minimum 3 star rating 3.0 TR Capacity	Set	5		
2	Supply of inverter type Hi-wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Minimum 3 star rating 1.5 TR capacity	Set	4		
	Sub Total Part A				
Part B:					
1	Installation, testing and commissioning of Cassette and hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.				
A	Cassette type	Set	5		
B	Hi-wall mounted type	Set	4		
2	Supply and erection of suitable size of MS stand for outdoor units	Set	9		
3	Supply , installation ,testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers				
A	Suction line & liquid line for Cassette units	RM	70		
B	Suction line & liquid line for hi-wall mounted units	RM	30		
4	Drain line from indoor to outside as per standards. Drain should properly taken to the ground level.	RM	120		
5	Supply, laying, testing and commissioning of flexible electrical control cable of suitable size for casette units	RM	85		
6	Supply, laying, testingand commissioning of flexible electrical control cable of suitable size for HWM units	RM	45		
7	supply, installation, testing and commissioning of 24hr duty timer for alternative cyclic operation of 2 Acs at ATM room complete with required wiring etc	Set	1		
	Sub Total Part B				
	Grand Total (Part A + Part B)				

GST as applicable