

PRICE BID FOR THE CIVIL WORKS IN SBI BRANCH AT SIRHIND CITY

CIVIL WORKS		ESTIMATE			
S No	DESCRIPTION	QTY	UNIT	RATE	AMT
1	DISMANTLING WORK:				
i	Dismantling and removal of malba of existing B.M. Room toilet, including brick walls, doors, windows, floor tiles, wall tiles of existing B. M. toilet Ladies & Gents toilets ceilings etc.	1	job/Ls		
ii	Dismantling and disposal of malba (of unwanted items) of existing branch, tables, counters, partitions, storage, dismantling and removal toilets' glazed tiles on walls 7 floor, removal toilets' fixtures, pantry etc. Split AC's, Alum. Doors windows, wall panelling, electrical items, data and telephone cables, electrical D/B's etc. and keeping running of branch with temporary connections	1	job/Ls		
2	Construction of 6" thick cement concrete block wall for toilets, pantry, UPS.	520	Cuft		
3	Cement plastering 12mm/18mm th. (1:5) on new/old constructed walls.	2200	Sqft		
4	Constuction of RCC lintols including steel reinforcements 4 Nos 16mm dia m.s. rods, rings 8 dia tor @ 5" C/C, shuttering, scaffolding etc. over doors & windows openings	15	Cuft		
5 i	Construction of Pantry slab (RCC 1:1.5":3), 3" thick, 10'-0" long, 20'-0" wide + 3" embedding in walls on all three sides of slab, with 10 mm dia tor steel @ 5" C/C in both directions	24	Sqft		
ii	P/F Single bowl S.S. Sink with complete fitting at base of sink for the disposal of waste water	1	No		
iii	P/F black granite (250/- sqft Cost in the market) with making moulding grinding and polishing.	30	Sqft		
iv	P/F vitrified tiles of size 4'x2' as per colr/shade appropved of Nitco/Johnson/Kazaria/Somany.	250	Sqft		
v	P/F uPVC concealed piping work 1" dia in kitchen from W.T. as well as fresh water supply with all required elbows, tees, nipple, stop corks etc.	1	Job		
vi	Providing 7 fixing C.P. Taps long body of Parryware model Model No. G1405A1) including cups, nipples etc.	2	Nos		
vii	Providing & fixing Small body taps (Parryware Model No. G1404A1)	1	No.		
vii	P/F PVC floor trap with C.P. jali and 2" PVC pipe for the disposal of waste water upto the existing toilet.	1	Job		
6	Renovation / furnishing of GENTS TOILET (12'X5'-0"), LADIES TOILET (8'x5') & Manager toilet (5.5'x5')				
i	Small body taps (Parryware Model No. G1404A1)	3	Nos		
ii	Long body taps (Parryware Model No. G1405A1)	1	Nos		
iii	Angle Valves / Stop Cocks (Parryware Model No. G1453A1)	14	Nos		
iv	PVC Connection pipes	9	Nos		
v	Waste pipes for Sink complete	1	Nos		
vi	Waste pipes for Wash Basin complete	3	Nos		
vii	European W.C. (Flair mModel or equivalent)	3	Nos		
viii	Wash basin QubeX Model	3	Nos		
ix	Seat cover	3	Nos		
x	Jet spray for WC	3	Nos		
xi	Towel Rail 2'-0" long	3	Nos		
xii	Soap Dish	3	Nos		
xiii	Mirror 18"x24"	3	Nos		
xiv	Towel ring	3	Nos		
xv	Urinals	3	Nos		
xvi	P/F Floor Tiles 12"x12" anti skid of Nitco/Johnson/Kazaria/Somany.	150	Sqft		
xvii	P/F vitrified tiles of size 4'x2' with recommended chemical, joints filling on wals, as per color/shade appropved of Nitco/Johnson/Kazaria/Somany.	650	Sqft		
xviii	P/F uPVC concealed piping work 1" dia in all three toilets' to wash basins, W.C.'s, urinals, general taps etc. from W.T. for water supply with all required elbows, tees, nipple, stop corks etc.	3	Toilets		

xix	P/F PVC floor trap with C.P. jali and 3" PVC pipe for the disposal of waste water drom wash basin or and from F.T. to F.T. and then upto the existing sewer line	7	Nos		
xx	P/F 4" dia PVC with "S" or "P" or elbow trap as reqd for W.C's including 4" dia PVC pipe from W.C. to existing Sewer/I.C.	3	Nos		
7 i	Construction of I.C. chamber with PVC cover of size 2'x2' for sewer disposal of B.M. toilet.	3	Nos		
ii	Construction of G.T. chamber with PVC cover of size 12'x12' for the sewer/waste water disposal of B.M. toilet.	1	No.		
iii	P/laying 4" dia PVC sewer line embeded in cement concrete.	65	Rft		
iv	P/laying 3" dia PVC sewer line embeded in cement concrete.	15	Rft		
8	Providing and fixing wihite 18 guage sheet pressed steel (Door size:2'-6"/3'-0"x7'-0"ht) chowkhats for pantry, toilets, of size 4"x2.5" (single pataam) including 1.25" thick flush doors with teak wood lipping, 1mm thick laminate on both sides, all required hardwares, such as door glass, handles, hinges, etc.	5	Nos		
9	Providing and fixing wihite 18 guage sheet pressed steel ventilator frame (size:2'-6"x1'-4"ht) chowkhats for toilets of size 4"x2.5" (single pataam) including fixed glass 5mm thick, to be fixed with wooden / putty etc.	3	Nos		
TOTAL					
GST 18%					
TOTAL WITH GST					

CONTRACTOR

