

BILL OF QUANTITIES FOR INTERIOR AND FURNISHING WORK FOR NEW TB JETPUR BRANCH					
Sl. No.	Description of Item	Qty.	Unit	RATE	Amount
	<b>PARTITIONS AND DOORS</b>				
1	<p>Providing and fixing in position Full /Low Height Partition consisting of aluminium hollow section of 50x50mm size 1.5mm thick of JINDAL/ INDAL conforming to ISI 303 standard as internal frame structure placed horizontally &amp; vertically in 600 x 600mm interval , except skirting member which shall have 2x50x50mm members at reqd.spacing and 6mm wide grooves or as required as per architectural drawing. The framing shall be fixed with 6 mm thick MR grade ply of approved make firmly screwed to the aluminium frame on either side.The exposed surface to be pasted with 1.0mm thick laminate of approved pattern, make &amp; colour. Items include providing and fixing glass in side partitions of public counters or in full height partitions complete with bevelling of size 1.5" on free standing glass in lowHeight Partitions as per steem beech wood moulding on free end of Low Height partition, 12x12mm steem beech wood requirement,making grooves providing 65x31mm beading. Item also includes providing and fixing 100mm wide skirting of 1mm thickness. MettalicLaminate as per approved sample on exposed partition surface as per architectural drawings cost to include cost of silcon filling ,providing and applying melamine finish on wood surface/grooves including providind and applying 2-3 coats of VIPER over a coat of anti-termite paint where ever required. complete to the satisfaction of Architect / Bank's Engineer.cost to include high glossor texture laminate as per approved sample.</p> <p>Note1: Surface measurement for one face and visible area below the false ceiling will be made for payment.In case of height variationon both sides of partition,average height shall be taken for payment. Note2: Rate inclusive of Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing &amp; direction</p>	SQM	42		
2	Item same as item no 1.1 but providing 12mm thk bison board with 1.00mm thk laminate instead of 8 mm thk commercial ply. In inner surface or both sidesof partionions	SQM	5		

Sl. No.	Description of Item	Qty.	Unit	RATE	Amount
3	<b>PANELLING</b> Providing and fixing Wall Panelling consisting of 2" x 1 " 18 gauge section placed at 2'0x2'-0" horizontally and vertically with Unanodised Alluminium size 1.5mm thick of JINDAL/ INDAL confirming to ISI 303 standard as internal frame structure (as per site requirement) framework. The framing shall be fixed with with 6mm thick MR grade ply of approved make firmly screwd to the aluminium frame on either side finished with 1mm th (high glossor texture) laminate as per approved sample. Item includes providing and fixing 12x12mm steem beech wood beading making 6 mm grooves complete with polish & melamine spray finish on wood surface/grooves as per architectural drawings finished with 1mm thick laminate. Item includes providing and fixing 100mm wide skirting of 1mm thick mettalic laminate as per approved sample. <b>Note:</b> Surface measurement for one face & visible areas below false ceiling will be made for payment.	SQM	98.00		
4	<b>PANELLING WITH ALCO-BOND PANELS (ALUMINIUM FRAMES)</b> Providing and fixing panelling on external wall "Alco-bond" with necessary alluminium framed panelling (using 2" x 1" sections) as per the company specifications. The rate is inclusive of all fixtures and fittings (with sealant) for proper finish. (Branch & Wealth Mgmt )	SQM	43.00		
5	Providing and fixing 750mm deep Public Counter fabricated out of 19mm. Thick commercial range Ply finished with 1.0mm thick High gloss laminate or duco finish with high gloss PU coating as per approved sample on all exposed surfaces, including top, front of drawers & sides etc. All exposed internal and external surfaces leg & CPU space, foot rest, steel Key board, drawer area, to be finished with 1.0mm thick laminate inlay of different colour with 75mm Straight edging or full round edging on both sides ( except joint of cabinet) complete with edge polish, transaction counter fabricated out of 12mm thick toughened Eteched glass in front (acid wash ) 500mm wide & fixed at 900mm height with stainless steel studs as per approved sample and as per architectural drawings. Front glass panel shall be 1'-6" high and shall be fixed between transaction counter & public counter. The rate shall include providing and fixing 0.8mm thick laminate fixed over on all visible & invisible internal surfaces of shutters, drawers, internal side of back ply, both sides of vertical & horizontal members with wood moulding/ wood edging, 2mm thick edge binding tape fixed with adhesive on edges of board /ply as required, 100mm wide Skirting with necessary and beech wood moulding with high gloss PU coating, hardware handles as per approved sample, autoclosing hinges for shutters as per approved sample, telescopic sliding channel and locks. Item includes providing and fixing 1mm thick laminate of approved colour on apron of counter, p/f stainless steel cable manager etc. complete to the satisfaction of Architect/ Bank's Engineer. Note: Rate shall be inclusive of cost of cutting hole complete.	RM	4.6		
6	<b>Writing Counter (Circular)</b>				
	Providing and fixing Writing desk with dia of 900mm and height 1200 mm with top of 12mm thick toughend glass with bevelled edge supported on base of 19mm thick commercial board and teak wood finish laminate complete with base plate & 100mm high skirting finished with decorative mettalic laminate as per drawing etc. complete to the satisfaction of Architect/ Bank's Engineer. Reference drawing of BM Table is part of this tender.	Nos.	1.00		

Sl. No.	Description of Item	Qty.	Unit	RATE	Amount
<b>7</b>	<b>TABLES</b>				
	MANAGER TABLE: Upgradation of Manager's/officer's Table table top finished with 1 mm thick high glossor laminate with wood moulding,12mm thick etched plate glass complete.Item includes providing and fixing drawers, shelves,shutters, 100mm wide skirting of mettalic decorative laminate polishing the exposed steem beech wood surface with high gloss PU coating.Item includes providing and fixing 0.8mm thick laminate/enamel painting on all visible & invisible internal surfaces of shutters, drawers, internal side. Providing and fixing stainless steel cable manager inclusive of cutting & making hole and making good the surface etc.complete to the satisfaction of Architect/Bank's Engineer.				
	Existing size	<b>Nos.</b>	<b>6.00</b>		
<b>8</b>	<b>UPGRADATION OF SIDE CABINETS</b>				
	Upgradation of existing side cabinets all exposed surfaces, side side & front finished with 1mm thick laminate, complete colour with shelves, drawers,shutters, 100mm wide decorative mettalic laminate skirting as per approved sample. Item includes providing and fixing necessary hardware,hinges,locking arrangement with lock, telescopic steel channel runners ,handles, stainless steel wire manager as per approved sample. Enamel paint if required be on all visible & invisible internal surfaces of shutters, drawers internal side of back ply, side and both sides of vertical, horizontal members with teak wood moulding/teakwood edging and 2mm thick edge binding tape fixed with adhesive on edges of board/ply as required etc. complete to the satisfaction of Architect/Bank's Engineer.				
	Existing size	<b>Nos</b>	<b>9.00</b>		
<b>9</b>	<b>FALSE CEILING</b>				
<b>A</b>	<b>ARMSTRONG TILE CEILING:</b> Providing and fixing False Ceiling with Mineral Fibre Accoustic Ceiling Tiles of Armstrong with with narrow reveal (NR/E), having noise reduction properties laid on exposed grid system with 15mm side SilhoutteXL 6mmtype black inside 'T'section flanges of white colour, main runners spaced at 1200mm centers securely fixed to the structure soffit with approved hangers at 1200mm max. centers, 1200mm flush fitting crossed tees interlocked between main runners at 600mm centers to form 1200x600 modules. 1200mm cross tees shall be crimped in 600x600mm module formed by fixing 600mm long flush fitting cross tees centrally between the 1200 cross tees, ceiling tiles of visual pattern tiles 8581M of size 600x600x15mm placed in the grid etc. complete to the satisfaction of Architect/Bank's Engineer. Note: Rate shall include making necessary cutouts or openings for light fixtures etc. complete. .	<b>SQM</b>	<b>130</b>		
<b>B</b>	<b>GYPSON BOARD CEILING:</b> Providing and fixing 12.5mm thick Gypsum Ceiling Board False Ceiling in horizontal, vertical surfaces moulded corners & offsets as per architectural drawing which shall include providing and fixing roll formed G.I. perimeter channels of sizes27x.5mm thick having one flange of 30mm along the perimeter of the ceiling fixed to the brick wall or partition with help of rawl plug or screw including ending of G.I.intermediate channels of size 45x9mm thick with two flanges of 15mm thick each from the soffit @1200mm c/c with steel /G.I.hanger of width 25mm & 0.5mm thickness fixed to soffit with G.I.cleat & steel expansion fasteners of 0.5mm thickness having knurled wedge of 51.5mm, two flanges of 26mm each with tips of 10.5 mm fixed to the intermediate channel with the help of converting clips in a direction perpendicular to the intermediate channel of 350mm c/c 12.5mm taper edge gypsum plaster board confirming to I.S.: 2095,1982 shall be screwed at 230mm c/c with screw fixing done mechanically with suitable attachment of the tapered & squared edges of the boards as recommended by the manufacturer finished with two or more coats of oil bound distemper over acoat of primer. Item includes extra frame work for necessary hatch doors/ opening upto 600mmx600mm or as per requirement with 19mm commercial board wherever required including necessary brass hinges, screws & finish smooth as directed The rate shall include the cost of extra frames for A.C openings light fixtures,speakers & coves etc.complete to the satisfaction of Architect/ Bank's Engineer. Note: Only horizontal base area shall be measurement for payments.	<b>SQM</b>	<b>90</b>		
<b>10</b>	Putty: Providing and applying waterproof putty on walls and columns (average 2mm thk). The rate shall include scrapping, leveling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the window and door frames.	<b>Sqmt.</b>	<b>10</b>		
<b>11</b>	<b>PLASTIC EMULSION</b> Providing & applying plastic emulsion paint on walls, columns & ceilings (other than false ceiling). The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread, quality finish (roller finish) of approved make , shall be provided.	<b>Sqmt.</b>	<b>15</b>		

Sl. No.	Description of Item	Qty.	Unit	RATE	Amount
12	Upgrading Storage Cabinets with 1mm thick high glossor texture laminate Providing and fixing decorative mettalic laminate skirting as per architectural drawings. The rate shall include providing and fixing 0.8mm thick laminate/enamel painting over on all visible & invisible internal surfaces of shutter, drawers & internal side of back ply side and both sides of vertical & horizontal members with 2mm thick edge binding tape fixed with adhesive on edges of commercial board/ply as required. Item also includes providing and fixing necessary hardware, stainless steel auto closing hinges as per approved sample, handles as per approved sample, locking arrangement, 75mm brass tower bolts, locks, telescopic channels for drawers as per site requirement etc. complete to the satisfaction of Architect/ Bank's Engineer	sqm	11		
13	Providing and fixing 12 mm thick, toughened glass Door, inclusive of Providing and fixing 12mm thick toughened, fixed, side glazing panels same as Door and with frameless fittings of DORMA/OZONE make, with following parts, viz: SM1040/equivalent forover/side panel, SM 1041/equivalent connector for side/upper panel, SM 1020/equivalent upper patch, SM 1010/equivalent bottom patch, SM 1049/equivalent E floor lock, SM 1052/equivalent strike plate BTS 84, floor spring including Providing and fixing of DORMA/OZONE make handles TG 9159/equivalent EQ-S as per approved design, grinding & polishing smooth of glass edge with cutting & making good the floor wherever required etc complete to the satisfaction of Architect/ Bank's Engineer. <b>Note:</b> Rate inclusive of Providing and Fixing Frosted polyester film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction				
a	Toughened Glass Door all accessories as required only.	SQM	5.00		
b	Fixed Glazing	SQM	36.00		
14	P & S of Visitors sofa. The seat shall be made out of 19 mm BB in a box form. The back shall be made out using internal wooden frame work of size 2"x1 1/2" covered with 6 mm ply. It shall be covered with 100 mm & 50 mm th. 40 density u foam in seat & back respectively. This should be again covered with 14 mm th. 40 density u foam with madarpat cover on it & upholstered of suggested shade & finish in seat & back on all open visible sides with basic rate of Rs.900/- per meter. It will have wooden handles as / drawing. outer length with armrest will be considered for measurement purpose.	No. of seats	8.0		
15	Supplying and installation 3'-0" x 1'-9" x 1'-3" height Center Tepoy as follows.	1.00	NO		
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.				
	GRAND TOTAL				