

STATE BANK OF INDIA
PRICE BID FOR ELECTRICAL WORKS OF ASSOCIATION OFFICES AT AO MUZAFFARPUR

SR.	ITEM DESCRIPTIONS	UNIT	QTY.	RATE	AMOUNT
1	<p>(A) COMPUTER SOCKET OUTLET WITH WIRING Computer socket outlet cluster point including supply and fixing of modular type socket outlet clusters components and its wiring from CDB, complete in all respect as detailed below. Each computer socket outlet cluster comprising the following 4 Nos. 6/10A 5 pin modular type International sockets 1 No. 16A modular type common controlling switch with indicator on table top with 2 Nos. 2.5 Sq.mm. + 1 x 1.5 Sq.mm. (green colour for earth) PVC insulated copper wire in pre-laid (as per ISI) PVC conduit including interconnection, painting etc. as required to be completed in all respect from CDB to Computer point.</p>	NO.	3		
2	<p>POINT WIRING: Point wiring with 1100 V grade 3 nos. single core 1.5 sq.mm. and 1 for common earth by looping method) PVC insulated stranded copper conductor wire (IS:694) through suitable size M.S. conduit (ISI marked embossed on conduit surface) by thred cutting, complete with junction box, circular box, elbows, bends, couplers and other accessories on surface above false ceiling or concealed by chase cutting on wall from light & fan switch board to light, fan & 6A socket outlet on the same switch board or separately mounted switch board. The work includes supply and fixing of all materials such as modular type 6A switch for light and fan point, 6A 2/3 pin shuttered socket outlet with switch in each switch board, 3 plate ceiling rose / angle or batten holder etc. as required. The point wiring also includes circuit wiring with 1100 V grade 2 nos. single core 2.5 sq.mm. + 1 no. single core 1.5 sq.mm. PVC insulated stranded copper conductor cable (IS:694) through suitable size M.S. conduit as described above from DB to switch board, interconnection, mending good all damages to original finish, painting etc. It is to note here that the rate for switch to point for the length of wire below 4m shall be payable on actual basis.</p>				
A	1 Light control by 1 switch	NO.	6		
B	Ceiling Fan wiring with electronic regulator	NO.	1		
C	3 pin 6/10A modular socket with switch in each board	NO.	1		
3	Supply & Fixing of 18W LED T5 Batten fitting of Syska / Phillips / Wipro / CG / HPL / Mescab / Century make complete with all accessories.	NO.	5		
4	Supply & fixing of company made approved metal clad socket with 25A SP MCB/modular type 20A Socket & top with indicator with 25A SP MCB	NO.	1		
5	With 2 No. 4sqmm + 1x2.5sqmm PVC insulated copper wire in PVC Conduit pipe	MTR.	20		
6	With 2 No. 2.5sqmm + 1x1.5sqmm PVC insulated copper wire in PVC Conduit pipe	MTR.	35		
7	Supply & fixing of exhaust fan complete with all respect. (Make: Polar, Orient, CG, Havells, Usha, Mascab)	NO.	2		
8	Supply & fixing of ceiling fan complete with all respect. (Make: Polar, Orient, CG, Havells, Usha, Mascab)	NO.	2		
9	Supply & Fixing of 36W-2'x2' LED Panel light recessed mounted of Syska / Phillips / Wipro / CG / HPL / Mescab / Century make complete with all accessories. Syska cat no. SSK-PAB-	NO.	2		
10	Supply & Fixing of 15W LED Downlighter recessed mounted of Syska / Phillips / Wipro / CG / HPL / Mescab / Century make complete with all accessories.	NO.	3		
11	<p>Air Conditioners :- Supply and installation of Split Type 1.5 tonne capacity Air-Conditioners (5 Star, inverter) of (Voltas/Blue star / hitachi / carrier / o-general / LG / Panasonic/Godrej/Lloyd) including 4 KVA automatic stabiliser of v guard/Sen & Pandit and fixing of outdoor units with steel stand all accessories complete in all respect. NOTE- The existing AC is very old and not working, need to replace with new AC.</p>	NO.	2		
12	1x20A 3 Pin modular socket with switch on separate switch board	NO.	1		
RS.(Total in word):-		TOTAL			

NOTE:-

***All safety norms, I.S.Code, I.E.Rules must be followed. In case of any confusion please contact to the Bank's Engineer.**

*** Rate are inclusive of transportation charge etc. but exclusive of GST.**