

PRICE BID OF CIVIL and ALLIED INTERIOR & FURNISHING WORK						
OF SEWA AND ASSOCIATION OFFICES AT AO MUZAFFARPUR						
S.NO.	ITEM	PARTICULARS	UNIT	QTY.	RATE	AMOUNT
1	<b>PLASTIC EMULSION PAINT</b>	Providing two or more coats of Plastic emulsion paint over a coat of cement primer of ICI, Berger Paints (India Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do—to complete job.	Sq.m	563		
2	<b>CERAMIC TILES</b>	Dismantling of floor & wall tiles,CHISELLING over existing surface and Providing and laying Ceramic glazed tiles (thickness to be specified by the manufacturer) of ist quality conforming to IS :15622 of approved make in colours such shades except white , Ivory ,Grey , Fume Red , Brown , laid on 20 mm thick Cement motar 1:4 (1cement: 4 coarse sand) including pointing the joints with white cementand matching pigment etc., complete.(MAKE AS PER APPROVED BY SBIIMS LIKE NITCO , , SOMANY, johnson , KAJARIA) with all complete job. TILE MUST BE DOUBLE CHARGE TILES.	Sqm	52		
3	<b>BIB COCK</b>	BIB COCK (TWO IN ONE):Providing and fixing heavy duty 15 mm dia C.P. brass two in one bib cock of Hindware/jaquar/Parryware with wall flange all complete as per standard specifications and as directed by the Engineer-in-Charge.	NO.	2		
4	<b>WASH BASIN</b>	Providing and fixing corner wash basin of make Hindware/jaquar/Parryware with C.I. brackets/ rack bolts, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with provision of pillar tap with all complete job as directed by EIC.	no.	1		

5	<b>WC PAN EUROPEAN TYPE</b>	WATER CLOSET (ENGLISH TYPE) :Providing and fixing first quality European water closet of approved make EWC Constellation in white in colour including providing and fixing cistern height 80cm, width 36 cm with necessary porcelain, P/ S trap heavy duty plastic seats of approved manufacturer such as commander in approved colour, CP brass hinges, buffers etc., all complete including fixing in position with necessary holes, providing and fixing CP brass screws and connecting the outlet to the soll stack including testing the joints all complete as per specifications and as approved by the Engineer-in-charge. The water closet must be of <b>hindware/jaquar</b> only.	NO.	2		
6	<b>WPC DOOR</b>	Providing and fixing WPC type door of 32mm thickness with wpc frame as approved by SBI and Indian specs for washroom including the cost of tower bolt side bolt door handle and all other fixture and with all complete job as directed by EIC.	Sq.m	5		
7	<b>UPVC PIPE</b>	Providing and laying of 100/75 mm Upvc pipe of su-preme make or as per approved by EIC.including the cost band,tee or other fixture and all complete job.	m	25		
8	<b>HEALTH FAUCET</b>	Providing and fixing of health faucet of Jaquar/hindware/parryware make only	NO.	2		
9	<b>CONNECTION PIPE</b>	Supply & Fixing of connection Pipe from Angle cock /Stop cock to Piller Cock.	NO.	4		
10	<b>C.P.JALI</b>	Providing and fixing of C.P.Jali ist quality pure Stainless Steel.	NO.	6		
11	<b>NAHANI TRAP</b>	Providing and fixing of Nahani trap of supreme	no.	2		
12	<b>STOP COCK/ANGLE COCK</b>	Providing and fixing stop cock/angle cock of jaquar/parryware/hindware make only	no.	8		

13	<b>CPVC PIPE</b>	CPVC/upvc Pipe of hot and cold water resisting of thickness 15mm,32mm including the cost of T BAND with all connection pipe and as required with all complete job	m	10		
14	<b>MIRROR</b>	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : Rectangular shape 453x357 mm.	NO.	3		
15	<b>GRANITE</b>	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and po-lishing etc. all complete as specified and as directed by the Engineer-in-Charge : 11.55.1 Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.ALSO FOR TABLE TOP LIKE STRUCTURE OF WASH BASIN.	Sq.m	1		
16	<b>PLASTER</b>	Repair of existing and /or applying new Plaster wherever required of 1:4 cement mortar of 12mm to 20mm thickness with approved brand of cement and coarse sand. This includes supply and use of seepage control materials. The repair shall be done by removal of loose plaster by making grooves of atleast 6mm and width 12mm in both direction from the crack line.	Sqm	36		
17	<b>SHOWER</b>	Providing and fixing of SS shower of minimum 100mm wide of Hindware/Jaquar	No.	1		

18	<b>DISMANTLING OF DOOR/WINDOW/VENTILATOR</b>	Dismantling of existing door/window/ventilator frame and panel alongwith iron grill,glass panel etc. manually or by mechanical means at all height and location. The rate to include stacking the serviceable material i.e.grills, railings, wood items like door frames, window frames, as directed at site and carting wayunserviceable material / debris to a place approved by Municipal corporation. The work also includes levelling the ground after carting away.	No.	3		
19	<b>PANELLING</b>	<p>Providing and fixing wall, beam &amp; Column Paneling as per drawing &amp; design :</p> <p>The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally &amp; vertically.</p> <p>The framework of aluminium box section is to be fixed by means of Aluminium angles of required size for proper fixity.</p> <p>The framework is to be covered by 6 mm thick <b>BWP</b> plywood /Exterior Grade MDF board of Green/Century or equivalent on exposed side with suitable fix-tures.</p> <p>The surface is to be finished with 1 mm thick high gloss laminate of approved shade &amp; make.</p> <p>Provisions are to be made for fixing LED strips.</p> <p>The work is to include all necessary materials, accessories, labour, tools &amp; tackles and also allow provisions for electrical, computer &amp; telephone wiring conduits, switch boxes etc.</p> <p>Executed elevation area is to be measured for finished work.</p>				
		With 12 mm thick MDF board fixed on aluminium tubular frame finishing paneling surface with high gloss PU paint/1 mm thick high gloss laminate-In the wall.	Sq.m	42		

20	<b>BANNER BOARD AND LOGO FRAMING</b>	Providing and fixing of grass board with velvet of size upto 5'x6'. This includes all round protection with 12-19mm plywood/MDF and 0.08mm mica of color as directed by EIC/Bank/authorized official.	Sq.m	10		
21	<b>UNSKILLED LABOUR SUPPLY</b>	Supply of unskilled labour for miscellaneous works other than mentioned above. Supply to be done as per requirement and to be entered in site order book. Payment (including VDA ) shall be done on the basis of entry in order book.	Man days	15		
22	<b>WALL PUTTY</b>	Providing and applying wall putty of 2 mm average thickness over plastered & white washed/ old painted walls & ceiling to prepare the surface even and smooth compete as per direction of BANK/eic.	Sqm	332		
23	<b>URINAL</b>	URINAL :Providing and fixing wall hang urinal of approved make flat back large in white colour and size of (H x W x P): 59 c.m x 39 c.m x 37.5 c.m white in colour fixed with the help of angle brackets including providing water spreader, domb, and providing and fixing bottle trap all complete as per the directions of the Engineer-in-charge. The urinal shall be of Hindware/jaquar/parryware.	no.	1		
24	<b>BIBCOCK</b>	Providing and fixing of bibcock of Hindware/parryware in the baths.	Nos	2		
25	<b>ALUMINIUM SLIDING WINDOW</b>	Providing and fixing of powder coated aluminium sliding window in two track with 4 mm float glass as per specification. Slope shall be towards exterior wall. This includes labor, tools, tackles, transportation and lifting charges. The executed area of finished work shall be measured.	Sqm	5.5		

26	<b>VITRIFIED TILE FLOORING</b>	Providing, laying and fixing vitrified flooring / skirting/dado in specified area with vitrified tiles approx size 600mm x 600 mm X 8mm in light colours floor tiles specified by the Bank as per approved shade and colour of standard make i.e. Naveen/ Johnson/Nitco/ Euro(Premium quality) only, with the help of Pedilite or equivalent make pasting chemicals after required chipping and leveling the surface by 1:4 cement sand mortar if required all complete including cost of materials, labours etc.	Sqm	17		
27	<b>STORAGE CABINET and GLASS SHOWCASE WITH LOCK ETC</b>	Making and fixing low/FULLheight type storage cabinet with drawer and cupboard with shelf as per the drawing / design all made of 19 mm thick BWP block board of Green/Century /Mayur or equivalent/ Exterior Grade MDF board of Green/Century or equivalent top and front laminated with 1.0 mm thick laminate of Green/Marino /century or equivalent in required shade as of old items available in the HR cell. The top edges shall have Gamhar wood moulding. Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be melamine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per approved materials Colour laminate and specifications . The depth should be 30" as of available cabinets. rate includes handle, lock and other fittings , tools, tackles and labor cost. (Provision of cabinets for records & documents in Staf association and SC/St office)	Sqm	3.7		
28	<b>Brick work with bricks of class designation 100A including</b>					
	(A)Half brick masonry(125mm)		Sqm	7		
29	<b>2x2 GYPSUM TILE</b>	Providing and fixing gypsum tile of size 2'x2' on the existing tile grid and other repair work of false ceiling as per direction of EIC/bank.	Sqm	6		

30	<b>ROLLER BLIND</b>	Providing & fixing of roller blind (vista level or classic/ or equivalent of standard make) in off-white or any approved color on all windows & opening of C.M's chamber. All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All complete work as per drawing, design Specification and direction of Engineer-in-charge /Bank.	Sqm	6		
31	<b>HYDRAULIC DOOR CLOSER</b>	Providing and fixing hydraulic Hardwyn, Everite or approved make equivalent door closures of Hardwyn, Everite or equivalent approved brand and sample – all complete as per instructions of the Bank. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank.	2	NO.		
<b>RS.</b>			<b>TOTAL</b>			

\* ABOVE PRICE IS EXCLUDING GST BUT INCLUSIVE OF OTHER GOVT./ STATUTORY TAXES.

\* GST PAID EXTRA BY THE BANK AS PER RULE.

\*All work to be done as per IS specification

\*Brand mentioned in price bid shall be final and abiding.

(SIGNATURE)  
**AUTHORIZED SIGNATORY**