

PRICE BID

BOQ OF FURNITURE WORKS AT TRANSACTION BANKING HUB, SBI, AHMEDABAD.

A FURNISHING WORK

Sr. No.	Description	Quantity	Unit	Rate in figures	Rate in words	Amount
Note :	Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage & removing of all existing furniture items and relocating the same as per instruction by bank etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills					
1	TABLES					
	Note : for all work stations					
	FINISHING DETAILS IN NUTSHELL:					
	1) Table Top : 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished					
	2) Front Apron & Sides: 1.0 mm thick Dark Laminate					
	3) Facing of Drawers: 1.00 mm thick laminate finish					
	The W.S. should have Ready Made Foot Rest. High impact polysterene with chrome plated metal structure of approved make.					
	There should be provision for cable manager(Metal Cable Manager) system with necessary cutouts in top surface					
	<i>C.P.U. trolley with castors/roller supports/ Nylon castors.</i>					
	Key board tray with mouse pad made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it.					
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete					
	Heavy duty <u>telescopic full extension</u> sliding channel of approved make shall be used in all drawers.					
1A	AGM TABLE SIZE: 6'-0" X 2'-9" X2'-6" HT. with Laninate finish on Table Top , sides and all other visible surfaces etc complete as follows	1.00	NO			
	Supplying and installation of Table as per the following description : Size 6'-0" x 2'-9". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Drawers of size of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Ready made metal Key board with mouse pad of approved make shall be provided. Exposed surfaces of darwers shall have laminate, All internal surface will have 0.60 mm thick balacing laminate					
	Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing					

	Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.					
	Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with lacquer polished etc complete as directed.					
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.					
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete.					
	All the surface without laminate / balancing laminate shall be lacquered polished of approved shade					
	As per drawing and instruction of Architect/Bank work to be Completed (FOR DETAILS REFER DRG. NO-)					
1C	Same as above Item-no-1 but Size: 5'-0"x2'-6" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces	1.00	NO			
1D	" L shape work station" 4'-0" x 2'-0" + 3'-0" x 1'-4"	24.00	NO			
	Same as above Item-no-1 but Size: 4'-0"x2'-0" + 3'-0" x 1'-4" side table with 2 Nos Drawer Unit and openable shutter with 1.0 mm thick Laminate finish on all exposed surfaces					
1E	Linear Table with Drawer (Laminate Finish on Table Top and Drawer shutter)	8.60	RMT			
	Providing and fixing Linear Table having width of 2'-0" using 18 mm thick Commercial plywood for Top and verticle support at 4'-0" c/c, Providing storage cabinet Two drawer and One shutter Unit at Every 4'-0" c/c,Group lock, SS handle in counter as directed complete. 1.0 mm thick Laminate finish on table Top and front side of shutter. Providing Foot rest of 3" x 1.5" in C.P. Teak wood with lacquered polish. All internal surfaces shall have 0.60 mm thick balacing laminate as directed.[FOR DETAIL REFER DRG NO-08]					
1F	MEETING ROOM TABLE Approx Size 6'-0"x 3'-0" with corian top	1.70	SQMT			
	Supplying and installation of Meeting room Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 36 mm thick Ply wood patta of required width on edges with 6mm thick corian top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.					

	Exposed edges of Table Top shall be made 54 mm thick by providing additional 36 mm thick ply wood patta of required width. [Only Top shall be measured for payment purpose.]				
1G	DINING TABLE Approx Size 5'-0"/ 6'-0"x 3'-0"	1.70	SQ MT		
	Supplying and installation of Dining Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. [Only Top shall be measured for payment purpose.]				
2	SIDE CREDENZA (SIDE TABLE)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				
	2) Front Apron & Sides: Frosty White Laminate				
2A	Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 1.00 mm thick Laminate finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. (For BM & Officer's) Rate for length Less then 3'-3"	1.80	SQMT		
	Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface shall be provided with 0.60 mm thick balancing laminate				
	(FOR DETAILS REFER DRG. NO-)				
3	Low Height Storage (LHS) with Top & Front laminate finished.	13.00	SQMT		
	Same as above Item No-2, but all external surfaces to be finished with Laminate (approved shades)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				

	2) Front Apron & Sides: Dark Laminate/Frosty white Laminate as per design & instructions					
4	P/F ELECTRIC CUB BOARD	3.50	SQMT			
	Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-3". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.					
5	P/F PANTRY PLATFORM CUB BOARD SHUTTER	1.50	SQMT			
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiante surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface					
6	LOW HEIGHT PARTITION WORK					
	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS	62.00	SQMT			
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.					
7	FULL HEIGHT PARTITION WORK					
	P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR	130.00	SQMT			

	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.[REFER DRG NO-]					
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.					
	GLASS DOORS AND PARTITIONS					
8	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance Door For Branch and E-Lobby	7.80	SQMT			
	Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings . The door will have patch lock, pti pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides, (Ozone Make OGH-55P11-25X400), fixed with the glass by making necessary cutouts & holes. The glass edges shall be polished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.					
	The patch fittings (Ozone make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.					
8A	Same as above item but P & F FULLY GLAZED PARTITION With Patch Fitting for front side of Main Entrance [FIXED PORTION] For Branch and E-Lobby	14.00	SQMT			
9	Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with door frame as follows.	3.25	SQMT			
	Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 32 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 32 x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk S S screws, Approved make Dead Lock, S.S Handles, 150 mm long Door stoppers, doorstop of approved make etc. All exposed surface /edges not laminated be provided with lacquer polish. Work to be completed as per drawing & instructions [REFER DRG NO-5]					

	PANELLING WORK					
10	P/F Wall panelling with laminate finishing for wall and Pillar etc	1.00	SQMT			
	Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. .					
10A	Providing and fixing 18 mm thick plywood of 4" height with 1.0 mm thick laminate finish runner patta on Storage Top / Table Top if required.etc complete as directed.	20.00	RMT			
11	P/A WALL PAPERS	1.60	SQMT			
	Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft					
12	VISITOR'S SOFA (1.83m long) Providing and fixing visitor's sofa without arms as per details given in the drawings and with fully upholstered sofas using 76mmx38mm and 51mmx38mm wooden frame, 3" cushion in seat and back, 19mm ply with tapestry (upto Rs. 200.00/ per meter) etc. complete as per design, details and specifications. 40 density U-form to be used.	6.10	RMT			
	FALSE CEILING WORK					
13	P/F GYPSUM BOARD FALSE CEILLING	100.00	SMT			
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.					
	After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.					
	Note : (1) Rate includes dismantalling of existing GYPSUM/ AMF/ POP false ceiling including stacking of servicable materials & disposal of unserviable materials & making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMT and paid in SqM (3) Only finished visible surface area shall be measured for payment.					
14	Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid	102.00	SMT			

	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose					
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications					
15	Supplying and installation 3'-0" x 1'-9"x 1'-3" height Center Tepoy as follows.	1	NO			
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.					
16	Providing and Fixing 2 nos sheets of 24"x 36" clear acrylic sheets (poster to be sandwiched in between). Outer sheet is 5 mm thick and bevelled crystal edge polished for 3/4" wide at 8-10 degrees on all sides and the Rear sheet is 5 mm thick flat etc complete as directed.	1.20	SQ.MT			
17	PAINTING WORK					
17A	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)	110.00	SMT			
	Providing and applying (with rollers only) Acrylic emulsion paint of required shade and approved make on old/new surface in two or more coats to give an even shade including the preparation of surface for painting, applying FULL primer and putty at all heights complete as per manufacturer's specification and as directed.					
17B	P/A SYNTHETIC ENAMEL PAINT	20.00	SMT			
	Providing and applying synthetic enamel paint at all heights of required shade and approved make on new / old work including scrapping / cleaning and preparation of surfaces for painting, applying primer and putty, with two or more coats of approved first quality enamel.					
	TOTAL COST					
Note:						
[a]	In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this					

[b]	All internal visible surface shall be provided with the 0.60 mm thick balacing laminate of aproved make & shade in the all S.W Counters/Tables/ Credenza,Storage Cup Board etc.					
B	CIVIL WORK					
Sr. No.	Description	Quantity	Unit		Rate	Amount
Note :	Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris , cleaning cutting wastage etc. all taxes, transportation, VAT ,Excise, Octroi etc. Excluding GST complete. [GST Will be paid as per Applicable at the time of payment of bills]					
	Basic Rate of Items are Excluding GST					
1	MASONRY WORK					
1.1	P/C 115 MM THICK BRICK PARTITION WALLS	10	SMT			
	Providing and constructing 115 mm thick brick masonry in partition walls with approved good quality bricks having a crushing strength of 35 kg/sq.cm for super structure in CM 1:4 (1 cement : 4 coarse sand) including scaffolding, racking out joints, reinforcement of 2 nos. 8 mm dia MS bars at every fourth leayer , curing etc. complete as directed at all heights as follows. (Rate includes the cost of MS bars or Iron hoop)					
	TOTAL OF MASONRY					
2	FINISHING WORK					
2.1	P/A POLYMER MORTAR PLASTER	10	SMT			
	Removing the loose plaster & concrete damages surfaces, cleaning the concrete surface with wire brush and reinforcement with rust remover, welding new reinforcement with Existing reinforcement if required applying epoxy resin to concrete & reinforcement surface of approved Brand and covering the surface with average 35 mm th. Polymer mortar using 1 bag cement 3 bag sand 5 lit Nitobond SBR Plus required water including scaffolding for repairing RCC slab, beam complete as directed (Rate including cleaning the site and carting away debris at all levels) .New reinforcement if required shall be paid as per Item No					
	TOTAL OF FINISHING					
3	FLOORING WORK					
3.1	P/F VITRIFIED TILES FLOORING [600mmx600mm]	10	SMT			
	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Basic price of Tiles shall be Rs. 600=00 per Sq. Mt (Excluding GST). etc. complete as directed. The rates include removal of existing Flooring up to bedding mortar . Its dispoasal .No additional sand bedding charges shall be paid for Electric trenches filling					

	Providing and laying 3 mm thick bubble guard of Cello make or equiv. for flooring protection and after completion of other furniture removing the same and carrying away as buy back etc					
3.2	P/L CERAMIC TILES FLOORING IN TOILET	4.2	SMT			
	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete. Sample of the tiles must be got approved from Architect/Bank. Rate includes dismantling of existing tiles flooring and disposal complete as directed. (Basic price of tiles shall be Rs.400=00 Per Sqmt)					
3.3	P/F CERAMIC TILES DADO ON WALL	20	SMT			
	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete. Sample of the tiles must be got approved from Architect/Bank. Rate all so includes backing coat of rough cement plaster. Rate includes dismantling of existing tiles and disposal complete as directed. (Basic price of tiles shall be Rs.400=00 Per Sqmt)					
	TOTAL OF FLOORING					
4	WATER SUPPLY WORK					
4.1	Providing and fixing concealed SCH-80 UPVC water supply line ISI approved mark, including all necessary specials, making zaries, making holes, cutting floors and making good after work is complete etc. complete as directed for. Pipe shall be Astral/Supreme make. at all levels					
[a]	- Do - for 25 mm dia line.	5	RMT			
[b]	- Do - for 38 mm dia line.	5	RMT			
4.1.1	Providing and fixing Open/concealed in structure SCH-80 CPVC water supply line ISI approved mark, including all necessary specials, making zaries, making holes, cutting floors and making good after work is complete etc. complete as directed for. Pipe shall be Astral/Supreme make. at all levels					
[a]	- Do - for 20 mm dia line.	5	RMT			
4.2	Providing and fixing following fixtures of Jaquar make or its equivalent with chromium plated disce etc. complete for concealed pipe lines.as directed by Architect					
	Jaquar CP continental ISI Marked or equivalent make					

[a]	Providing and fixing Bib Cock of Catalogue No - 037	1	NO.			
[a2]	Providing and fixing Auto closing system pillar Cock of Catalogue No - PRS-CHR-031 (PRESS MATRIC)	1	NO.			
[b]	Providing and fixing concealed stop cock of Catalogue No - 083	1	NO.			
[c]	Providing and fixing angle cock of Catalogue No -053	1	NO			
[d]	Providing and fixing Auto closing system angle Cock of Catalogue No - PRS-CHR-077 (PRESS MATRIC)	1	NO.			
[e]	Providing and fixing 25 mm, chromium plated brass Flush valve Catalogue No -1081A[Continental Range]. [Control Valve]	1	NO			
[f]	Providing and fixing 25 mm dia handle valve of approved Zoloto quality, for pipe lines etc complete as directed.	1	NO			
[g]	Providing and Fixing brass chromium plated soap dish of approved make & quality etc. complete as directed. Sample shall be got approved from Bank/Architect.	1	NO			
[h]	Providing and fixing brass chromium plated Napking Ring of approved make etc. complete as directed.	1	NO			
[i]	Providing and fixing Health Faucet [No 573]	1	NO			
TOTAL OF WATER SUPPLY						
5	SANITARY WORK					
5.1	Providing & laying & fixing UPVC SWR drainage line concealed/open in the structure as per details and requirement with necessary specials such as Y-2, T-2, offset, plugs, bends and filling the joints with approved adhesive including cutting of wall floor and making good after the work is cover etc. all as above. Pipe shall be Prince/Supreme / Astral make at all levels.					
[a]	For 75 mm dia 6 Kg/Cm2	5	RMT			
[b]	For 100 m dia pipe 6 Kg/Cm2	5	RMT			
[c]	Providing laying & fixing concealed 38 mm dia P.V.C. waste water pipe line complete as directed.	5	RMT			
5.2	P/F UPVC NAHNI TRAP	2	NO			
	Providing and fixing UPVC Nahni Trap of Astral or Supreme. Rate includes cutting of floor/wall, necessary outlet pipe with necessary adhesive. Upto downtake pipe, Fixing PVC Jali of approved make complete as directed.					
5.3	P/F EWC FLOOR MOUNTED	1	NO			
	Providing and fixing EWC first quality Hindustan , Nycer, Cera or equivalent type snow white glazed vitrous china, EWC M Cera S1056101 [COVENTIONAL With Built in Jet] of with heavy type black or white plastic seat, lead with CP brass hinges, rubber buffers with fittings, brakcets, providing and fixing the 25mm dia flush cock of Jaquar Catalogue No -1081A[Continental Range] , 25 mm dia CP brass flush bend including cutting and making providing and fixing jet spray in EWC of approved ISI quality etc complete as directed.					
Architect	Manish Desai					Contractor's seal and Signature

5.4	P/F LARGE FLAT BACK URINAL	1	NO			
	Providing and fixing Large flat back snow white glazed first quality lipped urinal of Cera make cat No.S4020107 including Approved make chromum plated angular cock of Jaquar Cat. No- 053[Continental]chromium plated , connecting PVCpipes with nuts and all fittings, 32 mm dia CP waste coupling of Jaquar make cat. No- 709 [ALLIED] , CP brass spreader and CP pipe, with necessary connecting pipe wall flange ,38 mm dia chromum plated waste coupling Approved make with required length of 32 mm dia concealed GI pipe upto the drain and bend, fixing clamps complete as directed.					
5.5	P/F WASH BASIN	1	NO			
	Providing and fixing first quality Snow white wash basin of 550 mm x 400 mm size, M Cera Cat No. S2040103 [Cornet] approved shape as per detail of approved make and quality such Cera/Hindustan/Nycer or equivalent with necessary specials, one chromum plated brass pillar cock 15 mm size of Jaquar make cat. No-021[Continental], one 15 mm CP angle valve of Jaquar Cat. No- 053[Continental]chromium plated , connecting PVCpipes with nuts and all fittings, 32 mm dia CP waste coupling of Jaquar make cat. No- 709 [ALLIED] and rubber plug heavy brackets with two coats of aluminium paint over brackets, and 32 mm dia CP brass bottle trap of Jaquar make cat. No-773[ALLIED] with necessary connection pipe wall flange etc. complete as directed					
5.6	P/F MIRROR	1	NO			
	Providing and fixing 1'-6"x2'-0" Mirror above wash basin 6 mm thick Mirror of approved make shall be fixed with 2" long S.S. Studs, 4 Nos. complete as directed.					
	TOTAL OF SANITARY					
Note:						
1	Rate includes Dismantling of existing toilet accessories like Urinal, Wash basin, W.C pan, EWC, NT, Flush Cock, Bib Cock, Stop cock, GI/CI pipe, Pvc Pipe line of any dia. and Removing door and windows etc.as directed by Bank nothing extra shall be paid for them.					

SUMMARY							
1	MASONARY WORK			Rs.			
2	FINISHING WORK			Rs.			
3	FLOORING WORK			Rs.			
4	WATER SUPPLY WORK			Rs.			
5	SANITARY WORK			Rs.			
TOTAL COST OF [1 TO 5]				Rs.			
[C] BUY BACK OF OLD FURNITURE							
Dismantling of entire furniture and fixtures from existing premises and buy back of furniture which is not required by Bank, as follows							
1	Wooden Partition for Server Room/ Manager Cabin & other partition	130	SQMT				
2	12mm th glass	11	SQMT				
3	Flush door shutter	2	SQMT				
	Wooden Table						
4	Manager Table Size 5'-3"x2'-6"	4	NO				
5	Table Size 5'-3"x2'-0"+ 1'-6" L-Type	15	NO				
6	Wooden Side Table 36" x16" x 30"ht	4	NO				
7	Low height and Full height Storage	31	SQMT				
8	Roller Blind	23	SQMT				
TOTAL COST OF BUY BACK "C"							
SUMMARY							
PART A - FURNISHING WORK							
PART B - CIVIL WORK							
PART B - BUY BACK							