SCHEDULE OF QUANTITIES - CONSTRUCTION OF STRONG ROOM AT THALASSERY BRANCH

Sr.No	Description of item	Quantity	Unit	Rate	Amount
	CONSTRUCTION OF STRONG ROOM				
1	Reinforced Cement Concrete 1:1.5 :3 with 20 mm aggregate for floor and side walls of strong room in ground floor etc. complete including chipping of existing wall and floor, shuttering and curing but excluding the cost of reinforcement.Good quality M-sand to be used.		m3		
2	Reinforced Cement Concrete 1:1.5:3 with 20 mm aggregate for floor of strong room in ground floor etc. complete including chipping of existing wall and floor including curing but excluding the cost of reinforcement.Good quality M-sand to be used.		m3		
3	Providing steel reinforcement for RCC works including straightening, bending, tying and placing in position ,using TMT bars of Tata, Visag or Sail brand		Kgs		
4	Provide and fix steel grill roofing for strong room in ground floor with 20 mm square steel rods at 7.5 cm c/c in both ways and angle sections including hoisting and placing in position, welding at all joints etc complete. Using TMT bars of Tata, Visag or Sail brand		Kgs		
5	Providing solid concrete block masonry laid with cement mortar 1:4 etc complete using good quality M-sand		m3		
6	Plastering with cement mortar 1:4 ,12 mm thick including curing.	50	m2		
7	Applying two coats of emulsion over one coat of putty and a coat of primer after cleaning the surface for the walls in banking hall		m2		
8	Painting with synthetic enamel paint two coats to neat finish over a coat of primer to steel grille work		m2		
9	P.C.C for bed in CC 1:4:8 mix,using 40 mm nominal size broken stone.including cost of materials,labour charge , conveyance etc. complete		CUM		

10	Flooring: Flooring with best quality vitrified flooring tiles, fixed over existing flooring with, 60x60cm (Kajaria or equivalent approved) as per the design, colour and make asper the instruction of the engineer in CM 1:3,12 mm thick including pointing with approved quality compound which match the colour of the tiles cleaning after laying including labour charges, cost and conveyence of materials etc. complete.	Sq.M	
	Total		