

**STATE BANK OF INDIA**  
**ADMINISTRATIVE OFFICE, GAYA**  
**PRICE BID FOR INTERIOR FURNISHING AND ALLIED CIVIL WORKS AT RASMEC GAYA**

S.No	Item Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	<b><u>LOW HEIGHT SINGLE WINDOW COUNTER</u></b> Providing and fixing low height Single Window counters / Case Manager's table with a maximum width of 3'0" in required shape as per typical design. The main structure of the counter is to be made of 19mm thick BWP Phenol Formaldehyde block board of Green/Century or equivalent make. The width of the counter should have 5'0" (with disc credenza / cabinet of 1'4" wide and maximum 3'6" length / depth (including width of counter). The vertical supporting members of counter are to be made of 19 mm thick BWP Phenol Formaldehyde block board (of approved or equivalent make). D-Tel box shall be fitted properly in right hand side. The key board pullout tray to be provided in addition to drawer with lock and key make arrangement of standard make. The left hand side should have cabinet made of 19 mm thick BWP, PF plywood and cavity keeping CPU as per design / drawing. The counter top have a neat hole to be made in the table for connecting the wires which is to be covered with a white colored PVC insert (wire manager) with moveable parts to put the wires and sockets to cover the hole neatly. The exposed block – board/ plywood to be covered with 1 mm thick laminate of Greenlam/Marino/Century or equivalent make of approved shade and colour. Exposed portions to be also covered with 1 mm thick laminate of approved shade and colour. The internal and non-visible side of all drawers, cabinets and counter table shall be painted with 3 coats of enamel paint over one coat of primer on the internal side. Glass portion made of 12 mm thick toughen glass of approved make as per design and specification securely fixed in toughen section as per design and details and all necessary standard quality of fittings, hard wares, locks (make or equivalent). Door shutter of 19 mm BWP board to be fixed at the rear side of counter with automatic locking system from Godrej or equivalent. All work to be completed as per approved materials Colour & Laminate etc and specification and direction of Engineer-in-charge.	Rmt.	0		
2	<b><u>FULL HEIGHT PARTITIONS PARTLY paneled AND PARTLLY GLAZED/SOLID PARTITION</u></b> Providing and fixing double skin partly paneled & partly glazed or solid full height partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members (Gamhar, Malaysian Sal wood / hollock) at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting, fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 6 mm thick BWP grade plywood and 0.8 mm thick (Greenlam / century or equivalent) laminate of approved shade and colour with grooves / small / panels cut and pasted in the same as per typical design, on both sides so as to form able skin partition to level 900 mm and with 8.0 mm clear float toughen glass of approved make as above at item-1 of Modi float or equivalent above, etched / etching film pasted as per design fixed in wooden frame . The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fasteners so as to form a stable system / partition all complete work with provision for wiring to be done by other agencies all complete work as per specifications and direction of Bank. Rates are inclusive of all hardware, paints, ply, laminate, toughened glass & other material, labour etc. All work to be completed as per drawing, design, specification and direction of Engineer-in-charge /Bank.	Sqm.	25		

3	<b><u>LOW HEIGHT PARTITION</u></b> Providing and fixing low / half height partitions up to 4' 0" with double skin paneling up to 3'-0" and 12 mm thick toughened glass of approved make above frameless on the top and sides and sturdily fixed at the bottom all complete job with all other specifications and details to be as per item No. 2 above and as per the design. All complete work as per Corporate Centre, Mumbai approved materials Colour & Laminate etc and specifications and direction of Engineer-in-charge /Bank.	Sqm.	19		
4	<b><u>WORK STATIONS / TABLES</u></b> (a). Making and erecting Desk-top with provision of wire manager having two sides vertical support panels and modesty panel. All made of 19 mm thick BWP grade block board of Green/Century or equivalent make, top laminated with 1 mm thick laminate of approved or equivalent make of approved shade and colour. Inner portion of table shall be painted with matt finish 3 coat of synthetic enamel paint with primer. (b) Making & providing drawer chest with two drawers and one cupboard with concealed hinges and Godrej or equivalent make multipurpose locks. Box made of 19 mm thick and bottom with 6 mm BWP grade ply of approved or equivalent make, front shall be clad with 1 mm thick laminate of approved or equivalent make of approved shade and colour. All drawers shall have 'Z' shape powder coated MS runners with PVC sound less rollers. All work to be completed as per Corporate Centre, Mumbai approved materials Colour Laminate and specifications and direction of Engineer-incharge/Bank. (c). Providing and fixing key board tray (as per design and specification at 1- above) and made of PVC / Laminated board on 'Z' shape powder coated runner with PVC soundless rollers. (i) 1500 mm x 900 mm x 750 mm(For CM & Manager) with side unit 900 mm x450 mm x750 mm (ii) 1350 mm x 750 mm x 750 mm(For other staff) with side unit 900 mm x450 mm x750 mm	Nos.	2		
		Nos.	11		
5	<b><u>LOW TYPE STORAGE CABINET</u></b> Making and fixing low type storage cabinet with drawer and cupboard with shelf as per the drawing/ design all made of 19 mm thick BWP block board (of approved or equivalent make), top and front laminated with 0.8 mm thick laminate (of approved or equivalent make) of approved shade and colour. Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be melamine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per specifications and direction of Engineer-in-charge.	Sqm.	2		
6	<b><u>12 MM THICK TOUGHENED GLASS DOOR/PARTITION</u></b> Supplying and Fixing of fully glazed Door (in single / double leaf shutter) and partition at approved position. The door and partition shall be made of 12 mm thick toughened float glass & the glass partition shall be fitted with Patch Fittings of approved make and the patch fittings shall be of sleek design fittings on top & bottom etc as suitable & required as per site condition for making the partition fully stable and secure etc. The door shall be fixed on approved make floor spring and with 2 Nos. of 18 inch S.S. handles, its fittings and fixtures, computerized vinyl push/pull sticker etc. complete all of approved make. The partition glass may be fixed on S. S. channel at lintel and floor levels and also with required/ suitable seal/ gaskets at corner/ junction point of two glasses, as per the site condition & instruction. The cost to include all fixtures, push/pull stickers, Labour etc. complete. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.	Sqm.	4.5		

7	<b><u>PROVIDING AND FIXING WALL &amp; COLUMN PANELING AS PER DRAWING &amp; DESIGN</u></b> The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically. The framework is to be fixed by means of Aluminium angles of appropriate size for proper fixity. The framework is to be covered by 9 mm thick BWP plywood on exposed side with suitable fixtures. The surface is to be finished with 0.8 mm thick laminate of approved shade & make. Provisions are to be made for fixing LED strips. The work is to include all necessary materials, accessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc. Executed elevation area is to be measured for finished				
	(a) Interior Columns in Banking Hall	Sqm.	15		
	(b) With 12 mm thick MDF board fixed on frame finishing paneling surface with 0.8 mm thick laminate.	Sqm.	90		
8	<b><u>FALSE CEILING TILES</u></b> Providing and fixing of Armstrong's Mineral Fibre Acoustical false ceiling tile of type Prima Fine Fissured RH-99% of approx size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Armstrong's Prelude XL Hot dipped galvanized exposed grid 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design, specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independently. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-ordinating with all trades and making any cutouts required for the same, full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.	Sqm.	65		

9	<p><b><u>GYPSUM FALSE CEILING</u></b>  Providing and fixing in position Seamless Gypsum Board Plain False Ceiling in one or more levels as directed including vertical surfaces between different levels.  The Ceiling including vertical surfaces is to be done with 12.5 mm thick plain Gypsum boards (of approved/equivalent make), duly finished with recommended filters, tapes, etc. to have a seamless flush look.  The ceiling system is to be fixed to a concealed GI framework (Gypsteel Ultra make or approved equivalent) by 25 mm long GI drywall screws at 250 mm intervals along both ways.  The framework shall be suspended securely from MS angle hangers fixed to true ceiling surface by dash fasteners.  The whole system is to be fitted with all necessary arrangements like perimeter channels, intermediate channels, ceiling sections, ceiling suspension angles, rawl plug, soffit cleat etc.  The work includes applying two coats of approved putty &amp; primer suitable for Gypsum boards after necessary surface preparation and final painting with approved acrylic emulsion paint on the surface.  Lids shall be made out of 9 mm thick BWR plywood duly painted to match the ceiling surface and provided with 2 No. 75 mm SS butt hinges &amp; 1 No. 100 mm SS tower bolt along the surface.  The work is to be completed with all materials, accessories. Labour, tools &amp; tackles and in strict conformity with manufacturers specifications &amp; recommendations.  Rate is to include the cost of making openings for ceiling mounted electrical &amp; air-conditioning accessories.  All materials should be approved by Bank.</p>	Sqm.	40		
10	<p><b><u>HYDRAULIC DOOR CLOSER</u></b>  Providing and fixing hydraulic door closures of Hardwyn, Everite or equivalent approved brand all complete as per specifications and direction of Engineer-in-charge /Bank.</p>	Nos.	2		
11	<p><b><u>FOOT REST</u></b>  Providing and placing foot rest made of 19 mm BWP grade block board with wooden lippings. All portions shall have a coat of matt finish enamel paint all complete work as per drawing, design. Specification and direction of Engineer-in-charge.</p>	Nos.	13		
12	<p><b><u>LOCKS</u></b>  S/F/F Godrej or equivalent mortise locks/ Night latches including cost of labor &amp; materials etc. to complete job.</p>	Nos.	1		
13	<p><b><u>SPARKLE FROSTED FILM</u></b>  Providing and fixing self adhesive Sparkle series Frosted Film and/or one way vision film of 3 M make as per design approved. The film has to be pasted on glasses surfaces as directed, cut &amp; fixed as per design including the Bank's logo. Supporting Invoice /bills are to be produced for payment of this item including certificate from the dealer certifying use of the product. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	Sqm.	18		
14	<p>Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand)</p>	Cum.	4.5		
15	<p>Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.  Cement mortar 1:3 (1 cement :3 coarse sand)</p>	Sqm.	12		
16	<p>12 mm cement plaster of mix :  1:4 (1 cement: 4 fine sand)</p>	Sqm.	65		
17	<p>Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.</p>	Sqm.	65		

18	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats	Sqm.	270		
19	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	Sqm.	3.8		
20	Providing and fixing TATA Pravesh Plain Steel Finish door of size 3.5'X7' with chowkhat, fittings and all other accessories including lock, tower bolts, hinges etc.	Nos.	1		
21	<b><u>REINFORCED CEMENT CONCRETE</u></b> Rcc of (1:1.5:3) cement :sand :stone chips of size 20mm work in at required place or as per EIC. With approved cement, sand, stone chips , including the cost of labour shuttering ,de-shuttering, proping etc and all complete job. (For door lintels).	Cum.	0.2		
22	<b><u>STEEL REINFORCEMENT</u></b> Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars of grade Fe-500D or more.(For door lintels).	Kg	35		
				<b>TOTAL</b>	
#GST will be paid extra as per applicable					