

PRICE BID OF 80 MM THICK INTERLOCKING PAVERS BLOCK AFTER FILLING THE SAND, BRICK FLAT SOLING, 100 MM THICK P.C.C (1:2:4) ON SLOPES OF FILLING SAND & PORCH PORTION FOR MAKING THE PASSAGE FROM ENTRANCE GATE TO INSTITUTE, DORMITORY & DIRECTOR BLOCKS ETC. AS PER SITE CONDITION FOR R-SETI BUILDING,PALAMU(LENGTH-450'-0" =137.20 METERS EXCLUDING PORCH PORTION)

Sl. No	Particulars of Items	Unit	Quantity	Rate (Rs.)	Amount
1	Supplying and fixing / fitting of 80 mm thick interlocking pavers block of approved make and colors as selected by the Bank's Officials / Director R-SETI and having requisite strength etc as per testing chart of pavers block over a bed of 50 mm thick coarse sand and joints filled with sand with proper leveling / slope etc. including cost of labour and materials etc. and disposal of unserviceable materials etc.to complete job as per direction of E / I.(All the fees & charges of testing of pavers block etc has to be paid by the vendor only).	Sq.m	585.50		
2	Providing 450 mm & 750 mm thick sand filling including cost of labour and materials etc. for making passage etc. to complete job as per direction of E /I.	Cu.m	386.90		
3	Providing 75 mm thick brick flat soling in slope portion including cost of labour and materials etc. for making passage etc. to complete job as per direction of E /I.	Sq.m	241.64		
4	Providing 100 mm thick P.C.C(1:2:4) with stone chips and approved quality of sand etc. in slope portion including cost of labour and materials etc. for making passage etc. to complete job as per direction of E /I.	Cu.m	23.40		
(Inclusive of transportation but excluding of GST)				Grand Total	