

TENDER ID :

PRICE BID FOR THE CONSTRUCTION OF BOUNDARY WALL WITH R.C.C PILLARS, TIE / PLINTH BEAMS, CAP BEAMS & BRICK WALLS ETC. AT R-SETI BUILDING, RANCHI

TOTAL LENGTH OF BOUNDARY WALL- 871'-0" =266.00 Meters.

HEIGHT OF BOUNDARY WALL FROM G.L-8'-0"

NO'S OF R.C.C PILLARS- 113 No's AT 8'-0" C / C

Sl. No	Description of item of works	Unit	Quantity	Rate (Rs.)	Amount
1	Earth work excavation in foundation trenches with ordinary soil etc. do to complete job.	Cu.m	205.00		
2	Providing 0'-6" thick sand filling including cost of labour & materials etc. .do to complete job.	Cu.m	25.62		
3	Providing designation 100A brick flat soling and joints filled with local sand in foundation and below the Tie beams etc. to complete job.	Sq.m	240.26		
4	Providing R.C.C(1:1.5:3) in foundation trenches with stone chips & approved quality of sand do to complete job.	Cu.m	107.41		
5	Providing back earth filling in foundation trenches including cost of labour etc. to complete job.	Cu.m	68.33		
6	Providing R.C.C(1:1.5:3) in tie / plinth beams with stone chips & approved quality of sand do to complete job.	Cu.m	18.28		
7	Providing designation 100A B/W in C.M (1:4) in S / S with approved quality of sand do to complete job	Sq.m	451.45		
8	Providing 0'-9" thick R.C.C (1:1.5:3) in cap beams with stone chips & approved quality of sand do to complete job.	Cu.m	13.61		
9	Providing ½" thick C.P in C.M (1:4) with approved quality of sand do to complete job.	Sq.m	1011.85		
10	Providing R.C.C (1:1.5:3) in Pillars with stone chips & approved quality of sand do to complete job.	Cu.m	19.31		
11	Providing 2 or more coats of weather coat paint of Asian paints/ICI Dulux/Berger/Nerolac or equivalent approved brand over a coat of cement primer to give an even shade over newly plaster finished walls & ceilings as per direction of Bank.	Sq.m	1362.36		

12	Providing average 2mm to 3mm thick wall putty of approved shed and make of J.K. / Birla as per Bank's specifications includes all labor material and transportation etc to complete job as per direction of E / I.	Sq.m	1362.36		
13	Providing tore bar including cutting, bending, binding & placing of rods etc. to complete job. (Make-Tata/Sail) Foundation in Jali: - 10 mm dia. bar in both ways at 100mm C/C. Tie / Plinth Beam: - 16 mm bar= 04 no's & 12mm bar=02 no's. Stirupps-8mm dia.at 200mm C/C. Stiffener / Pillar: - 12mm bar =04 no's, Stirupps-8mm dia.at 200mm C/C. Cap / Top Beam: - 12mm bar =04 no's & 10mm bars=02 nos. Stirupps-8mm dia.at 200mm C/C.	M.T	18.20		
14	Providing ½" thick C.P in C.M (1:6) with water proofing compound over roof with approved quality of sand do to complete job.	Sq.m	350.51		
15	Demolishing of existing boundary wall carefully and keeping usable brick at a place and disposal of unserviceable materials outside of R-Seti building etc. to complete job.	Cu.m	160.92		
16	Taking out of existing main grill gates and again re-fitting the gates in new boundary wall and disposal of unserviceable materials outside of R-Seti building etc. to complete job.	Sq.m	11.90		
17	Providing two or more coats painting with finest 1st quality synthetic enamel paint of Asian paints / ICI Dulux/ Berger Nerolac/ equivalent approved brand of specified colour to give an even after proper scrapping, sand-papering, etc. as per direction of Bank.	Sq.m	23.80		

18	Extra for providing and placing in position 2 no's 6mm dia. M.S bars at every third course of half brick masonry etc. to complete job.	Sq.m	451.45		
19	Centering & shuttering of RCC wok including cost of labour and materials etc. to complete job.	Sq.m	718.00		
20	Deduction of 25,000 no's old brick for the construction of boundary wall etc. to complete job.	Nos per thousand.	19000.00		

Sub-Total (A)

PRICE BIDE OF 80 MM THICK INTERLOCKING PAVERS BLOCK AFTER FILLING THE SAND, BRICK FLAT SOLING, 100 MM THICK P.C.C (1:2:4) ON SLOPES OF FILLING SAND & PORCH PORTION FOR MAKING THE PASSAGE FROM ENTRANCE GATE TO INSTITUTE, DORMITORY & DIRECTOR BLOCKS ETC. AS PER SITE CONDITION FOR R-SETI BUILDING, RANCHI (LENGTH 427'0" = 130.10 METERS EXCLUDING PORCH PORTION)

Sl. No	Particulars of Items	Unit	Quantity	Rate (Rs.)	Amount
1	Supplying and fixing / fitting of 80 mm thick interlocking pavers block of approved make and colors as selected by the Bank's Officials / Director R-SETI and having requisite strength etc as per testing chart of pavers block over a bed of 50 mm thick coarse sand and joints filled with sand with proper leveling / slope etc. including cost of labour and materials etc. and disposal of unserviceable materials etc.to complete job as per direction of E / I.(All the fees & charges of testing of pavers block etc has to be paid by the vendor only).	Sq.m	606.32		
2	Providing 450 mm thick sand filling including cost of labour and materials etc. for making passage etc. to complete job as per direction of E /I.	Cu.m	277.40		
3	Providing 75 mm thick brick flat soling in slope portion including cost of labour and materials etc. for making passage etc. to complete job as per direction of E /I.	Sq.m	158.74		
4	Providing 100 mm thick P.C.C(1:2:4) with stone chips and approved quality of sand etc. in slope portion including cost of labour and materials etc. for making passage etc. to complete job as per direction of E /I.	Cu.m	15.98		

Sub-Total (B)

(Inclusive of transportation but excluding of GST)

Grand Total (A+B)

* PRICE INCLUDES TRANSPORTATION,
LIFTING, FIXING CHARGES AND OTHER
TAXES AS PER GOVERNMENT RULES

* ALL OTHER TERMS AND CONDITIONS AS
PER INDIAN STANDARDS/SPECIFICATIONS

* ABOVE PRICE IS EXCLUDING GST

* GST PAID EXTRA BY THE BANK AS PER
RULE.