

**PRICE BID OF OF 80 MM THICK INTERLOCKING PAVERS BLOCK AFTER FILLING THE SAND, BRICK FLAT SOLING, 100 MM THICK P.C.C (1:2:4) FOR MAKING INTERNAL PATHWAYS FOR CAMPUS OF RSETI BUILDING AT SUPAUL**

<b>Sl. No</b>	<b>Particulars of Items</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate (Rs.)</b>	<b>Amount</b>
<b>1</b>	Supplying and fixing / fitting of 80 mm thick interlocking pavers block of M-30 grade by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per direction of Engineer-in-charge.	<b>Sq.m</b>	<b>804.00</b>		
<b>2</b>	Supplying and filling 300 mm thick sand filling including cost of labour and materials etc. for making pathways to complete job including watering, ramming, consolidating and dressing complete as directed.	<b>Cu.m</b>	<b>241.20</b>		
<b>3</b>	Providing 75 mm thick brick flat soling including cost of labour and materials etc. to complete job as directed.	<b>Sq.m</b>	<b>152.00</b>		
<b>4</b>	Providing 100 mm thick P.C.C(1:2:4) with stone chips and approved quality of sand etc. including cost of labour and materials etc. all complete as directed	<b>Cu.m</b>	<b>14.25</b>		
(Inclusive of transportation but excluding of GST)				<b>Grand Total</b>	