

**TENDER ID :**

**PRICE BID FOR THE CONSTRUCTION OF BOUNDARY WALL WITH R.C.C PILLARS, TIE / PLINTH BEAMS, CAP BEAMS & BRICK WALLS ETC. AT R-SETI BUILDING, DEOGHAR**

**TOTAL LENGTH OF BOUNDARY WALL- 1,155'-0" =352.00 Meters.**

**HEIGHT OF BOUNDARY WALL FROM G.L-8'-0"**

**NO'S OF R.C.C PILLARS- 150 No's AT 8'-0" C / C**

<b>Sl. No</b>	<b>Description of item of works</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate (Rs.)</b>	<b>Amount</b>
<b>1</b>	Earth work excavation in foundation trenches with ordinary soil etc. do to complete job.	<b>Cu.m</b>	<b>264.00</b>		
<b>2</b>	Providing 0'-6" thick sand filling including cost of labour & materials etc. .do to complete job.	<b>Cu.m</b>	<b>33.00</b>		
<b>3</b>	Providing designation 100A brick flat soling and joints filled with local sand in foundation and below the Tie beams etc. to complete job.	<b>Sq.m</b>	<b>309.70</b>		
<b>4</b>	Providing R.C.C(1:1.5:3) in foundation trenches with stone chips & approved quality of sand do to complete job.	<b>Cu.m</b>	<b>138.20</b>		
<b>5</b>	Providing back earth filling in foundation trenches including cost of labour etc. to complete job.	<b>Cu.m</b>	<b>88.00</b>		
<b>6</b>	Providing R.C.C(1:1.5:3) in tie / plinth beams with stone chips & approved quality of sand do to complete job.	<b>Cu.m</b>	<b>23.40</b>		
<b>7</b>	Providing designation 100A B/W in C.M (1:4) in S / S with approved quality of sand do to complete job	<b>Sq.m</b>	<b>584.60</b>		
<b>8</b>	Providing 0'-9" thick R.C.C (1:1.5:3) in cap beams with stone chips & approved quality of sand do to complete job.	<b>Cu.m</b>	<b>17.80</b>		
<b>9</b>	Providing ½" thick C.P in C.M (1:4) with approved quality of sand do to complete job.	<b>Sq.m</b>	<b>1309.50</b>		
<b>10</b>	Providing R.C.C (1:1.5:3) in Pillars with stone chips & approved quality of sand do to complete job.	<b>Cu.m</b>	<b>24.90</b>		

<b>11</b>	Providing 2 or more coats of weather coat paint of Asian paints/ICI Dulux/ Berger/Nerolac or equivalent approved brand over a coat of cement primer to give an even shade over newly plaster finished walls & ceilings as per direction of Bank.	<b>Sq.m</b>	<b>1762.90</b>		
<b>12</b>	Providing average 2mm to 3mm thick wall putty of approved shed and make of J.K. / Birla as per Bank's specifications includes all labor material and transportation etc to complete job as per direction of E / I.	<b>Sq.m</b>	<b>1762.90</b>		
<b>13</b>	Providing tore bar including cutting, bending, binding & placing of rods etc. to complete job. (Make-Tata/Sail) Foundation in Jali: - 10 mm dia. bar in both ways at 100mm C/C. Tie / Plinth Beam: - 16 mm bar= 04 no's & 12mm bar=02 no's. Stirrups-8mm dia.at 200mm C/C. Stiffener / Pillar: - 12mm bar =04 no's, Stirrups-8mm dia.at 200mm C/C. Cap / Top Beam: - 12mm bar =04 no's & 10mm bars=02 nos. Stirrups-8mm dia.at 200mm C/C.	<b>M.T</b>	<b>24.00</b>		
<b>14</b>	Providing ½" thick C.P in C.M (1:6) with water proofing compound over roof with approved quality of sand do to complete job.	<b>Sq.m</b>	<b>453.60</b>		
<b>15</b>	Demolishing of existing boundary wall carefully and keeping usable brick at a place and disposal of unserviceable materials outside of R-Seti building etc. to complete job.	<b>Cu.m</b>	<b>209.20</b>		
<b>16</b>	Taking out of existing main grill gates and again re-fitting the gates in new boundary wall and disposal of unserviceable materials outside of R-Seti building etc. to complete job.	<b>Sq.m</b>	<b>12.00</b>		
<b>17</b>	Providing two or more coats painting with finest 1st quality synthetic enamel paint of Asian paints / ICI Dulux/ Berger Nerolac/ equivalent approved brand of specified colour to give an even after proper scrapping, sand-papering, etc. as per direction of Bank.	<b>Sq.m</b>	<b>24.00</b>		

<b>18</b>	Extra for providing and placing in position 2 no's 6mm dia. M.S bars at every third course of half brick masonry etc. to complete job.	<b>Sq.m</b>	<b>584.60</b>		
<b>19</b>	Centering & shuttering of RCC wok including cost of labour and materials etc. to complete job.	<b>Sq.m</b>	<b>930.00</b>		
<b>20</b>	Deduction of 25,000 no's old brick for the construction of boundary wall etc. to complete job.	<b>Nos per thousand.</b>	<b>25000.00</b>		
<b>(Inclusive of transportation but excluding of GST)</b>			<b>Grand Total</b>		

**NOTE :-**

\* PRICE INCLUDES TRANSPORTATION, LIFTING, FIXING CHARGES AND OTHER TAXES AS PER GOVERNMENT RULES

\* ALL OTHER TERMS AND CONDITIONS AS PER INDIAN STANDARDS/SPECIFICATIONS

\* ABOVE PRICE IS EXCLUDING GST

\* GST PAID EXTRA BY THE BANK AS PER RULE.