

**PRICE BID OF CIVIL WORKS  
BENIPUR BRANCH AND ATM**

S.NO.	ITEM	PARTICULARS	UNIT	QTY.	RATE	AMOUNT
1	<b>ACRYLIC EMULSION</b>	Providing two or more coats of ACRYLIC EMULSION PAINT paint, 1st quality Asian paints / ICI Du-lux/ Berger/Nerolac or equivalent approved brand over a coat of cement primer to give an even shade over newly plastered or old surface in walls & ceiling.	Sq.m	490		
2	<b>WALL PUTTY</b>	Providing and applying wall putty of 2 mm average thickness over plastered & white washed walls & ceiling to prepare the surface even and smooth complete as per direction of EIC/BANK	Sq.m	490		
3	<b>URINAL</b>	URINAL :Providing and fixing wall hang urinal of approved make flat back large in white colour and size of (H x W x P): 59 c.m x 39 c.m x 37.5 c.m white in colour fixed with the help of angle brackets including providing water spreader, domb, and providing and fixing bottle trap all complete as per the directions of the Engineer-in-charge.	no.	3		
4	<b>CERAMIC TILES</b>	Dismantling of floor & wall tiles, CHISELLING over existing surface and Providing and laying Ceramic glazed tiles (thickness to be specified by the manufacturer) of 1st quality conforming to IS :15622 of approved make in colours such shades except white , Ivory , Grey , Fume Red , Brown , laid on 20 mm thick Cement mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete.(MAKE AS PER APPROVED BY SBIIMS LIKE NITCO , , SOMANY , KAJARIA) with all complete job.	Sq.m	50.5		
5	<b>BIB COCK</b>	BIB COCK (TWO IN ONE):Providing and fixing heavy duty 15 mm dia C.P. brass two in one bib cock of approved with wall flange all complete as per standard specifications and as directed by the Engineer-in-Charge.	NO.	3		
6	<b>WASH BASIN</b>	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps with all complete job as directed by EIC	no.	3		

7	<b>WC PAN EUROPEAN TYPE</b>	WATER CLOSET (ENGLISH TYPE) :Providing and fixing first quality European water closet of approved make EWC Constellation in white in colour including providing and fixing cistern height 80cm, width 36 cm with necessary porcelain, P/ S trap heavy duty plastic seats of approved manufacturer such as commander in approved colour, CP brass hinges, buffers etc., all complete including fixing in position with necessary holes, providing and fixing CP brass screws and connecting the outlet to the soll stack including testing the joints all complete as per specifications and as approved by the Engineer-in-charge.	NO.	3		
8	<b>ACP DOOR</b>	Providing and fixing ACP type door of 32mm thickness with aluminium frame as approved by SBI and Indian specs for washroom including the cost of tower bolt side bolt door handle and all other fixture and with all complete job as directed by EIC	Sq.m	7		
9	<b>UPVC PIPE</b>	Providing and laying of 100/75 mm Upvc pipe of su-preme make or as per approved by EIC.including the cost band,tee or other fixture and all complete job.	m	50		
10	<b>HEALTH FAUCET</b>	Providing and fixing of health faucet of Jaquar/hindware/parryware make	NO.	3		
11	<b>CONNECTION PIPE</b>	Supply & Fixing of connection Pipe from Angle cock /Stop cock to Piller Cock.	NO.	6		
12	<b>C.P.JALI</b>	Providing and fixing of C.P.Jali ist quality pure Stainless Steel.	NO.	6		
13	<b>NAHANI TRAP</b>	Providing and fixing of Nahani trap	no.	6		
14	<b>STOP COCK/ANGLE COCK</b>	Providing and fixing stop cock/angle cock of jaquar/parryware/hindware make	no.	12		
15	<b>CPVC PIPE</b>	CPVC/upvc Pipe of hot and cold water resisting of thickness 15mm,32mm including the cost of T BAND with all connection pipe and as required with all complete job	m	50		
16	<b>MIRROR</b>	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : Rectangular shape 453x357 mm	NO.	3		

17	<b>GRANITE</b>	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge : 11.55.1 Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent	Sq.m	2		
18	<b>Sink</b>	Providing and fixing of S S sink including sink cock ,waste pipe ,waste coupling etc. all complete.	No.	1		
19	<b>Brick work with bricks of class designation 100A including the cost of labour and with all complete job Cement mortar 1 :4 (1 cement: 4 coarse sand )as directed by EIC.</b>					
	(A)Full brick masonry(250mm)		Cum	5		
	(B)half brick masonry(125mm)		sqm	154		
20	<b>Plaster of 1:4 cement mortar of 12mm to 20mm thickness with approved brand of cement and coarse sand.</b>		Sq.m	450		
21	<b>DEMOLISHING</b>	Demolishing of brick work including plastered wall 5"/10" stacking of serviceable material and disposing of unserviceable material outside the premises in suitable dumping yard approved by Municipal Corporation.Rate to include carting away material in the dumping yard.	Cum	62		
22	<b>DISMANTLING OF DOOR/WINDOW/VENTILATOR</b>	Dismantling of existing door/window/ventilator frame and panel alongwith iron grill,glass panel etc. manually or by mechanical means at all height and location. The rate to include stacking the serviceable material i.e.grills, railings, wood items like door frames, window frames, as directed at site and carting way unserviceable material / debris to a place approved by Municipal corporation. The work also includes levelling the ground after carting away	No.	18		
23	<b>DEMOLISHING</b>	Demolishing of RCC work by mechanical mean work including stacking of serviceable material and disposing of unserviceable material outside the premises in suitable dumping yard including cutting reinforcement bars	Cum	2.5		

24	<b>VITRIFIED FLOORING</b>	Providing, laying and fixing vitrified flooring / skirting in specified area with vitrified tiles approx size 600mm x 600 mm X 8mm in light colours specified by the Bank as per approved shade and colour of standard make i.e. Naveen/ Johnson/Nitco/ Euro(Premium quality) only, with the help of Pedilite or equivalent make pasting chemicals after required chipping and leveling the surface by 1:4 cement sand mortar if required all complete including cost of materials, labours etc.	Sq.m	325		
25	<b>REINFORCEMENT</b>	Cutting ,bending and tying reinforcement in wall and floor slab with all labour ,material all complete. Above plinth hot rolled deformed bars	kg	2000		
26	<b>COLLAPSIBLE GATE</b>	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer	Sqm	13.6		
27	<b>ROLLING SHUTTERS</b>	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and rangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength onforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters.80 x 1.25 mm MS laths and 1.25 mm thick top cover	Sqm	15.6		
28	<b>RCC</b>	Rcc of (1:1.5:3) cement :sand:stone chips of size 20mm work in at required place or as per EIC. With approved cement,sand,stone chips ,including the cost of labour shuttering ,deshuttering proping etc and all complete job	CUM	25		
<b>RS.</b>				<b>TOTAL</b>		

**NOTE:-**

\* ABOVE PRICE IS EXCLUDING GST.

\* GST PAID EXTRA BY THE BANK AS PER RULE.

\*ALL WORK AS PER IS SPECIFICATION

**AUTHORIZED SIGNATORY**