

*Ar. Manav Salhotra*

**B.ARCH, M.C.O.A. ,A.O.I.O.V**

Member Council of Architecture

Reg. No. –CA/2001/27498

Associate of Institute of Valuers

Reg. No.- F-16504

Registered with Ministry of Finance

Regd. No- 189/CCIT/ASR/ITO(T)/VALUER/

2011-12/15



## **3D Vision Architects**

ARCHITECTS, ENGINEERS, INTERIOR  
DESIGNERS, VALUERS,  
LANDSCAPPERS  
& VASTU CONSULTANTS

329, Govt. College Road, GURDASPUR.

Mob. No. 098141-77578

E-mail: salhotra\_manav53@rediffmail.com

Ref. No .....

Dated: .....

**To**  
**The Regional Manager,**  
**Regional Business office,**  
**Hoshiarpur.**

### **SOQFOR INTERIOR FURNISHING WORK OF SBI TIBRI BRANCH , GURDASPUR IS SUCH AS .**

<b>S.No</b>	<b>ITEM</b>	<b>UNIT</b>	<b>QTY</b>	<b>RATE</b>	<b>AMOUNT</b>
<b>A</b>	<b>INTERIORS / FURNISHING</b>				
<b>1.</b>	<b>Single Level SWO Counters</b>				
	Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick ply (ecotech) with 1.0 mm thick laminate on outer visible surfaces (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood/MDF beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. Commercial block board and finished with 6mm thk. flexi ply as base for acrylic sheet (laminate 1.0 mm thk) as/design with provision for LED Light in bottom. Teak wood/MDF lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications.	Rft.	15'-0"		

	<p>Three drawers with autolock running on both sides mounting Telescopic (channels) of EBCO make, made of 19 mm thick ecotech ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood &amp; front of 19 mm thick ply (ecotech). Non Visible/Inside surface i.e. inside leg-space of table, inside drawers shall be finished with 1mm thk. white/off white laminate. All exposed Teak wood edges / teak wood lipping /MDF beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes &amp; the counter should also includes foot rest , Space for CPU as per drawing, complete in all respects. The provision of swapping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front.</p>				
2	<p><b>POLYACRYLIC SURFACE HARD TOP ON SWO COUNTER :</b></p>				
	<p>Providing and fixing (12mm thick) white polyacrylic stone (non-absorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design provided by the Architects complete in all respect including adhesives, buffing and wastage.</p>	sft	60.00		
3.	<p><b>12 MM thk. toughened glass for Banking / SWO Counters with Etching. - front &amp; Sides.</b></p>				
	<p>Providing and fixing 12 mm thick, clear plain toughened glass of fixed in vertical position at counter level &amp; to side partitions as per drawing, the counter top glass fixed on both sides to toughened glass partitions &amp; side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free.</p>	Sqft.	81.0		

4.	<b>Superior quality stainless steel L - shaped clamps / glass holders</b>				
	Superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides to holding the front glass partition to S.W.Counter.	Nos.	60.00		
5.	<b>Providing and fixing S. lacquered glass</b>				
	Providing and fixing S. lacquered glass in front of SWO counter of 6 mm thk of approved colour (aqua blue). Glass shall be pasted duo corning silicon neutral care(DC 816 white) over the front of counter as per item no.-01. All Edges of the galss is grinded, polished and left free, only glass area with maximum ht ( at center) shall be measured for the purpose of payment.	sqft	22.50		
6.	<b>Officer's &amp; Staff Tables</b>				
	Table made of 19 mm thk. ply (ecotech) with front and side visible vertical surfaces to be finsihed with laminate 1.0 mm thick; Table Top to be cladded with additional 4mm thk MDF finished with Satin Enamel Spray Painted of approved shade, with 40 mm X 12 mm thick teak wood/MDF beading all around, as per drawing. The front of the table top shall be projected as per drawing.The modesty guard shall be finished with 12.0 mm thk. toughed glass with 4" wide S.S. Spacer. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels, as per manufacturers instructions / specifications.				
	A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick ply (ecotech)/ )/ CENTURY (Sainik) finished with 1.0 mm thk laminate(clour as approved by Architect/ bank engg concerned) and $\frac{3}{4}$ " x $\frac{1}{4}$ "				

	teakwood/MDF lipping on two visible sides. three lockable drawer running on side mounting drawer slides (channels) of EBCO make made of 19 mm thick commercial ply with 1.0 mm thick laminate on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick bply. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 1mm thk. laminate of white/off white shade and teak wood /MDF edges / lipping / beading shall be Spirit polished or Spray Painted as required.				
a)	Size- 6'-0" X 3'-0" X 2'-6"	Nos.	3.00		
b)	Size- 7'-0" X 3'-0" X 2'-6"	Nos.	1.00		
<b>7</b>	<b>3m Vinyl Prints with acrylic sheets</b>				
	Providing and fixing 3m Vinyl film sand witched with in 4mm thk acrylic sheets fixed with SS Studs over existing wall/panelling/partition complete in all respects to the entire satisfaction of the Engg./ Architect.	Sqft.	80.00		
<b>8</b>	<b>8.0 MM thk glass on top of officers tables.</b>				
	Providing & Fixing 8mm thk clear float glass for Officers' & BM table top with bevelling on edges all around & grinding including cutting for wire manager as per the instructions of the Achitect/Engineer in charge.	Sqft.	75.0		
<b>9.</b>	<b>Side Credenza</b>				
	Providing & fixing Side credenza ( 15" to 18" deep ) made of 19 mm thick ply (ecotech) and 6 mm thick plywood on back side & 1.0 mm thick laminate on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontally running on side mounting drawer slides (channels) of EBCO make. The remaining				

	part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all non visible/inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping / beading shall be Spirit polished with matching pigment. (Teak Veneer Make: Greenlam/Uniply.,Basic rate @ 80/- sq.ft incl.taxes)				
a	Officer's & Staff side credenza as per Drawing & specification mention in item above. Size - 3'-0" / 4'-0" X 1'-6" X 2'-6" (W X D X H)	Sqft.	35.0		
<b>10.</b>	<b>Back credenza / Storage</b>				
	Providing & fixing back credenza 18" deep ( top surface 18" to 24" as per site) & 36" HT. made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & 1.0 mm thick laminate (colour and specification as approved by Architect / bank engg concerned) horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawers 4"high, horizontaly running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.	sqft.	118.125		
<b>11.</b>	<b>Work Stations for System Room</b>				
	Providing and fixing in position single level work station counter each to be divided at approx. 4 rft. In length, in system / swift room as per site conditions, 2'0" wide and 2'6" high, counter shall be made 19 mm thick ply (ecotech) with 1.0 mm thick laminate on vertical as well as horizontal surfaces with provision of cable management for computer cables and electrical switch board at appropriate place, with teakwood lipping ¾" x ¼" on all edges including bottom touching	sqft.	15.0		

	<p>floor. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications. A full depth CPU shelf 14" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply laminated with 1mm thick laminate on top and ¾" x ¼" teakwood lipping on two visible sides.</p>			
	<p>A full length foot rest made of hard wood 3" x ½" section shall be provided at 4" above floor level. One drawer with lock and one cupboard with shutter made of 19 mm commercial ply with 1 mm laminate on front side of cupboard shutter with shutter having good quality locks, magnetic catcher, hinges, handle / knob etc. is to be provided. The shutters shall be provided beneath the drawers with each counter on its right / left hand size. All the three sides of the drawer will be made of 12 mm commercial plywood and front side of 19 mm ply (ecotech) with 1 mm thick laminate. The bottom of drawer shall be made of 6 mm thick commercial plywood. The drawer will be provided with handle / knob of good quality to be got approved before fixing with drawer channel of 18" length &amp; the counter should have provisions of foot rest , Space for CPU Non-laminated surface i.e. inside leg space of counter inside of drawer / cupboard / outside of drawers / footrest / lipping / moulding etc. to be enamel painted white and teak wood edges / lipping / beading shall be spirit (natural) polish.</p>			
12.	<p><b>False Ceiling With Steps. - Gypsum Board for Bank Hall, B.M Cabin etc.</b></p>			
	<p>Providing and fixing suspended false ceiling (as per specification of manufacture) including steps as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to</p>	Sqft.	1026.52	

	<p>receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).</p>			
	<p>The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings, A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade.</p>			
	<p>The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills &amp; trap door etc. if required &amp; finishing of ceiling in all respect. Steps/ Vertical bands shall be measured in square feet. Payments shall be made only for exposed surfaces &amp; actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools, lifts and all heights etc.</p>			
13.	<p><b>False Ceiling - (Mineral Fibre) for Bank Hall, B.M Cabin etc.</b></p>			
	<p>Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 &amp; micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The</p>	Sqft	965.79	

	framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.			
	Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.			
14.	<b>Full Height Partitions with etching on glasses. - Solid / partly glazed.</b>			
	Providing and fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 2'0" to 2'6" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs / steel lugs. The frame work to be clad with 8.0 mm thick commercial ply and 1.0 mm thick laminate as per pattern on both sides upto 3'0" height and above 7'0" height and 5.00 mm thick glass with etching as per design fixed with teak wood moldings above 3'0" height and upto 7'0" height. The skirting shall be finished with 1.0 mm thk brushed steel finsih lamiante. Work also includes providing and fixing of door as per drawing and specifications. All ply / wood to be treated with wood preservatives of approved ISI quality. The doors should be 38 mm thick and also be of similar specification with bottom and top rail of 8" & 6" respectively etched Glass including heavy duty brass hinges and 6 lever mort ice lock of godrej make and other hardware. The work should be complete	Sqft.	312.75	



	in all respect including requisite hardware.			
	All mouldings/ lipping shall be finished with high gloss Spirit polished of approved shade. The rate shall also include for providing groves in laminate . All job to be done to Architect's satisfaction / as per bank direction. Measurements to be taken upto false ceiling level & Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made above false ceiling.			
	<i>Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.</i>			
15.	<b>Low Height Partition with Laminate ((film to be provided on glasses as per requirement) ( Height + 4'-0" ) )</b>			
	Providing and fixing Low Height Partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick commercial ply and 1.0 mm thick laminate (as per approved shade in two or more clours as specified by Architect/ bank engg. Concerned) as per pattern on both side's upto 4'0" height. The skirting shall be finished with 1mm thk brushed steel finsih lamiante. All ply / wood to be treated with wood preservatives of approved ISI quality. All mouldings /lipping shall be finished with high gloss Spirit polished of approved shade. The doors should be 38 mm thick and also be of similar specification with bottom and top rail of 8" & 6" respectively etched Glass including heavy duty brass hinges and 6 lever mort ice lock of godrej make and other hardware. The work should be complete in all respect including requisite hardware.	Sqft.	169.0	
	<i>Note: (i) All ply to be sprayed with anti termite and antiborer spray. (ii) Rates to include all necessary supports and as per details</i>			

	<i>(iii) Measurements to be recorded up to finished false ceiling level.</i>				
16.	<b>Main Entrance Door for B.O , B.M. CABIN &amp; E-Lobby - Toughened Glass 12.0 mm thk. with etching /Logo</b>				
	Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf glazed Toughned door of size approximately, 1800 to 700mm X 2100 mm all sides edge grinded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include necessary etching film / logo all inclusive, complete	Sft.	70.0		
17.	<b>Hardware for fixing Toughened Glass for B.O., B.M. Cabin &amp; E-Lobby</b>				
	Fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherer ever required and SS cover over patch fittings to accommodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete of godrej / dorma.	Job	3.00		
18.	<b>Wall Paneling Laminated (1.00 mm Thk Laminate (windows. B.M. cabin, columns, officers table)</b>				
	Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un annodised Aluminium ( as per requirement) frame work @ 16" to 24" c/c vertically & horizontally.The frame work to be clad with 8.0 mm thick commercial ply for vertical surface and 6.0 mm thk commercial ply provided above that for grooving of size 3/8"x 3/8" and finished with 1.0 mm thk laminate as per design.The paneling shall be closed at top with 2"x 3/4" teak wood beading above upto 2'-0" level of back storage credenza along wall and inside managers room upto false ceiling level, teak wood lipping / beading shall be spirit polished. and following finishigs as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0				

	mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza, storage etc.				
i.	Vertical Paneling finished with laminate 1.0 mm thk (two clour) (as approved by Architect/bank engg.)	Sqft.	1084.75		
19.	<b>DECORATIVE PANELLING (LOUVERS PANELLING)(in B.M. Cabin)</b>				
	Providing & fixing interlocking Charcoal wall panel of 2700mmx160mmx240mm fixed to the wall & partition with suitable glue. Complete design -138 of EURO PARATIK or equivalent.	Sqft.	61.125		
20.	<b>LACQUERED GLASS PANELLING (for columns)</b>				
	Panelling with 6mm lacquered glass (St. Gobain "Planileque" or equivalent), fixed to walls over a layer of 12mm thick commercial ply/mdf using clear silicone adhesive, complete in all respects	Sqft.	43.20		
21.	<b>Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop &amp; Suggestion Box</b>				
	Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'-6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.	Nos.	1.00		

22.	<b>Door Closer</b>				
	Providing and fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej / Hyper / Everrite make, to Doors complete in all respects.	Nos.	8.00		
23.	<b>Mortice Lock</b>				
	Providing and Fixing silver colour (or matching with colour scheme as per site) Godrej make mortice lock to doors complete in all respects.	Nos.	5.00		
24.	<b>Night latch Lock</b>				
	Providing and fixing night latch lock in cash cabin door of Godrej make in aluminium / wooden doors, complete in all respects.	Nos.	1.00		
25.	<b>Colour Powder coated Aluminium Doors with Both Side Pre-laminated / PVC coated Board / 12.0 mm thk.Glass with etching &amp; frosted as per requirements.</b>				
	Providing and fixing aluminium door made of approved colour powder coated, aluminium extruded sections of various sizes as given below to be fabricated as per approved pattern for doors fixed in position with butt hinges to frame & frame fixed in position with rawl plugs, wooden pegs, screws, aluminium angles / cleats, etc. The doors will be made of three horizontal members and two vertical members provided with 8" long aluminium tower bolt, door stopper, 4 – lever, Make- Plaza, Harrison, Godrej, built in dead lock and aluminium T section / angle at vertical side. Both sides pre-laminated board/ glass 12 mm thick shall be fixed in panels with tapered glazing clips. After fixing / embedding with walls & lintel, etc. the surface will be properly repaired / made good with existing specifications. a). 65 X 38 X 16 Gauge - All horizontal and vertical members of Door Frame. b). 114 X 44 X 16 Gauge - All bottom & lock / middle rail horizontal members of doors. c). 83 X 38 X 16 Gauge - Door members - Top rail & Stiles. The rate shall include all hardware to complete the job.	Sqft.	71.50		

26.	<b>Colour Powder coated Aluminium Doors with Both Side Pre-laminated / PVC coated Board / 5.50 mm thk. Board as per requirements.(for doors and internal partitions )</b>				
	<p>Providing and fixing aluminium door made of approved colour powder coated, aluminium extruded sections of various sizes as given below to be fabricated as per approved pattern for doors fixed in position with butt hinges to frame &amp; frame fixed in position with rawl plugs, wooden pegs, screws, aluminium angles / cleats, etc. The doors will be made of three horizontal members and two vertical members provided with 8" long aluminium tower bolt, door stopper, 4 – lever, Make- Plaza, Harrison, Godrej, built in dead lock and aluminium T section / angle at vertical side. Both sides pre-laminated board 12 mm thick shall be fixed in panels with tapered glazing clips. After fixing / embedding with walls &amp; lintel, etc. the surface will be properly repaired / made good with existing specifications.</p> <p>a). 65 X 38 X 16 Gauge - All horizontal and vertical members of Door Frame.  b). 114 X 44 X 16 Gauge - All bottom &amp; lock / middle rail horizontal members of doors.  c). 83 X 38 X 16 Gauge - Door members - Top rail &amp; Stiles.  The rate shall include all hardware to complete the job.</p>	Sft.	84.0		
27	<p><b>Door to System room - Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC.</b>  (Kutty flush doors &amp; furniture co. Pvt Ltd.paonta sahib, distt. Sirmour, H.P. &amp; GMT, Baddi)</p>	Sft.	21.00		
a)	<p>Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm ) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash</p>				

	fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fastners).			
b)	Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make, provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately).			
c	Hardware for fixing - Fire rated steel door including frame Providing and fixing following hardware for fixing fire rated steel door including frame, complete. Hinges 4X3X3 ( Min. 3Nos), Pull Handle 19 X 250mm - Pair, Dead Lock, Fire Rated Wired Glass size - 300 X 200, Fastners Hilti 10 X 92mm - (Min - 10Nos.)			
28.	<b>BOXING FOR ELECTRICAL PANEL (18mm FIBRE CEMENT BOARD)</b> Providing & fixing at site cabinet 8'-6"height having overall depth of 1'-6".the carcass shall be made of <b>18mm thk Fibre Cement Board</b> . The shutters shall be made of 18mm thk Fibre Cement Board. with 1.0mm thk laminate on outer surfaces using suitable adhesive. The shutters shall be mounted on <b>heavy duty overlap type SS hinges</b> & provided with magnetic catchers, lock & towerbolts as required with 5mm thk teak wood lipping on all the exposed edges, duly spirit polished. All internal surfaces, & back of shutters shall be painted white, complete in all respects. MAKE : <b>ZYKRON</b>	sqft	189.0	

	<b>(Century Ply) / SHERA Board / Equivalent</b>			
29.	<b>Glass films</b>			
	Providing and fixing 3 M make decorative film on glass of approved shade as per architect's instruction with grooves etc. all completed. Note Actual area of film installed will be measured and paid . No wastage will be considered	Sft.	110.34	
30.	<b>PLANTER BOX</b>			
	Supplying Planter 15'x15"x15" made of 19mm comm. Ply with 1mm laminate and polished teak wood moulding 25 x 8 mm on top & lining of aluminum sheet.	No.	8.0	
31.	<b>BANK LOGO &amp; LETTERS</b>			
	Providing , making to shape and size ( as per the design provided) and fixing to position SBI bank logo made out of ACP sheet of bank blue color ( pre approved) fixed to position with aluminium framework with required screws, nutts bolts and hooks etc. of size 2' x 2'	1.00	no.	
	SBI logo 10" dia (SS FINISH)	1.00	no.	
	English letters 10" high (SS FINISH)	3.00	no.	
32.	<b>ACP CLADDING</b>			
	Providing cutting, bending and fixing of aluminium Composite Panel cladding of approved make / manufacture on external façade of size as shown in drawings at all heights and elevation including necessary frame work, either curved or straight or circular in plan. The aluminium composite panel should consist of 3 mm thick thermoplastic core of anti - oxident LDPE + HDPE ( Virgin Core) sandwiched between two layers 0.5 mm thick aluminium alloy sheet ( alloy grade 3003 of ASTM B-209) making a total panel thickness of 4 mm.The surface finish shall be PVDFcoat of 30 micron over a base polyester coat on top and service coat on the reverse with chrome /alkyd of 6 - 7 microns coating shall confirm to ASTM D 2244-93 and ASTM D 523 - 89	sqft	271.75	

	<p>for color retention and chalk resistance.ACP shall be fixed on especially designed aluminium frame work with horizontal and vertical members of extruded aluminium made out of AA 6063 T, 6 - 20 microns anodizing shall be done on the aluminium section. The aluminium frame work shall be of 50 x 25 x 1.6 Sheet to be supplied in width of 1220 mm. The color shade and texture of the ACP to be as per the approved Bank color design and pattern.</p>				
<p>33.</p>	<p><b>ROLLING WINDOW BLINDS:</b></p>				
	<p>Providing &amp; Fixing Roller Blinds of Vista make-Iceland Series made of Translucent fibre glass fabric of approved shade including 32mm round channel and mechanism and other fitting fixed in position as per manufacture's specification, complete in all respects to the satisfaction of Architect/Engineer in Charge</p>	<p>Sqft</p>	<p>83.25</p>		
	<p><b>TOTAL AMOUNT</b></p>				
	<p><b>GRAND TOTAL</b></p>				