

**BILLS OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) OF
STATE BANK OF INDIA FOR DRT 2 AT THIRD FLOOR, BHIKHUBHAI CHAMBER, AHMEDABAD**

Sr. No.	Description	Quantity	Unit	Rate	Amount
---------	-------------	----------	------	------	--------

Note : Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills

[A] FURNISHING WORK

TABLES

1	PO TABLE SIZE: 8'-0" X 3'-0" X 2'-6" HT. with Laninate finish on Table Top, sides and all other visible surfaces etc complete as follows	1	NO	
---	---	---	----	--

Supplying and installation of Table as per the following description : Size 8'-0" x 3'-0". Table top shall be made from 18 mm thick BWR ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick BWR ply wood with wooden framing. Drawer of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick BWR ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Computer Key board tray with moused of metal of approved make shall be provided. All internal surface will have 0.60 mm thick balacing laminate.

**Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing
Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.**

Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer polished etc complete as directed.

Table shall have **ready made CPU trolley with castors** and metallic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges & corners

Exposed edges of Table Top, **Ready made Foot Rest & drawers** shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.

All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete.

All the surface without laminate / balancing laminate shall be lacquered polished of approved shade

Sr. No.	Description	Quantity	Unit	Rate	Amount
	<p>As per drawing and instruction of Architect/Bank work to be Completed.</p> <p>FINISHING DETAILS IN NUTSHELL:</p> <p>1) Table Top : 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished</p> <p>2) Front Apron & Sides: 1.0 mm thick Dark Laminate</p> <p>3) Facing of Drawers: 1.0 mm thick Dark Laminate</p> <p>4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate</p>				
1[a]	Same as above Item-no-1 but Size: 6'-0"x2'-9" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. [FOR REGISTRAR OFFICER] existing table to be used with renovation, changing of lamination, repairing of shutters, Drawers, Locks and sliding channels, key boards including polishing beading pattis etc complete.	1		NO	
1[b]	Same as above Item-no-1 but Size: 5'-6"x2'-6" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. [FOR ASS. REGISTRAR] existing table to be used with renovation, changing of lamination, repairing of shutters, Drawers, Locks and sliding channels, key boards including polishing beading pattis etc complete.	1		NO	
1[c]	Same as above Item-no-1 but Size: 5'-0"x2'-6" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. [FOR OFFICER BESIDES ASST. REG.] existing table to be used with renovation, changing of lamination, repairing of shutters, Drawers, Locks and sliding channels, key boards including polishing beading pattis etc complete.	1		NO	
1[d]	Same as above Item-no-1 but Size: 4'-0"x2'-0" without Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. [FOR OFFICERS] existing table to be used with renovation, changing of lamination, repairing of shutters (If any), Drawers (If any), Locks and sliding channels, key boards including polishing beading pattis etc complete.	11		NO	
1[e]	Same as above item no-1 but Size: 4'-0"x2'-0" without Drawer Unit with 1.0 mm thick Laminate finished on all exposed surfaces. [FOR OFFICERS]	1		NO	

Sr. No.	Description	Quantity	Unit	Rate	Amount
2	<p>Linear Table with Drawer (Laminate Finish on Table Top and Drawer shutter) Providing and fixing Linear Table having width of 2'-0" using 18 mm thick BWR plywood for Top and verticle support at 4'-0" c/c, Providing storage cabinet Two drawer and One shutter Unit at Every 4'-0" c/c, Group lock, SS handle in counter as directed complete. 1.0 mm thick Laminate finish on table Top and front side of shutter. Providing Foot rest of 3" x 1.5" in C.P. Teak wood with lacquered polish. All internal surfaces shall have 0.60 mm thick balacing laminate as directed.</p>	7	RMT		
2[a]	<p>Same as above Item No. 2 But Linear Table having width of 3'-0"</p>	3	RMT		
2[b]	<p>Same as above Item No. 2 Linear Table (Drawer if any) But, existing table to be used with renovation, changing of lamination, repairing of shutters (If any), Drawers (If any), Locks and sliding channels, key boards including polishing beading pattis etc complete.</p>	3	RMT		
3	<p>SIDE CREDENZA (SIDE TABLE) Side Credenza Size 3'-6" x 1'-4" x 2'-6" ht. Openable shutter with 1.00 mm thick Laminate finish on Top, front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. Rate for length Less then 3'-3"</p> <p>Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick BWR ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick BWR plywood. Openable shutters shall be made from 18 mm thick BWR ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate</p> <p>Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate</p> <p>FINISHING DETAILS IN NUTSHELL: 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Apron & Sides : Frosty White Laminate</p>	1	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
3[a]	<p>SIDE CREDENZA (SIDE TABLE) with partly Drawers Same as above Item No 3 all external surfaces to be finished with 1.0 mm thick Laminate (approved shades). Size shall be 3'-0"/3'-3" x 1'-4" x 2'-6" ht. with Partly drawers & Partly openable shutters as directed FINISHING DETAILS IN NUTSHELL: 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Apron & Sides: Frosty White Laminate</p>	5	SMT		
3[b]	<p>Side Credenza Size 3'-3" x 1'-4" x 2'-6"/3'-0" ht. Same as Item No. 3 But, Existing side table to be used with renovation, changing of lamination, repairing of shutters, Drawers, Changing Locks, sliding channels, key boards including polishing beading pattis, Change Hinges etc complete.</p>	7	SQ.MT		
3[c]	<p>STORAGE CABINET with Top & Front laminate finished. Storage of any height Same as above Item No-3, but all external surfaces to be finished with Laminate (approved shades) FINISHING DETAILS IN NUTSHELL: 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Apron & Sides: Dark Laminate/Frosty white Laminate as per design & instructions</p> <p>FULL HEIGHT PARTITION WORK</p>	13	SQMT		
4	<p>P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed. For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid. No extra payment shall be made for members going up to slab/beam bottom.</p>	90	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
4[a]	<p>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS</p> <p>Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.</p>	21	SQMT		
4[b]	<p>PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE</p> <p>Same as item no 10 but P/F 30 / 32 mm thick flush shutter with both side laminate including SS hinges with countersunk SS screws, Approved make Night latch Lock, S.S Handles,Door stoppers, doorstop etc complete as directed.</p>	2	SQMT		
5	<p>Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows.</p> <p>Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 32 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 32 x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk S S screws, Approved make Dead Lock, S.S Handles,150 mm long Door stoppers, doorstop of approved make etc. All exposed surface /edges not laminated be provided with lacquer polish. Work to be completed as per drawing & instructions.</p>	2	SQMT		
PANELLING WORK					
6	<p>P/F Wall panelling with laminate finishing for wall and Pillar etc</p> <p>Providing and laying panelling on walls & pillars having 12 mm thick 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect.</p>	50	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
7	<p>FALSE CEILING WORK P/F GYPSUM BOARD FALSE CEILING Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.</p> <p>After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note : (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for pavement.</p>	95	SMT		
8	<p>Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications</p>	73	SMT		
9	<p>SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick BWR plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed.</p>	1	SMT		
10	<p>Supplying and fixing Verticle Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 90=00 Per Sq.Ft Excluding GST)</p>	30	SMT		
11	<p>Providing and fixing "Dorma/Ozone/Godrej" or equivalent make door closure.</p>	15	NO		

Sr. No.	Description	Quantity	Unit	Rate	Amount
12	<p>Supplying and installation 3'-0" x 1'-9"x 1'-3" height Center Tepoy as follows.</p> <p>Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.</p>	1	NO		
12[a]	<p>Same as above but size 1'-9" x 1'-9" x 1'-3" height for Corner Tepoy</p>	1	NO		
13	<p>P & S of Visitors sofa. The seat shall be made out of 19 mm BB in a box form. The back shall be made out using internal wooden frame work of size 2"x1 ½" covered with 6 mm ply. It shall be covered with 100 mm & 50 mm th. 40 density u foam in seat & back respectively. This should be again covered with 14 mm th. 40 density u foam with madarpat cover on it & upholstered of suggested shade & finish in seat & back on all open visible sides with basic rate of Rs.900/- per meter. It will have wooden handles as per drawing. outer length with armrest will be considered for measurement purpose.</p>	6	RMT		
14	<p>Reconditioning of existing sofa by changing Upholstry of Rs. 650 per Rmt. Rubber form (40 density sleepwell - 4" thick in seat and 3" thick in back) to be provided. Work also involve replacing back cloth and any broken wooden members, complete lacquer polishing as directed.</p>	2	RMT		
15	<p>Removing, refixing and realignment of existitng Furnitures</p> <p>Removing, Refixing and re-alignment of Tables,Side Tables, cup board , Misc. other furnitures to be used from existing premises including polishing and minor repairs.</p> <p>(i) Shiffing and re-laying table,side table, cup board as per new lay out . Rate also incudes removal and refixing of electric/ data/telephone connection as per site requirements.</p> <p>(ii) Necessary cutting, modification and repairing if required. Repairing of shutters, Drawers, Changing Locks, sliding channels and Hinges including Painting /polishing beading pattis etc complete.</p> <p>(iii) Rate includes changing of laminate.</p>				
[a]	<p>Removing and refixing of existing storage cup board with necessary cutting and modification including painting/ polishing etc complete as directed.</p>	10	SQMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
[b]	Removing & Refixing of existing Full & Low Height wooden partition with glass and door with Necessary modification and repairing/alternation if required. etc complete including changing of laminate/ painting/ polishing all surface complete as directed.	115	SQMT		
16	Providing and Fixing Wooden stage Creating raised floor in PO COURT using 50mm x 50mm x 3mm MS Hollow section at 600mm c/c both ways with necessary verticle support and base plate of 100mm x 100mm x 3mm thk. as per site requirements. And fixing 25 mm thk. BWR plywood with 3 mm thik PVC Flooring of approved make complete as directed.	16	SMT		
17	PAINTING WORK				
[a]	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT) Providing and applying (with rollers only) Acrylic emulsion paint of required shade and approved make on old/new surface in two or more coats to give an even shade including the preparation of surface for painting, applying FULL primer and putty at all heights complete as per manufacturer's specification and as directed.	500	SMT		
[b]	P/A SYNTHETIC ENAMEL PAINT Providing and applying synthetic enamel paint at all heights of required shade and approved make on new / old work including scrapping / cleaning and preparation of surfaces for painting, applying primer and putty, with two or more coats of approved first quality enamel.	100	SMT		
TOTAL COST OF FURNISHING WORK [A]					
[B]	BUY BACK OF OLD FURNITURE Dismantling of entire furniture and fixtures from existing premises and buy back of furniture which is not required by Bank, as follows				
1	Wooden Partition with glass and door	1	LS		
TOTAL COST OF BUY BACK [B]					

Sr. No.	Description	Quantity	Unit	Rate	Amount
SUMMARY					
[A]	FURNISHING WORK				_____
[B]	LESS BUY BACK OF OLD FURNITURE			(-)	_____
	NET TOTAL COST [A - B]				_____

Note:

- [a] In all furniture work, contractor shall make necessary cutout in panelling / partitions / wooden members to facilitate electrical / data cabelling and No extra amount shall be paid for this.
- [b] All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balacing laminate of aproved make & shade in the all S.W Counters/Tables/ Credenza,Storage Cup Board etc.