

PRICE BID FOR RENOVATION OF CANTEEN AT ALAPPEY BRANCH PREMISES.

SI.No	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	Dismantling the existing mangalore pattern roof tiles , purlin,, lattice beam, members and necessary concrete demolishing etc, removing the debris away from site . Rates include the cost of labour, transportation charge etc complete.	M2	70		
2	Dismantling the old and damaged brick masonry works along with old plastering and disposing the debris away from site. Usable materials may be stacked at the site.	LS	1		
3	Providing & fabricating at site, roof truss work with 0.35mm thick matt finish galvalum trafford sheet with 63mm GI Pipe post,100 X 50 fir truss, 25 X 25 purlin etc complete. Applying two coats of enamel paint over a coat of zinc chromate primer etc complete.The rate includes conveyance and cost of all materials, lead & lift, labour charges, scaffolding at all levels etc.	M2	100		
4	Earth work excavation in ordinary or hard soil including bailing / pumping out water if necessary and disposing the excavated earth on the banks or filling it where necessary. (for rectification works to existing compound wall and cracked masonry walls)	M3	35		
5	P C C 1:4:8 using 40mm metal, M sand including cost of material, labour charges for mixing laying and consolidation etc, complete for foundation. (for rectification works to existing compound wall and cracked masonry walls)	M3	15		
6	RCC M20 using 20mm metal, M sand for Column footing, column Pedestal, Plinth beam,lintel/beam, slab, sunshade etc	M3	2		
7	Supplying & fabricating steel reinforcement including cold bending, tying and fixing in position various size of high yield strength deformed, including cost and conveyance of all materials to site, labour charges for binding wire etc. complete.	Kg	350		
8	Solid block of 20cm thickness masonry work using best quality block and M sand in CM 1:4, including the cost of material and labour charge etc. complete for replacing damaged parts of the existing compound wall	M3	40		

PRICE BID FOR RENOVATION OF CANTEEN AT ALAPPEY BRANCH PREMISES.

SI.No	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
9	Internal and external Plastering in C.M 1:6, using plastering crusher sand, 12mm thick one coat floated hard and trowelled smooth	M2	150		
10	Painting with two coats of good quality plastic emulsuion paint over a coat of primer , including cost and conveyance of all materials to site, labour charges ,transportation and watering etc complete.(make Asian, Berger, Nerolac or equivalent)	M2	175		
11	Enamel painting : Painting with 2 coats of synthetic enamel paint over a coat of wood primer after cleaning the surface.Approved make : Asian, Berger, Nerolaco or equalant	M2	15		
12	Flooring with best quality vitrified tiles (antiskid) over a bed of CM 1:4, 20 mm thick, with necessary cement grout for rooms including laying, cutting, polishing, pointing, acid washing, finishing etc complete. The cost includes all material, labour charges, transporation charges etc complete.	M2	90		
13	Kitchen counter top granite slab laying.	M2	10		
14	Granite double edge polishing.	M	16		
15	Kitchen wall tile cladding.Providing and fixing first quality vitrified wall tiles (minimum basic value should be @ Rs.1000/m2) conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades, size as specified by Engineer in charge , in Dados, over 12mm thick bed of cement mortar 1:3 and fixing with grey cement slurry @ 3.3 Kg per sqm, including pointing in white cement mixed with pigment of matching shade complete for walls. Approved brand : Cera / johnson / bell or equivalent.	M2	10		

PRICE BID FOR RENOVATION OF CANTEEN AT ALAPPEY BRANCH PREMISES.

SI.No	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
16	Providing & fixing SS Single bowl with drain board sink. Approve Brand - Franke / KAFF or equivalent. Size - 27"X18"X8" approximately	No.	1		
17	Supplying and fixing sink tap (basic price of around Rs. 1200/No) , swevel type of approved quality. , jaquar or crab tree or equivalent, including all necessary plumbing works	No.	1		
18	Supplying and fixing half pedestal wash basin (parryware, Cera or equivalent make, basic price of wash basin around Rs. 3500/No) rates including cost of pillar cock quarter turn, bottle trap are of crabtree or jaguar , waste coupling, waste pipe, angle cock with all necessary fittings etc. complete.	No.	3		
19	Providing and Laying of PVC pipes, Solvent pasted type joints inclusive of all necessary specials like bends, tees, offsets, junctions, pan connector etc., laid under floor / under ceiling / on walls with suitable clamps including making bores in masonry and rendering the bores in cement mortar after laying the pipes and specials curing etc., complete. all inclusive of Material & labour				
19 a)	25mm PVC, 15kg/cm2	Rm	15		
19 b)	32mm PVC, 15kg/cm2	Rm	20		
19 c)	50mm PVC, 6Kg/cm2	Rm	25		
20	Aluminium Door : Providing and fixing Aluminium door shutter with frame made out of ' Indal/Jindal ' sections powder coated with approved colour, 63x38x1.5mm thick, fitted with 9mm thick particle board from finished floor level to a height of 100cm, with necessary silicon gel, glazings clips; a pair of 300 mm long SS handles, door stopper, tower bolt, 4 nos.of 150mm SS Hinges and locking arrangement. Necessary etching pattern/etching sticker to be provided...	Nos.	5		
21	Providing and fixing good quality Aluminium mesh for window openings with Aluminium frame. Aluminium rectangular section - Frame of size - 2.5" X 1.5"X 1.5mm at 60 cm intervals each. Mesh size - 1 cm grid with a thickness of 1.5mm.	SqM	50		

TOTAL

GST at applicable rates will be extra