

**BILLS OF QUANTITY FOR CIVIL WORK FOR FLOORING AND OTHER
MISCELLANEOUS WORK AT STATE BANK OF INDIA SIDHAPUR BRANCH, SIDHAPUR.**

Sr. No.	Description	Quantity	Unit	Rate	Amount
1	EARTH WORK				
1.1	EXCAVATION WORK Excavation for foundation of 0.23m thick brick walls of the proposed ATM inside the branch premises including the earth filling and the foundation trenches, ramming, watering, consolidating etc. complete. Including transportation of the surplus earth etc. complete.	2.70	CMT		
2	CONCRETE WORK				
2.1	P/L PCC 1:4:8 FOR WALL FOUNDATION Providing and laying machine mixed Plain Cement Concrete 1:4:8 (1 part cement: 4 parts coarse sand : 8 parts of stone agreegat of size 40 mm and down.) for specified thickness, for foundaitons below walls etc. including centering and shuttering if required, laying spreading, ramming, consolidating as per requirement and curing etc. complete as directed.	0.54	CMT		
3	MASONRY WORK				
3.1	P/C BRICK WALLS (230 mm Thick) Providing and constructing brick masonry in CM 1:6 (1 cement & 6 coarse sand) with approved first class bricks having minimum crushing strength of 35 kg/sq.cm including scaffolding, racking out the joints, curing etc. Complete as directed by Engineer - in charge. For Wall at all levels below and upto plinth level.and above plinth level all heights	3.82	CMT		
4	FINISHING WORK				
4.1	P/A 12MM THICK FINISH CEMENT PLASTER ON NEW WALLS Providing and applying 12mm thick finish cement plaster at all heights and below plinth in 1:4 cement mortar to the walls, beams, ceiling, stair, column, pattias, grooves including scaffolding, curing & finishing smooth. The plastered surface shall be rubbed with 'Iron plate". till the surface shows cement plaste in line and level complete as directed.	16.72	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
---------	-------------	----------	------	------	--------

5 FLOORING WORK

5.a P/F VITRIFIED TILES FLOORING [600mmx600mm] 203.31 SMT

Providing & fixing 600 x 600 mm Vitrifed tiles flooring of approved make and shade for flooring as per design. in CM 1:4 over a cement mortor bedding, .Levelling the existing underneath CM bedding & providing cement slurry including light compaction as directed. The rate includes filling the joints of tiles using adhesive & pigments. The rate includes curing acid cleaning, cutting etc. complete. Rate shall be same for all levels. **Basic price of Tiles shall be Rs. 600=00 per Sq. Mt (Excluding GST).** etc. complete as directed. **The rates include removal of existing Flooring up to bedding mortar. Its disposalal .No additional sand bedding charges shall be paid for Electric trenches filling**

Providing and laying 3 mm thick bubble guard of Cello make or equiv. for flooring protection and after completion of other furniture removing the same and carrying away as buy back etc

5.b P/F 75MM HEIGHT SKIRTING 67.53 RMT

Providing & laying 75 mm height skirting cut out of vitrified tiles 600mmx600mm of Approved make over cement paste after making necessary cutting / hacking in walls, surface preparation as directed complete with joint filling etc. Rate also includes, filling of Zaries in skirting complete as directed.The rates include removal of existing skirting . Its disposal Basic price of Tiles shall be Rs. 600=00 per Sq. Mt

5.c MIRROR POLISH ON POLISHED KOTAH STONE FLOORING : 4.96 SMT

Providing and applying mirror polish on the existing polished kotah stone flooring in entrance steps and side otta.

Total amount of civil work

Rs

Sign & Stamp with the Contractor