

PRICE BID**Creation of Seating arrangement at 5th Floor B-wing IT-Retail Loans Dept. SBI GITC Belapur****Civil Work**

Sr.No	Description	Qty	Unit	Rate	Amount
1	Providing and fixing in position running counter of 600 mm wide to be made out of 19 mm thick ply (confirming to IS 303) the bottom vertical support every approx 900 mm as per approved design, All the exposed surfaces of the counter shall finished with approved make/colour/pattern of 1mm thick laminate and TW half round moulding will be finished with zink polish matching/approved colour as per existing laminate colour provided as per the instruction of the Banks complete the work, rates are inclusive of necessary hardware, Keyboard, cable manager, footrest, 1 nos drawer with locking arrangement and 1 nos CPU Pedestal if required etc to complete the work.	75	RFT		
1	Providing and fixing in position running counter of 600 mm wide to be made out of 19 mm thick ply (confirming to IS 303) the bottom vertical support at every approx 1250 mm as per approved design, All the exposed surfaces of the counter shall finished with approved make/colour/pattern of 1mm thick laminate and TW half round moulding will be finished with zink polish matching/approved colour as per existing laminate colour provided as per the instruction of the Banks complete the work, rates are inclusive of necessary hardware, Keyboard, cable manager, footrest, 1 nos drawer with locking arrangement and 1 nos storage with center partition if required etc to complete the work.	145	RFT		
2	Providing and fixing toughened clear 8 mm thick glass partition of size 1'6" x 2' on running counters top at specified/approved locations with 1.5" round moulding at corners, rates are inclusive all necessary hardware required for fixing/ embedding the glass in half partitions and fixed with " D " brackets/SS fittings etc. complete the work as per site conditions and instructions of the Bank.	30	Nos		
3	Providing and fixing double charged vitrified tiles of Kajaria, Johnson, etc. make (size 600mm x 600mm) flooring in cement sand mortar (1:4) bedding including removal of existing flooring, debris etc. from site as per directions of the Bank	100	Sft		
4	Providing & Fixing new low height partition with Aluminium frame covered by 8 mm ply (confirming to IS 303) from both side, and surface finished with both side 1 mm laminate both side as per approved pattern, matched with existing shade	530	Sft		
5	Repairing of existing junction box finished with wooden frame below the tiles level with required opening for cables including necessary replacement of broken tiles covered with 5 mm thick SS sheet, approx size consider 2'*2')	6	Nos		
6	Carefully removing and shifting the existing storages, workstations etc. and storing the servicable material to Banks specified location.	1	Lumsum		
Total					

18% GST Extra