

**ESTIMATE FOR WOODEN FLOORING IN STATE BANK OF INDIA, ADMINISTRATIVE OFFICE  
BUILDING, URBAN STATE, PHASE-II, BATHINDA.**

Sr.No	Description of work	Unit	Qty	Rate	Amount (Rs.)
1	Providing and fixing of 8mm thick Greenlam/Pergo/Vista Laminated wooden flooring (Premium Shades), classification of use 31/23 with a surface abration resistance of class AC4 (average 3000 cycles) impact resistance of 7.7 mm, resistance to cigarette burn with a rating of 4(EN438-2:05)swelling after 24 hrs in water of 8.22%, modulus of rupture of 53.3 newton/mm <sup>2</sup> internal bond 1.78 newton/mm <sup>2</sup> , surface soundness 2.62 newton mm <sup>2</sup> (EN 13329:2000)with a 0.2 mm thick wear layer on top of a high Density fiber substrate core (density ~ 948.3 kgm/m <sup>3</sup> of plank size 1206mmx193mmx8mm having locking arrangement (lock strength> 1100 lbs/ft) with an underlayment made of natural colour foam , with accessories like end profile, Transition profile, reducer, etc. complete. The Profiles are 100% matching.				
	Cost of Vinyl Floor Rs. 135 / sq.ft inclusive of delivery, Octroi, loading- Unloading at site and all taxes thereon.				
	<b>Total value of work</b>	<b>Sq.ft</b>	<b>3407</b>		

GST will be paid extra as applicable

SIGNATURE OF CONTRACTOR & SEAL OF FIRM