

STATE BANK OF INDIA
ADMINISTRATIVE OFFICE, BHAGALPUR

PRICE BID FOR INTERIOR FURNISHING AND ALLIED CIVIL WORKS AT RBO SAHARSA

S.No	Item Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	<p><u>FULL HEIGHT PARTITIONS PARTLY paneled AND PARTLLY GLAZED</u> Providing and fixing double skin partly paneled & partly glazed full height partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members (Gamhar, Malaysian Sal wood / hollock) at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting, fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 6 mm thick BWP grade plywood and 0.8 mm thick (Greenlam / century or equivalent) laminate of approved shade and colour with grooves / small / panels cut and pasted in the same as per typical design, on both sides so as to form able skin partition to level 900 mm and with 8.0 mm clear float toughen glass of approved make of Modi float or equivalent above, etched / etching film pasted as per design fixed in wooden frame . The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fasteners so as to form a stable system / partition all complete work with provision for wiring to be done by other agencies all complete work as per specifications and direction of Bank. Framing of partition to be erected upto beam/slab bottom, however plywood and laminate to be pasted upto false ceiling height. Rates are inclusive of all hardware, paints, ply, laminate, toughened glass & other material, labour etc. and measurement will be upto false ceiling height only. All work to be completed as per drawing, design, specification and direction of Engineer-in-charge /Bank.</p>	Sqm.	0		
2	<p><u>LOW HEIGHT PARTITION</u> Providing and fixing low / half height partitions up to 4' 0" with double skin paneling up to 3'-0" and 12 mm thick toughened glass of approved make above frameless on the top and sides and sturdily fixed at the bottom all complete job with all other specifications and details to be as per item No. 1 above and as per the design. All complete work as per Corporate Centre, Mumbai approved materials Colour & Laminate etc and specifications and direction of Engineer-in-charge /Bank.</p>	Sqm.	27		
3	<p><u>PARTITION REPAIRING</u> Repairing of full height partly paneled partly glazed / non-glazed / low height partitions etc. including with 6 mm thick ply board both sides of Century/Green or equivalent make & 0.8 mm thick laminate of Century / Greenlam or equivalent make with change of Godrej or equivalent make multipurpose locks etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.</p>	Sqm.	41		
4	<p><u>WORK STATIONS / TABLES</u> (a). Making and erecting Desk-top with provision of wire manager having two sides vertical support panels and modesty panel. All made of 19 mm thick BWP grade block board of Green/Century or equivalent make, top laminated with 1 mm thick laminate of approved or equivalent make of approved shade and colour. Inner portion of table shall be painted with matt finish 3 coat of synthetic enamel paint with primer. (b) Making & providing drawer chest with two drawers and one cupboard with concealed hinges and Godrej or equivalent make multipurpose locks. Box made of 19 mm thick and bottom with 6 mm BWP grade ply of approved or equivalent make, front shall be clad with 1 mm thick laminate of approved or equivalent make of approved shade and colour. All drawers shall have 'Z' shape powder coated MS runners with PVC sound less rollers. All work to be completed as per Corporate Centre, Mumbai approved materials Colour Laminate and specifications and direction of Engineer-incharge/Bank. (c). Providing and fixing key board tray (as per design and specification at 1- above) and made of PVC / Laminated board on 'Z' shape powder coated runner with PVC soundless rollers.</p>				
	(i) 1500 mm x750 mm x 750 mm with side unit 900 mm x450 mm x750 mm	Nos.	1		
	(ii) 1350 mm x750 mm x 750 mm with side unit 900 mm x450 mm x750 mm	Nos.	24		

5	<u>WORK STATIONS REPAIRING</u> Dismantling of existing work station tables etc and re-fixing the same as per the drawing including repairing with 6 mm thick ply board of Century / Green or equivalent make & 1 mm thick laminate of Century/Greenlam or equivalent make with change of Godrej or equivalent make multipurpose locks & 02 or more coats of paintings etc. wherever required & disposal of unserviceable materials to complete job as per direction of E/I.	Nos.	17		
6	<u>STORAGE CABINET</u> Making and fixing low type and full height storage cabinet with drawer and cupboard with shelf as per the drawing/ design all made of 19 mm thick BWP block board (of approved or equivalent make), top and front laminated with 0.8 mm thick laminate (of approved or equivalent make) of approved shade and colour. Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be melamine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per specifications and direction of Engineer-in-charge.	Sqm.	18		
7	<u>LOW HEIGHT CABINET REPAIRING</u> Dismantling of low storage cabinets etc and refixing the same, including repairing with 6 mm thick ply board of Century/Green or equivalent make & 0.8mm thick laminate of Century / Greenlam or equivalent make with change of Godrej or equivalent make multipurpose locks & 02 or more coats of paintings etc. wherever required & disposal of unserviceable materials to complete job as per direction of E/I.	Sqm.	19		
8	<u>PROVIDING AND FIXING WALL & COLUMN PANELING AS PER DRAWING & DESIGN</u> The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically. The framework is to be fixed by means of Aluminium angles of appropriate size for proper fixity. The framework is to be covered by 9 mm thick BWP plywood on exposed side with suitable fixtures. The surface is to be finished with 0.8 mm thick laminate of approved shade & make. Provisions are to be made for fixing LED strips. The work is to include all necessary materials, accessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc. Executed elevation area is to be measured for finished				
	(a) Interior Columns in Banking Hall	Sqm.	13		
	(b) With 12 mm thick MDF board fixed on frame finishing paneling surface with 0.8 mm thick laminate.	Sqm.	130		
9	<u>FALSE CEILING TILES</u> Providing and fixing of Gypsum false ceiling tile of size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Prelude XL Hot dipped galvanized exposed grid 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design, specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independently. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-ordinating with all trades and making any cutouts required for the same, full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.	Sqm.	90		

10	<u>ROLLER BLIND</u> Providing & fixing of roller blinds (vista level or classic/ or equivalent of standard make) in off-white or any approved color on all windows. All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All complete work as per drawing, design Specification and direction of Engineer-in- charge /Bank.	Sqm.	31		
11	<u>ALUMINIUM PARTITION AND DOOR</u> Providing and fixing anodized aluminium section for aluminium partition and door to be made from INDAL / ZINDAL or equivalent standard all complete including glazing beads, gaskets with suitable heavy sections as per design and specification, all complete with all approved quality of hardware's including locks, handles etc. as per instruction of the Bank. Section to be used approx Top 60 x 38 mm. Bottom 60 x 38 mm sides, middle 60 x 38 mm x 2 mm thickness in all, The work is to be completed with all materials, accessories, labor, tools & tackles and in strict conformity with manufacturer's specifications & recommendations. All materials should be as per specification. Visible plan area is to be measured for finished work.	Sqm.	9.5		
12	<u>CONFERENCE TABLE</u> Providing and fixing U-shaped conference table of 2'3" width with 19mm thick BWP Phenol Formaldehyde block board of Green/Century or equivalent. The vertical supporting members of counter etc. are to be made of 19mm thick BWP Phenol Formaldehyde block board of Green/Century or equivalent. The table top has a neat hole, to be in the table for connecting the wires which is to be covered with dark coloured PVC insert(wire manager) with movable parts to put the wires and sockets to cover the hole neatly. The exposed block board/plywood to be covered with 4.0 mm thick veneer of approved shade and colour with PU polish. The internal and non-visible side of tables shall be painted with 3 coats of enamel paint over one coat of primer on the internal side. The table to be completed as per drawing and direction.	metres	16		
13	<u>PUTTY</u> Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm.	80		
14	<u>PAINTING</u> Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm.	500		
				TOTAL	
#GST will be paid extra as per applicable					