

**AO NANDED**

**TENDER FOR Interior civil and furniture work for KILLARI branch**

**TENDER ID NO.: AONAN202304002**

It has been decided by competent authority to update the parts of the tender notice as under:

SN	Description	Existing Schedule	Proposed Schedule
1	Price bid	<p>Single window counter: Providing &amp; fixing in position single window counter as per design, made of 18 mm / 19mm thick MR grade ply structure. The work top is to be made of 18 mm / 19mm thick MR grade ply structure. Thereafter, a double layer of flexi-ply (12 mm + 6 mm thick) ( ( the bottom of this niche to have provision of cove lighting with LED strips) is to be fixed with necessary fittings to the plywood structure and laminated glass in approved shade, . All exposed external surface finished with 1 mm high gloss laminate and internal surfaces finished with 0.8 mm laminate of approved shade. The rate shall be inclusive of Providing &amp; Erecting in position, Glass dividers out of 12mm thk glass on front side of workstations of length 1500mm and height 700mm from the table top and to be placed in position with the D-brackets including edge moulding and polishing of the glass with provision of etching / frosted film etc complete, CPU trolley of approved make (with wheel arrangement), necessary fittings, fixtures, hardware such as channels, hinges, ball catches, automatic locking arrangement, wire managers etc including providing the necessary openings for electrical/computer wiring complete The work is to be completed with providing of foot rest, key board tray with telescopic arrangement. vertical glass of 12 mm to be fixed at the front of SWO with one horizontal glass ( if required) of approx 150mm with itching and crystal finish etc. complete as per instructions of EIC. Design and detail of the counters shall be as per Bank's new uniform colour, layout &amp; elevation policy available with Bank's Engineer. ( size 1500x900x750 mm)</p>	<p>Single window counter(1500x900x750 mm) : Providing &amp; fixing in position single window counter as per design, made of 18 mm / 19mm thick BWR grade ply structure. The work top is to be made of 18 mm / 19mm thick BWR grade ply structure. Thereafter, a double layer of flexi-ply (12 mm + 6 mm thick) ( ( the bottom of this niche to have provision of cove lighting with LED strips) is to be fixed with necessary fittings to the plywood structure and laminated glass in approved shade, . All exposed external surface finished with 1 mm high gloss laminate and internal surfaces finished with 0.8 mm laminate of approved shade. The work is to be completed with providing of foot rest, key board tray with telescopic arrangement. vertical glass of 12 mm to be fixed at the front of SWO with one horizontal glass ( if required) of approx 150mm with itching and crystal finish etc. complete as per instructions of EIC. Design and detail of the counters shall be as per Bank's new uniform colour, layout &amp; elevation policy available with Bank's Engineer. ( size (Note: cost is inclusive of partitions all , door, counter table, side table, front and side glass) The rate shall be inclusive of Providing &amp; Erecting in position, Glass dividers out of 12mm thk glass on front side of workstations of length 1500mm and height 700mm from the table top and to be placed in position with the D-brackets including edge moulding and polishing of the glass with provision of etching / frosted film etc complete, CPU trolley</p>

			of approved make, necessary fittings, fixtures, hardware such as channels, hinges, ball catches, automatic locking arrangement, wire managers etc including providing the necessary openings for electrical/computer wiring complete as per the instructions of Engineer. Elevation of the table shall be as directed by Engineer on site
2	Price bid	-	Note- 1. All the specification mentioned are to be strictly adhered and follow. 2. POP covering / Sponge need to be laid above existing tiles at contractors's cost, so that the tiles below are not damages . The contractor has to ensure that no scratches/damages are there to the tiles if observed the damages will be recovered by the contractor. No extra payment for this shall be made
3	Date of availability of Tender documents on Bank's website	From 25.04.2023 to 09. 05..2023 <b>Bank's Website:</b> <a href="https://bank.sbi/web/sbi-in-the-news/procurement-news">https://bank.sbi/web/sbi-in-the-news/procurement-news</a>	Extended up to 12.05.2023
4	Last date & time for submission of Technical Bid, EMD& Price Bid	From 25.04.2023 to 09. 05..2023 by 03:00 PM	Extended up to 15:00 HRS on 12.05.2023 The Bid shall be prepared and submitted in 2 parts – Technical Bid and Price Bid and is to be submitted through e-Tendering on the following service provider portal at: URL: <a href="https://etender.sbi/SBI/">https://etender.sbi/SBI/</a> and EMD in original at specified address.  <b>Note:</b> It is sole responsibility of the bidder to ensure submission of their bid online & time and submission of EMD in original at specified addressby stipulated date. The SBI shall not entertain bids received late due to any delay on account of delivery by the courier agency/speed post or any other mode for the reasons whatsoever.



5	Date and Opening of Technical Bid	15:30 PM on 09. 05..2023	Rescheduled on 12.05.2023 at 15:30 HRS
---	-----------------------------------	--------------------------	--

All other terms & conditions of the empanelment document will remain same.

  
Chief Manager (HR)

