

**Price Bid for Area Development Work of Muzaffarpur Main Branch under RBO
Muzaffarpur**

Date: . .2023

S.No.	Item Description	Unit	Qty	Rate	Amount
1	Providing and laying 80 mm thick factory made cement concrete interlocking paverblock of M35 grade made by block machine with strong vibratory compaction, of approved size, design & shape laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc including the cost of dressing and after test of paver blocks from a govt engineering college, al complete as per the direction of EIC/Bank. The cost includes watering, ramming and all other tools tackles to complete the job etc.	Sq.mtr	890.2		
2	Supplying laying, compacting and finishing coarse sand including royalty fees of mining department as per law to the site as per direction of EIC/Bank. Each compacted thickness shall not be more than 250mm. The pre and post level to be taken in 5m grid for determination of average depth of filling.	Cum	184.75		
3	Constructing brick masonry linear drain with cement mortar 1:4 (1 cement : 4 coarse sand) below FGL for drainage of rain/excess water to main drain. This includes 12-20 mm cement plaster over the brick work and finishing the internal and exposed surfaces with neat cement slurry to make the surface water tight.	Cum	18.29		
Amount in word:		Total in INR			

NOTE: ABOVE PRICE IS EXCLUDING GST BUT INCLUSIVE OF TRANSPORTATION COST AT SITE.
GST PAID EXTRA BY THE BANK AS PER RULE
ALL WORK TO BE DONE AS PER IS SPECIFICATION

(SIGNATURE)
AUTHORIZED SIGNATORY