

**PRICE BID FOR MINOR INTERIOR WORKS AT PROPOSED STARTUP CELL AT SBI TECHNOPARK  
BRANCH - FIRST FLOOR.**

SI No.	Description of work	Quantity	Unit	Rate	Amount
1	<b>Custom Made Full Height Solid Partition:-</b> Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beadings. Measurement for the partition area shall be considered from floor level to false ceiling level only.	22.00	Sq.M		
2	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	5.00	Sq.M		
3	<b>Wall and Column Panelling:-</b> Providing and fixing columns/ wall panelling to detail as shown in the drawing with 18 mm thick plywood finished with 1 mm thick laminate.	10	Sq.M		

4	<p><b>Gypsum Board False Ceiling:-</b> Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete. Rate to include closing of all wall openings with masonry or plywood, above the false ceiling level, as per Engineer's instructions.</p>	40	Sq.M		
	<p><b>Rate includes removal of the existing old grid ceiling/gypsum ceiling and removal of debris away from site.</b></p>				
5	<p><b>TABLE for CONFERENCE HALL of size - 0.75m x 3.75m :-</b></p>	1	Nos.		
	<p>Supply and fixing Conference hall table of size of the table is 3.75X0.75x0.75m. The width and height of the table is 75 cm and 75 cm respectively. The length of the table is 375 cm. The table top and sides are made of 18mm thick marinegrade plywood(IS 303 grade) finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip. The inner vertical portion of the table is with 18mm thick plywood, verticals to be given at 75cm c/c amd finished with 1mm thick laminate of approved color and brand with exposed top edges lipped with 2 mm pvc edge band tape.</p>				
	<p>12mm thick glass with polished bevelled edges to be provided for the table top with necessary wire manager. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Main vertical supports at corners and covering all around made of 18 mm thick plywood at front, sides and rear with necessary lipping etc. complete. Cable managers to be provided at intermediates as shown in the drawing. Also, necessary provisions, as required by for electrical works, such as fixing sockets/switches etc should be facilitated.</p>				

6	Demolition of existing aluminium partition of size 5.1m x 3m and stacking the materials as per Bank's instructions.	1	Lumpsum		
7	Fully glazed Door:- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.( DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	8	Sq.M		
8	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using <b>PT</b> Standard fittings like PT 90/PT 92 of <b>Dorma or equivalent make</b> at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns.	30	Sq.M		

9	<b>Officers Table</b>				
	Providing and fixing Branch Manager's table of size 1350 x 800 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip.12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete.	1	No.		
10	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface.	167	Sq.M		
11	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade over a coat of putty including cleaning the surface.	60	Sq.M		
12	Providing and Fixing Roller Blinds of good quality and approved colour.	15	Sq.M		
	<b>TOTAL</b>				
	<b>GST @ 18%</b>				
	<b>GRAND TOTAL</b>				