

BOQ FOR LOUVERS & ZEBRA BLINDS WORKS AT STATE BANK OF INDIA, ADMINISTRATIVE OFFICE, URBAN STATE PHASE-II BATHINDA.

Sl. No.	Description of Item	Qty.	Unit	Rates	Amount
	LOUVERS & ZEBRA BLINDS				
	Note: It is the responsibility of the vendor to co-ordinate with other vendors/ bank officials and state/ central departments etc as required. Vendor to arrange its own electricity supply/ water arrangement etc required for its working & operations. However, if available at site, vendor could use the same. The rates mentioned in the items to include all lead and transportation and no additional payment will be paid on account of lead and transportation charges. The vendor is required to dispose of all the rubbish/ unserviceable material to the nearest dumping ground & no additional payment will be made in this regard. The vendors are advised to visit the site and understand the requirements first, thereafter quote their rates and in case of any query regarding the technical aspect or item/ requirement, he may contact the Project Architect/ Engineer – In – Charge.				
1	LOUVERS ON VERTICAL SURFACE	590	Sqft		
	Providing, supplying & fixing Charcoal/ PVC based Louvers of approved shade with the required groove pattern as approved by the Bank on the vertical surface on the predetermined locations. The Item to include fixing of 8 thick HDF board (Moisture content- < 8%, Water Absorption 5% after 2 Hours Soaking)(Make. GREENPLY/ Century / Duro) on the wall with the appropriate arrangement. Placing louvers on the 8 mm thick HDF board with the approved adhesive so as to fix them properly on the board. The item to include cutting required for electrical DB, MCB, sockets, switches etc. The item to also include wastage of materials and measurement to be done of the visible surface.				
2	ZEBRA BLINDS	200	Sqft		
	Providing, supplying & fixing Zebra Blinds of approved make, shade etc as per the directions of the Bank at the predetermined locations. The fabric used should be dust, moisture resistant and the vendor to get the sample approved from the Bank before supplying the items.				
3	FLOOR TILES	250	Sqft		
	Providing and laying Doubly charged/ Full body charged (as approved by the Engineer – In – Charge) Vitrified tiles of size 800 mm x 800 mm or as approved by the Engineer – In – Charge/ Bank Officials in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colors and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/ sqm. The joints in tiles to be of 3 mm and the same are to be grouted with epoxy grout as approved by the Bank. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. The item to include the cost of brick ballast/ PCC/ mortar etc required below the tile surface to either raises the level/ makes the base strong/ hard. The work also include repair of tiles as required.				
	Total value of works				

GST will be paid extra as applicable