

PRICE BID FOR INTERIOR WORK (NEW PREMISES) AT SBI BRANCH HALALPUR, DIST - SONIPAT, HARYANA					
S.No.	Particulars	Unit	Qty	Rate (Rs.)	Amount (Rs.)
<b>INTERIOR WORKS</b>					
<b>1.0</b>	<b>PARTITIONS AND DOORS</b>				
	Measurement of height shall be taken from finished floor level up to the level of false ceiling, in case of varying heights on either side of partition, average height shall be considered. The rates include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions. All wood framework to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti termite treatment properties.				
<b>a</b>	Providing & fixing <b>Solid Full Height Partition</b> 75mm thick with 45x50 mm GI sections (1mm thk.) of India Gypsum @ 600 mm c/c in both directions, (vertical member to be in one piece) and horizontal direction, 11mm thk. MDF board to be fixed on both sides and <b>1.0mm thick laminate pasted on both sides including provision of grooves as per design/drawing.</b> Partition to have 100 mm high laminate band at skirting on both sides of partition, Item includes melamine polish on the wood surfaces and finishing of grooves with polish etc. 12mm thk. toughened glass to be fix with aluminium profile section 20x45mm (powder coated black) having removable beading one side, as per detail drgs. Rest of specifications same as main specifications of partitions, complete to the satisfaction of the Architect / Bank's Engineer. <b>(Make of MDF :- Greenpanel, Action Tesa, Century) Make of Laminate: Merino, Aica, Archidlam.</b>	Sq.Mt.	30.00		
<b>b</b>	Providing & fixing 12mm thick clear toughend <b>Fixed Glass for BM Cabin &amp; Branch Entry</b> in aluminium profile section 20x45mm (powder coated black) having removable beading one side, as per detail drgs. and complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	27.50		
<b>c</b>	Providing and fixing front <b>Frameless Patch Fitting Door</b> with 12mm thick toughened glass with frame less glass fittings & double action floor springs as per design. The item includes providing and fixing S.S. handle not less than 450mm long on both side of glass, locks and fittings (Enox) as per the manufacturer's specifications etc. complete to the satisfaction of Architect/ Bank's Engineer. Size of door :- 1000x2300 (H)mm. <b>(Make of door Spring :- Enox ,Ozone, Dorma)</b>				
<b>(i)</b>	Door Size:- 3'-3" x7'-6"	Nos.	2.00		
<b>(ii)</b>	Door Size:- 3'-6" x7'-6"	Nos.	1.00		
<b>d</b>	Providing & fixing <b>Low Height Partition (SWO Counters)</b> 75mm thick with same specifications as item no. 1(a) above but with 1.0mm thick <b>hi-gloss (white) laminate</b> fixed on both sides with <b>12mm thick toughened glass</b> fixed in partition with U-brackets as per design/ drawing, height of partition to be 1350mm High complete to the satisfaction of the Architect / Bank's Engineer. <b>(Make of MDF :- Greenpanel, Action Tesa, Century) Make of Laminate: Merino, Aica, Archidlam, Green.</b>	Sq.Mt.	13.50		
<b>e</b>	Providing & fixing <b>Glazed Door</b> as per design/drawing with 75x50 mm teak wood polished frame (chaukhat). The flush door shutter 35mm thick waterproof of specified make laminated with 1mm thick laminate on both sides. Item includes fixing <b>8mm thick toughened glass</b> fixed with Steam Beech wood beading as per size in design/drawing polished in mellamine finish. The door is to be complete with mortice door lock & SS handle ,S.S stopper, 125mm S.S. hinges , Door Closer <b>(Hettich/ Dorma/ Godrej)</b> . All wood surfaces to be mellamine polished complete to the satisfaction of Architect / Bank's Engineer.	Sq.Mt.	5.00		

S.No.	Particulars	Unit	Qty	Rate (Rs.)	Amount (Rs.)
<b>SUB TOTAL : 1.0 : PARTITIONS AND DOORS</b>				<b>RS.</b>	
<b>2.0</b>	<b>PANELLING</b>				
<b>a</b>	Providing & fixing <b>Panelling (Laminate)</b> with frame work with 45 x 25 mm GI sections (India Gypsum) @ 600 mm c/c in both directions, with 11mm thk. MDF board finished with 1.0mm thk. laminate in two or more colour. Panelling to have skirting of 100 mm high laminate, 1mm thick with provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer.	Sq.Mt.	77.00		
<b>b</b>	Providing & fixing <b>additional box</b> panelling behind SWO counters as per design with specifications same as item 2(a) having depth 150 /180 mm as per design/details with extra frame work as necessary for making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc.complete to the satisfaction of Architect/Bank's Engineer. <b>(Note only front facia to be measured for payment.)</b>	Sq.Mt.	4.50		
<b>c</b>	Providing & fixing <b>Low Ht. Panelling (Laminate)</b> with frame work 45 x 25 mm GI sections (India Gypsum) @ 600 mm c/c in both directions, with 11mm thk. MDF board finished with 1.0mm thk. laminate in two or more colour. Panelling to have skirting of 100 mm high laminate, 1mm thick with provision of extra frame work as necessary for skirting and Steam Beech wood beading out of 45x25mm on top polished in mellamine finish wherever required , making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer. <b>(Only front facia to be measured for payment.)</b>	Sq.Mt.	8.00		
<b>d</b>	Providing & fixing <b>Digital printing glass 8mm thick</b> as per design on wall panelling behind SWO counter as per design, pasted with silicone on MDF board 11mm thk. with frame work of 45 x 25 mm GI sections (India Gypsum) @ 600 mm c/c in both directions fixed to wall complete to the satisfaction of the Architect /Bank's Engineer.	Sq.Mt.	8.00		
<b>e</b>	Providing & fixing <b>Lacquer Glass (5mm thickness)</b> panelling on specified area having 50% lacquer glass & rest laminate finish. Base framing with 45x25mm G.I sections (India Gypsum) on wall @ 600 c/c in both directions with 8mm comm. ply. After having fixed lacquer glass on 50% surface area the balance area to be raised by fixing 4mm mdf finished with 1mm thick laminate in level with lacqure glass, as per drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer.	Sq.Mt.	17.5		
<b>f</b>	Providing & fixing <b>Panelling (Artificial Grass )</b> with frame work with 45 x 25 mm GI sections (India Gypsum) @ 600 mm c/c in both directions, finished with 8mm thk. commercial ply. The ply to be covered with 6.0 mm thick artificial green foliage panel 400x600 each, as per drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer.	Sq.Mt.	2.5		
<b>SUB TOTAL : 2.0 : PANELLING</b>				<b>RS.</b>	

S.No.	Particulars	Unit	Qty	Rate (Rs.)	Amount (Rs.)
<b>3.0</b>	<b>FALSE CEILING</b>				
	Item includes providing False Ceiling in plane, curve shape and design .Suspending system and frame work shall match layout of A.C. ducts / grills, electrical /fire protection wiring / fixtures, return air grills etc. Rate to include provision of extra frame work, necessary scaffolding for double height needed due to layout of other utilities refered above and fixtures etc. <b>Including finished with a top coat of paint. (Measurement shall be taken of the plan area only nothing extra Paid for cove design and verticle sections &amp; Bend Etc.)</b>				
<b>a</b>	Providing and fixing <b>Gypsum Board False Ceiling</b> with INDIA GYPSUM ULTRA main ceiling sections at 1200 c/c and cross members at 450 c/c of INDIAN GYPSUM. The grid work to be suspended from ceiling with hangers at every 1200 c/c in both directions. The Frame work to be as per manufacturer's specifications. 12.5 mm thk. GYPBOARD to be screwerd to the frame. The board to be finished with filling the tapered edges of the board with jointing compound and finishing with paper tape of INDIA GYPSUM. The ceiling to be <b>finished with a top coat of paint</b> as per manufacturer's specification along with provision of all necessary cut outs for electrical / air conditioning grills and necessary frame work including cove and curve designs etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	135.00		
<b>b</b>	Providing and fixing <b>False Ceiling with Mineral Fibre Acoustic Ceiling Tiles</b> Dune Premier 600x600mm x15 mm (thk.) of Armstrong / USG Boral with MICROLOOK edges and having noise reduction properties laid on exposed grid system with 16mm wide <b>Silhouette(black)</b> type T-section flanges of white colour, main runners spaced at 1200 mm c/c securely fixed to the soffit of structure with approved hangers at 1200 mm maximum c/c. Flush fitting 1200 mm crossed tees to be interlocked between main runners at 600 mm c/c to form 1200 x 600 modules. 1200 mm cross tees to be crimped. 600 x 600 module to be formed by fixing 600 mm long flush fitting cross tees centrally between the 1200 cross tees. Rate to include making necessary cut-outs or openings for light fixtures, air conditioning grills/diffusers/speaker and other utilities etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	45.00		
<b>SUB TOTAL : 3.0 : FALSE CEILING</b>				<b>RS.</b>	
<b>4.0</b>	<b>COUNTER/ TABLES/ WORKSTATIONS</b>				
	All Tables/ Counters/Work stations to have 18mm thk. BWR ply top and sides and 1.0 mm thk. laminate (Decorative/Texture/Metallic/High Gloss) finish on exposed surfaces along with 0.8 mm thk. white laminate on inside surface, drawer units to be made from 12 mm thk. BWR ply with 18mm thk. BWR ply FASCIA with 1.0 mm thk. laminate finish (as per individual item).The drawers to run on telescopic drawer channels. Drawer units shall have two smaller and one bigger drawer and auto locking arrangement (Godrej). Footrest 75x50mm made of 2nd class teakwood member to be fixed in each table. The rate shall include providing all hardware such as drawer channels, S.S. handles,lock,cable manager (Hettich/ Dorma/Haffele) etc. complete. The item also includes a tray for keyboard runing on telescopic channel, finshed with laminate on top and rounded front of size 560x450mm, readymade metal CPU trolley (Ebco) with castors etc. complete to the satisfaction of Architect/ Bank's Engineer.				

S.No.	Particulars	Unit	Qty	Rate (Rs.)	Amount (Rs.)
a	Providing and placing <b>Branch Manager Table</b> made of 12mm thk. BWR ply finished with approved 12mm thk. <b>white solid acrylic surface</b> on table and sides made with 19mm thk. commercial ply finished with 1.0mm thk. high gloss decorative laminate. Modesty panel to be made of 12mm thk. frosted toughened glass. Table top edges to be approx. 50mm thk. with corian finish as per design & details. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/drawing. The table size shall be 2250x750x750(H)mm.	Nos.	1.00		
b	Providing and placing in position <b>Officer Table</b> made of 18mm thk. commercial ply top and sides finished with 1.0mm thk. laminate. Front modesty panel to be made of 18mm thk. commercial ply finished with 1.0mm thk high gloss laminate in shade as per SBI standards. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing.				
	Table size shall be 1600x750x750 (H)mm.	Nos.	3.00		
c	Providing and fixing <b>Side Table of Officer Tables</b> and finished with laminate 1mm thick as per color & shade. The side table to have shuttered storage below with one shelf. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles (Hettich/ Dorma/Hafele) and locks (Godrej) etc. complete as per design/drawing. The side table size shall be 1000x450x750(H)mm.	Nos.	3.00		
d	Providing and placing in position <b>Banking Counters</b> in straight/curved shapes 750 mm high made of 18 mm thk. exterior grade ply duly rounded with 6mm thk. flexi ply covering in 750mm wide working top, finished with <b>12mm thk. high density white solid acrylic surface (Dupont/ LG/ Merino) in curved</b> shape and rest of the structure made from 19mm thk. BWR ply finished with 1.0 mm thk. high gloss laminate in shade as per SBI standards. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above but with divisions for currency as per Bank's instructions. The drawer units shall be provided with autolocking system (Godrej) for drawers etc. complete as per design/ drawing. <b>(Measurement will be taken from top plan).</b>	R.Mt.	6.40		
e	Providing and fixing <b>Side Storage Tables for Banking Counters &amp; Branch Mgr.</b> made of 18 mm thk. BWR ply board having 450mm wide top provided with <b>12mm thk. high density corian solid acrylic surface (Dupont/ LG/ Merino)</b> and sides finished with 1mm thk. laminate. The side table to have shuttered storage below with one shelf. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles (Hettich/ Dorma/Hafele) and auto locking arrangement (Godrej). etc. complete as per design/drawing.				
	Side table size shall be 1000x450x750(H)mm.	Nos.	6.00		
f	Providing <b>Wooden Dressing Table</b> for locker room including looking mirror as per design drawing/ selection etc. complete to the satisfaction of Architect/Bank's Engineer.	Nos.	1.00		
g	Providing and fixing <b>Wall Mounted Writing Desk Unit</b> made of 18mm thk. BWR ply finished with 1.00mm thk. laminate and having shelves for keeping Bank slips, as per the design/ drawing etc. complete to the satisfaction of Architect/Bank's Engineer. Size of the writing desk shall be 1200x450x1100(H)mm.	Nos.	1.00		

S.No.	Particulars	Unit	Qty	Rate (Rs.)	Amount (Rs.)
h	Providing and fixing 12mm thk. <b>Toughened Glass</b> in front portion of single window counters with s/s brackets including cutouts for passing currency and communication as per drawing. The edges of the glass to be machine polished complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	7.50		
<b>SUB TOTAL : 4.0 : COUNTER/TABLES/WORKSTATIONS</b>				<b>RS.</b>	

<b>5.0</b>	<b>STORAGE CUPBOARDS</b>				
a	Providing & fixing <b>Low Height Box Storage Cupboard</b> 450mm deep with frame, all sides, shelves to be made with 18 mm thk. BWR ply and 6mm thk. BWR ply fixed at the back. The shutters to be made with 18mm thk. BWR ply. Shutters, top and sides finished with 1.0 mm thk. laminate on all exposed surfaces. All edges to have 2mm thk. edge binding tapes as per details, all shutters to be made overlapping the frame and edges of shutters to have 1mm thk. edge binding tapes(rehau) as per details including S.S. handles, magnetic catchers, self closing hinges, locks ( <b>Godrej/ Hettich/ Hafele</b> ) etc. The item includes polishing the wood surfaces with melamine polish and inside surfaces to have 0.8 mm thk white laminate finish etc. complete to the satisfaction of Architect / Bank's Engineer. <b>(Only front elevation will be considered for area calculation)</b>	Sq.Mt.	15.50		
<b>SUB TOTAL : 5.0 : STORAGE CUPBOARDS</b>				<b>RS.</b>	
<b>6.0</b>	<b>MISCELLANEOUS</b>				
a	Providing & applying the walls, ceiling and elsewhere with <b>Plastic Emulsion Paint (roller finish)</b> after preparing the base by removing existing paint/ finish and applying 2-3 coats of birla white putty for making the surface plane & smooth and then applying 2 or more coats of plastic emulsion paint with final coat done with rollers as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt	50.00		
b	Providing and applying approx. 12mm thk. <b>POP Punning</b> on walls , ceiling and elsewhere to give a clean smooth and plumb surface as per the instructions of Architect/Bank's Engineer.	Sq.Mt	17.00		
c	Providing & applying <b>Texture Paint</b> (Berger/ Dulux/ Asian) in two or more shades as approved by Bank with roller & spray, after preparing the base for the same as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt	17.00		
d	Providing and fixing panelling in ATM in position with Aluminium Composite Paneling (ACP) for Cladding with framing of aluminium tube section of min. 50mmx25mm and 20 gauge at a spacing of 600mm center to center both ways. ACP to be of approved shade in 600mm wide panels or distributed equally. ACP sheets to be fixed to the frame with 3M make adhesive along with mirror screws. ACP sheets ( <b>Alubond/ Alstone/ Alcobond</b> ) to be min. 3mm thick with aluminum foil thickness to be min. 0.25mm on both sides. Item includes providing additional sections to fix indoor AC units which will be installed at the highest position etc. complete as per instructions of Architect/ Bank's Engineer. <b>Item includes scaffolding as may be required etc. complete as per site conditions.</b>	Sq.Mt	47.00		

S.No.	Particulars	Unit	Qty	Rate (Rs.)	Amount (Rs.)
e	SHUTTER BOXING - Providing & fixing in position Aluminium Composite Panel (ACP) with framing of Aluminium Tube sections of min 2" * 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. ACP thickness of 3mm minimum. Aluminium foil thickness to be min 0.25 mm., 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. ACP thickness of 3mm minimum. <b>Alubond, Eurobond, Fujibond, Alcobond</b> or equivalent ISI approved brands to be used. Shades to be as per bank's approval. Trap door will be 12 mm marine ply finished with ACP, complete as per instructions of Architect/ Bank's Engineer. <b>Item includes scaffolding as may be required etc. complete as per site conditions. (Only front facia to be measured for payment.)</b>	Sq.Mt	15.00		
f	Providing and fixing <b>Louvered Shutter Cabinet Box</b> for main panel fabricated out of 19 mm thick commercial board and finished with 1 mm thick laminate of approved make, louvers aluminium powder coated. Coating of fire retardent and anti-termite paint inside. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	5.50		
g	Providing & fixing in position 4mm thick <b>Lacquered glass (Blue)</b> of approved make, shade duly fixed with adhesive/ s/s screw wherever required in desired pattern etc. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	4.50		
h	Providing & fixing <b>Frosting film 3M</b> wherever required in desired pattern etc. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	11.50		
i	Providing and fixing wooden <b>wicket gates of apprx. Size 900mm X 1200</b> mm made of 18 mm thk. BWR ply board & both sides laminated with godrej premium night latch lock hinges etc. complete as per instructions of Architect/ Bank's Engineer.	No.	1.00		
j	Disposal of rubbish/ mulba after dismantling/ demolition including clearing building waste of all types, rank vegetation etc. all complete as per the directions of Bank's Engineer/ Architect.	No.	1.00		
<b>SUB TOTAL : 6.0 : MISCELLANEOUS</b>				<b>RS.</b>	
<b>SUBTOTAL INTERIOR WORKS</b>				<b>RS.</b>	

**Note:-** The rates quoted includes all other taxes, duties, loading, unloading, transportation, other expenses etc to site. only GST will be paid Extra.