		D400		2002)
TENDER SCHEDULE FOR INTERIOR WOR	KS FOR	RACC	IUMKUR (63	5083)
Description	Qty	Unit	Rate	Amoun
PARTITIONS	Qty	Unit	Tuto	
FULL HEIGHT PARTITIONS - PARTLY GLAZED	65.00	Sq.M.		
Providing and fixing metal stud dry wall partition	00.00	Oq.m.		
with following specifications:				
Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
 12mm Exterior Grade MDF (EG-MDF) Board fixed on both sides with 25mm dry wall screws for the entire height of the partition. Partition fixed with 1.0mm laminate sheet on both sides as per the following : 				
Skirting level upto 100 mm from FFL to have 1.0mm laminate of dark blue colour				
From 100mm to 300mm level to have 1mm Laminate (aqua blue color)				
From 300 mm level to 1070 mm level to have 1mm Laminate (white color)				
From 1070 mm level to 2135 mm level to have 8mm clear float glass fixed with with 85mm x 15mm alround jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.The glass sizes subject to design drawing etc.				
From 2135mm level to 2235mm level <u>1mm</u> <u>Laminate</u> (aqua blue color) on both sides as shown in drawing.				
Partition above 2235mm level to have 1mm Laminate (white color) as shown in drawing.				
All MDF members to have minimum two coats of LOW VOC or NO VOC white duco paint finish.				

All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.			
2 HALF HEIGHT PARTITIONS	50.00	Sq.M.	
This item includes partitionsforSWOcounters, officer cubicles etc as per thelayout plan.Height of the partitions shall be asmentioned in the drawings.			
Same as full height partition Solid above, but for height of 1220mm from finished floor level, to a neat finish as per drawings and directions etc., complete and including the following:			
to be finished with 1.0mm laminatecapping of 75mm on top, 50mm bands of 6mm acrylic soild surface (Corean) on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete. (Corean shall be measured separately)			
Partition fixed with 1.0mm laminate sheet on both sides as per the following :			
Skirting level upto 100mm from FFL to have 1.0mm laminate of dark blue colour			
From 100mm to 300mm level to have 1mm Laminate (aqua blue color)			
From 300mm level to 1070mm level to have 1mm Laminate (white color)			
From 1070mm level to 1170mm level 1mm Laminate (aqua blue color			
From 1170mm level to 1220mm level to have to be finished with 1.0mm laminateon both sides as shown in drawing.			
3 32MM DOORS IN PARTITIONS - with glass panel:	4.00	Sq.M.	
Providing and fixing 32mm thick solid core flush shutter with 85mm x 35mm MDF frame with rebate alround the jamb and shutter fixed with 1mm Laminate as specified on both sides with glass panel of 8mm clear float glass fixed with 19 x 19mm beading on both sides and glass pasted with 3M privacy film as per design.			

4	The rate to include necessary hardware viz., door stopper, door buffer, pair of "H" type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC white duco paint finish for all MDF members, etc., complete as directed. <u>32MM DOORS IN PARTITIONS : solid</u> Same as <u>32mm Door in Partitions - with glass</u> <u>panel</u> as per above but for Solid door without glass panel and other specifications remaining	3.50	Sq.M.	
5	FIRE PROOF METAL DOOR (For UPS Room) :	6.00	Sq.M	
	Providing and fixing fire resistant door frame as section 143x57mm having built in rebate made out of 16 SWG G.I sheet(Zinc coating not less than 120gm/sqm) duly filled with vermuculite based concrete mix, suitable for mounting 60 minutes fire rated door shutters. the frame is fitted with intumuscent fire seal strip of size 10x4mm(minimum) alround the frame & fixing with dash fastener of approved size & make. Fire resistant door shutters of 60 minutes fire rating conformingto IS:3614(part-II), tested & certified as per laboratory approved by Engineer-in-charge, with suitable mounting on door frame, consisting of vertical styles, lock rail, top rail 100mm wide, bottom 200mm wide, made out 16 SWG G.I sheet(Zinc coating not less than 120gm/sqm) duly filled FR insulation material & fixing with necessary stainless steel ball bearing hinges of approved make. Including applying a coat of approved fire resistant primer etc. all complet as per direction og engineer-in-charge.			
		0.00		
6	WICKET GATE - for SWO Counters Wicket gate specified below may also be used with other low height partitions elsewhere in the branch if required, with height of wicket gate	9.00	Sq.M.	

Providing wicket gate made of 32mm solid flush door with alround PVC edge banding / BW lipping and height to match low height partitions. Wicket gate shall be finished with 1.0mm laminate sheet on both faces and shall fixed to partition with 85mm x 35mm MDF frame on sides with SS hinges as required with handles, stoppers, self lock etc complete. Wicket gate shall have self lock from inside fixed at lower height as per instructions and Bank requirement			
7 FIXED GLASS WORKS FOR PARTITIONS : (12MM TOUGHENED GLASS)	12.00	Sq.M.	
Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Skirting level upto available Ceiling / beam / lintel level and inline with wooden parttions / doors etc as per layout plan. The glass is to be fixed onto the ply/Exterior Grade MDF base with patch fittings and all the edges of the glass to be machine polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions including silicon sealant between glass panels etc., complete.			
8 12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:	3.00	Sq.M.	
Providing, making and fixing in position Fixed 12mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1830mm x 2135mm - 2440mm in two leaves, and Partition Doors of approximate size 900 - 1065mm x 2135mm - 2440mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.			

	(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1830mm - 1525mm x 2440mm - 2135mm and Single Door approx. Size: 900mm - 1220mm x 2440mm - 2135mm using 12mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Door Lock at 915 ht complete as per drawing.			
	(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.			
	WALL PANELLING: WALL PANELLING IN BANKING HALL	40.00	Sq.M.	<u> </u>
	Same as Full height Partition - Solid, as per relevant specifications above, but for Wall Panelling. The basic frame work to comprise all Exterior Grade MDF (EG-MDF) cladding as specified, but only on one side, to a neat job as per drawings and directions etc., complete.			
	Providing 18mm thick Exterior Grade MDF jamb for door and window openings of suitable depth as per site conditions and laminated with 1mm thk			
	All MDF members to have NO VOC or LOW VOC white duco paint finish.			
10	LACQUERED GLASS WORK FOR BM CABIN	1 00	Sq.M.	
	Providing and fixing in position 12mm toughened lacquered glass (colour - same as per laminate for skrting) for glass partition. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughining the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be 1525mm (h) x 830mm (w) subject to site conditions. The rate is for a finished item of work etc., complete as directed.		<u> </u>	

			<u> </u>	
11	WALLPAPER	3.00	Sq.M.	
	Providing and fixing approved quality wall paper			
	of washable grade including all adhesive, cutting,			
	pasting etc complete.			
	(Basic price Rs 800 per smt excluding tax,			
	transportation,wastage, loading / unloading, etc.,)			
	Note : Measurement will be taken only for wall			
	paper actually pasted at site.			
	FALSE CEILING:			
	Providing, making and fixing in position the			
	following types of different false ceilings with			
	different materials as specified below for a			
	finished item of work as per drawings and			
	directions etc., complete.			
12	Grid False Ceiling : Mineral Fibre Tile	128.00	Sq.M.	
	Providing & Fixing of Mineral Fibre Acoustical			
	Suspended Ceiling System with 15mm Tiles and			
	Exposed GRID. The tiles should have Humidity			
	•			
	Resistance (RH) of 90% - 99%, NRC 0.5, Light			
	Reflectance ≥87%, Thermal Conductivity k =			
	0.052 - 0.057 w/m K, Colour White, Fire			
	Performance UK Class 0 / Class 1 (BS 476 pt - 6			
	&7) in module size of 600 x 600 x 16mm , suitable			
	for Green Building application, with Recycled			
	content of 30% - 45% .			
	The tile shall be laid on Microline / Silhouette			
	profile grid system with 15mm - 16mm white			
	flanges incorporating a 6mm central reveal in			
	white/black colour and with a web height of 38mm			
	and a load carrying capacity of minimum 8			
	Kgs/M2 & minimum pull out strength of 100 Kgs.			
1				
	Microline / Silhouette, Main Runners & Cross			
	Tees to have mitred ends & "birdsmouth" notches			
	to provide mitred cruciform junctions. The T			
	Sections have a Galvanizing of 90 grams per M2			
	and need to be installed with Suspension system			
	as per manufacturers details.			

	The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent			
	support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.			
13	PLAIN GYPSUM FALSE CEILING	85.00	Sq.M.	
	Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:			
	27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.			
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.			

	Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed. The ceiling shall be finished with 2 coats of premium emulsion paint over primer putty etc complete			
14	VERTICAL FACES IN FALSE CEILING - UPTO 150mm HEIGHT	32.00	Rmt	
	Same as Plain false ceiling above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.			
	STORAGE UNITS:			
15	LOW HEIGHT STORAGE UNITS	14.00	Sq.M.	
	Providing, making and placing in position Storage Units of 1220mm high abutting wall and 760mm high as back credenza or abutting partition made in 18mm EG-MDF to all members except table top and 25mm block board for table top and 8mm EG- MDF for backing sheet . Tto be finished with 1.0mm laminate. All other exposed faces of the unit to have 1mm Laminate as specified and all unexposed faces to have 0.8mm Laminate. NO VOC or LOW VOC white duco paint finish for all wooden members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and PVC edge banding / BW lipping 20mm x 6mm etc., as per drawings and directions etc., complete.			
	Storage units shall have a internal horizontal shelf of 19mm block board finished with 0.8mm laminate on both sides with PVC edge banding / BW lipping polished malanine finish			
	NOTE			
	All exeposed surface shall be finished with 1.0mm laminate			
40	Full Height Otomore	45.00	Cc M	
10	Full Height Storage	15.00	Sq.M.	

Same as low height storage unit above but for			
2.1m height with internal shelves at every			
400mm, without Corian sheet on top, and other			
specifications remaining the same			
17 BRANCH HEAD TABLE:	1.00	Nos	
Table : 1950 - 2130mm x 900mm x 760mm			
Side Runner : 1065 - 1220mm x 450mm x			
Providing, making and placing in position			
Executive Table and Side Table with following			
Main Table and side Table top and to be made in			
25mm block board with 1mm thick lamination .			
The front side of the table to have a inverted " C "			
made with 2 x 18mm thick EG-MDF cladded with			
1mm lamination on the front and the verticals			
towards the modesty panel. The modesty panel			
to have 18mm EG-MDF cladded with 6mm thk			
toughened lacquered glass in blue colour as			
specified.			
The "L" shaped table top on the back side to			
have 50mm edge alround and to be cladded with			
6mm acrylic solid surface.			
All other members to be with 18mm EG-MDF and			
all exposed faces of the table to have 1mm			
lamination as specified.			
All the edges of 18mm EG-MDF to have PVC			
edge banding / BW lipping 20mm x 6mm maline			
One readymade CPU mobile pedestal .			
· · · · · · · · · · · · · · · · · · ·			
One Molded Key Board Tray with channels etc.,			
One Three Drawer Unit made with 18mm EG-			
MDF and 12mm EG-MDF. The unit to have 3nos			
equal drawers. The rate to include all necessary			
hardware viz., telescopic drawer channels,			
handles, locks, etc., and edges finished with PVC			
edge banding / 20mm x 6mm MDF edge lipping			
etc.,			
Side Table having one pedestal unit with 450mm			
wide having one drawer & one shutter with 1no			
.			
internal shelf made with 18mm EG-MDF and			
19mm plywood all laminated and with necessary			
hardware viz., 'W ' hinges, handles, locks, tower			
bolts, etc., and PVC edge banding / 20mm x 6mm			
MDF edge lipping etc			
All the unexposed faces to have 0.8mm			
- I andrata			
Ready Made Modular Foot Rest - 400mm x			
350mm x 65mm.			

				1	
	The cost to include all materials, labour etc., for a				
	finished item of work as per drawings and				
	directions etc., complete.				
18	OTHER OFFICER'S EXECUTIVE TABLES:	10.00	Nos		
	Table : 1500 - 1650mm x 760mm x 760mm	10.00	1100		
<u> </u>					
	Side Runner : 915 - 1050mm x 450mm x				
	Providing, making and placing in position				
	Executive Table and Side Table with following				
	specifications.				
	Main Table and side Table top and to be made in				
	25mm block board with to be finished with 1.0mm				
	laminate on top. The front side of the table to				
	have a inverted " U " made with 2 x 18mm thick				
	EG-MDF finished with 1.0mm laminate incuding				
	•				
	the verticals towards the modesty panel. The				
	modesty panel to have 18mm EG-MDF cladded				
	with 1mm Laminate as specified.				
	The " L " shaped table top on the back side along				
	with side tabe to have 49mm edge alround, which				
	is to be achieved by adding a 75mm piece of				
	18mm EG-MDF to the table top from bottom.				
	All other members to be with 18mm EG-MDF and				
	all exposed faces of the table to have 1.0mm				
	laminate as specified.				
	All the edges of 18mm EG-MDF to have 20mm x				
	6mm MDF lipping /PVC edge banding.				
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.				
	One Three Drawer Unit made with 18mm EG-				_
	MDF and 12mm EG-MDF. The unit to have 3				
	equal drawers. The rate to include all necessary				
	hardware viz., telescopic drawer channels,				
	handles, locks, etc., and 20mm x 6mm MDF /PVC				
	edge beanding etc.,				
	Side Table having one pedestal unit with 450mm				
	wide having one drawer & one shutter with 1 no				
	internal shelf made with 18mm EG-MDF and				
	19mm plywood with necessary hardware viz., ' W				
	' hinges, handles, locks, tower bolts, etc., and				
	20mm x 6mm MDF /PVC edge banding etc and				
	finished with 1.0mm laminate				
	All the unexposed faces to have 0.8mm Laminate.	T			

	Ready Made Modular Foot Rest - 400mm x			
	350mm x 65mm.			
	The cost to include all materials, labour etc., for a			
	finished item of work as per drawings and			
	directions etc., complete.			
<u> </u>				
19	Clerical Table same as above with out side	12.00	Each.	
	unit			
20	12MM TOUGHENED GLASS ON LOW HEIGHT	9.00	SQM	
20	PARTITIONS BETWEEN SINGLE WINDOW COUNTERS:	9.00	SQIVI	
	Providing, making and fixing in position 12mm			
	thick toughened clear float glass in sizes as per			
	design with cut out of 200mm x 150mm at position			
	to match Voucher tray. All the edges of the glass			
	to be polished for a smooth finish and the glass is			
	to be fixed with " D " brackets. The cost to include			
	all materials, labour, hardware etc., for a neat			
	finished job as per drawings and diretions etc.,			
	complete.			
	Glass size shall be as per length of low height			
	partiton after leaving about 300mm solid portion at both ends			
	Item includes providing Voucher tray of size 200 x			
	200, made of 19mm BB-laminated with BW			
	lipping /PVC edge banding etc and fixed onto the			
	low partition with all hardware etc complete			
21	ROLLER BLINDS	42.00	Nos	
<u> _ 1</u>	Providing and fixing in position of Roller Blinds of	42.00	1105	
	approved Fabric of Hunter Douglas / Mac / Vista			
	Levalor make or approved equivalent of approved			
	shade etc., as directed.			
	Shave etc., as unecteu.			
22	ACP CLADDING:	20.00	Sq.mts	
			39.1113	

	Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, The framing shall be fixed at intervals of 600mm c/c horizontally and vertically. using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges etc., complete for finished item of work but excluding cost of structural steel fabrication, scaffolding charges, if any, ACP Cladding - 4 mm thick.			
23	CONFERENCE TABLE 12'0' X 8'0" as per the Unifirm Internal Lay out colour scheme drawing	1	No	
	and specification, and as per instructions of engineer in charge comple			
	5 5 1			
24	High Back Chairs	2	Nos	
	APPROVED MAKE - MODEL	-	1105	
	GODREJ -Pulse HB			
	HOF - KAR-1007			
	BOSQ -TQ-Z-101			
	EUROTECH -Mate-HB			
	TRANSTEEL - KINETIC MESH HB			
	FEATHERLITE -FP Anatom HB			
25	Medium Back Chairs - Officers	26	Nos	
	APPROVED MAKE - MODEL			
	GODREJ - Oxbo MB			
	HOF - KAR-7005			
	BOSQ - TQ-Z-201			
	EUROTECH - Look-02			
	TRANSTEEL - FLUID BASICS			
	FEATHERLITE -Astro MBGS			
26	Low Back Chairs - Visitors	15	Nos	
	APPROVED MAKE - MODEL			
	GODREJ - Oxbo Visitor			
	HOF -VIT-1004			
	BOSQ - TQ-Z-301			
	EUROTECH			
	TRANSTEEL - LITE-V-KM-04-11			
	FEATHERLITE -Astro VA			

27	Low Back Chairs - Visitors (With out wheels)	16	Nos	
	APPROVED MAKE - MODEL			
	GODREJ - Oxbo Visitor			
	HOF -VIT-1004			
	BOSQ - TQ-Z-301			
	EUROTECH			
	TRANSTEEL - LITE-V-KM-04-11			
	FEATHERLITE -Astro VA			
28	Sofas			
	GODREJ - Parto			
	HOF -Redefino			
	BOSQ - DS-102			
	EUROTECH - Pearl			
	TRANSTEEL			
	FEATHERLITE - 238 -Pearl			
29	3 Seater sofa	1.00	Each	
	TOTAL INTERIOR WORK			
NOTE	e : Excluding GST as Applicable			
	Note : All the drawing and specification should be			
	following as per the Uniform internal lay out colour			
	scheme.			