

PRICE BID

ESTIMATE FOR RENOVATION OF 7 NO. TOILETS AT STATE BANK OF INDIA, ADMIN OFFICE, SHIMLA						
S.No.	DSR No.	Specifications	Qty.	Units	Rate	Amount
1	DISMANTLING & REPAIRWORKS					
1.1	15.23	Dismantling tiles in floors and dado including clearing the site as directed and disposal of the unserviceable materials/ debris away from the site with no cost & risk to the Bank.	1.00	job		
1.3		Disconnection of existing sanitary & CP fixtures, stacking of serviceable material & disposal of the unserviceable materials/ debris away from the site with no cost & risk to the Bank.	7.00	no.		
2	PLASTER WORK					
	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under,including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.				
	14.1.2	1:4 (1 cement: 4 fine sand)	44.00	sqm		
3	PCC					
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	1.50	cum		
4	WATERPROOFING					
	22.3	Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C., kitchen and the like consisting of:				
		(i) Ist course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions including rounding off junction of vertical and horizontal surface.				
		IIInd course of 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface				
		IIIrd course of applying blown or residual bitumen applied hot at 1.7 kg. per sqm of area.				
		IVth course of 400 micron thick PVC sheet. (Overlaps at joints of PVC sheet should be 100 mm wide and pasted to each other with bitumen @ 1.7 kg/sqm).	45.00	sq.m.		
5	VITRIFIED TILE FLOORING:					

	NS	Providing and laying 1st quality vitrified tiles (Marble series Double charged- JOHNSON/ KAJARIA/ RAK- as approved by Bank's Engineer/Architect) of following sizes, as per design pattern on floor & skirting with chemical or adhesive/ cement as directed and joints to be filled with grout of approved colour, including dismantling existing floor tiles and disposal of malba from site, cutting wooden/ aluminum doors to match new floor level, preparing of surface & disposal of malba from site.				
		24"x24" Vitrified tiles Double Charged- marble series.	35.00	sqm		
6	WALL TILES:					
	NS	Providing and laying 1st quality ceramic glazed tiles of size 12"x24" fixed usin cem. Sand mortar, with groves filled with white cement & matching pigment, complete in all respects Make: Kajaria, Nitco, Somany	180.00	sqm		
7	RCC SLAB WITH GRANITE FOR WASH BASINS					
	NS	Providing and fixing 18mm thk granite over RCC slab fixed with 1:3 cement sand mortar including moulding & grinding of exposed edges.The work should also including the rcc slab 2.5" thk in 1:2:4 cement concrete shutering & reinforcement in steel(12mmdia @ 6" bothways), complete in all respects.	3.50	sq.m		
8	ENAMEL PAINT					
	13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	13.61.1	Two or more coats on new work	10.00	sq.m.		
9	FALSE CEILING					
		Providing & fixing Armstrong false ceiling RH-99 with 600x600x16 mm Fine Fissured Beveled Tegular Edge false ceiling laid in Armstrong silhouette grid system. The frame work comprises of main runner spaced at 1200 mm centres securely fixed to structural soffit by approved hangers at 1200 mm maximum centres. Hangers (G.I. wires 4.0 mm dia) to be fixed by approved roof plug, level adjuster, screws etc. The last runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200mm long cross tee(with double stitching) to be inter locked between main runners at 600mm centres to form 1200x600mm module. Cut cross tees longer than 600mm to be supported independently. 600x600mm module to be formed by fitting 600 mm long flush fitting cross tee centrally between 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to wall @ 450 mm maximum centres. The rates include making opening for electric fixtures, A.C units etc. Rates include dismantling existing false ceiling and removal of malba from site, complete in all respect.	37.00	sq.m.		
		<i>MAKE: Armstrong, St. Gobain (India Gypsum)</i>				
10	TOUGHEND GLASS					
		Providing & Fixing 10mm thk. Toughned Glassfrosted finish in PaRTITIONS FOR URINALS with SS glass connectors of 304 Grade / , as per interior details/instruction of the Achitect/Engineer in charge.	3.00	sq.m.		

11	SPOT LIGHT					
		Supply of recess 7 watt LED COB spotlight assembly with driver complete as reqd. Phillips ASTRASPOT 7W or equivalent of Wipro / Bajaj	30.00	nos.		
12	G.I PIPES					
		Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.				
		15 mm dia nominal bore	120.00	mtr		
		20 mm dia nominal bore	32.00	mtr		
13	SOIL WASTE DRAINAGE PIPE WORK					
		Providing & fixing PVC(SWR) Pipes Type B, heavy class conforming to S13592-1992. (PRINCE / SUPREME / DIPLAST/ ASTRAL), including necessary fittings like bend, offset, collars etc., complete. Rates to include cutting/ chasing walls, floor, fixing pipe & making good the damages with cement mortar AND CONNECTING UPTO TO EXISTING EXTERNAL MANHOLES, complete in all respect.				
		75 mm dia	24.00	mtr		
		100 mm dia	10.00	mtr		
14	PVC PIPE WORK					
		Providing & fixing 150 mm dia PVC Pipes for exhaust fans, fixed to the roof slab/ suspended with suitable brackets/ hangers , including necessary fittings like bend, offset, collars etc., complete in all respect. (PRINCE / SUPREME / DIPLAST/ ASTRAL).	24.00	mtr		
15	CP FITTINGS & ACCESSORIES					
		<i>NOTE: The scope of work shall include removal of old fittings & fixtures wherever applicable. Making chase / holes & repairing them, complet in all respects. No extra payment shall be allowed for any incidental as above.</i>				
a)		Providing & fixing 15mm dia CP Bib Cock with CP wall flange, complete. MODEL = FLORA-F280002 of Hindware or equivalent of Cera.	7.00	nos.		
b)		Providing & fixing 15mm dia CP Angle cock with CP wall flange, complete. MODEL = ECO (Cat no.F-860077) of Hindware or equivalent of Cera.	24.00	nos.		
c)		Providing & fixing 15mm dia wall mounted BASIN MIXER , comprincing of inner body(Cat no F-280029) and the upper body (Cat no. 850093)including cutting and chasing the walls and making suitable connections, complete in all respects. MODEL=FLORA of Hindware or equivalent of Cera.	7.00	nos.		
d)		P: & F autoclosing Presmatic Angle cock with flange for urinals, complete in all respects. Model: F310016 of Hindware or equivalent of Cera.	7.00	nos.		
e)		P: & F aCP bottle trap including all connections, complete in all respects. Model: F850072 of Hindware or equivalent of Cera.	16.00	nos.		
f)		Providing & fixing round CP jali with CP outer ring, complete. Cat no. 5860055of Hindware or equivalent of Cera.	26.00	nos.		

g)		P & F 32mm, full thread CP Waste in wash basins, complete in all respects. Model F850002CP of Hindware or equivalent of Cera.	7.00	nos.		
h)		Providing and fixing in position approved make C.P. Brass liquid soap dispenser fixed into wall with C.P. brass screws complete in all respects including cutting and making good the wall etc. Make :(Ess Ess - Croma Series / Essel - Econ Series / Jaquar- continental series)	7.00	nos.		
i)		Providing and fixing CP Brass towel ring complete with brackets fixed to wooden cleats with CP brass screws with concealed fitting arrangement of approved quality and color. Make: Contessa of Hindware or equivalent of Cera.	7.00	nos.		
16	SANITARY FITTINGS:					
(a)		Providing & fixing floor mounted one piece WC with soft closing slim cove including fixing with anchor fasteners, etc complete as required.	7.00	nos.		
		MODEL=Cera Cruze (cat No. 92609) of Hindware or equivalent of Cera.				
b)		Providing & fixing table top Wash Basin complete in all respects.	7.00	nos.		
		MODEL: TOZZO (Cat No 10105) of Hindware or equivalent of Cera.				
c)		Providing & fixing urinal complete in all respects.	7.00	nos.		
		MODEL= CORTO-60022 , of HINDWARE/equivalent of CERA/SOMANY				
d)		Providing & fixing 600x450 mm or as directed, beveled edge mirror 5.5 mm superior glass (ATUL/ SAINT GOBBIN) complete with 6 mm thick hard board ground fixed to wooden cleats & CP brass screws, washers & clips etc. complete.	7.00	nos.		
		TOTAL				
AMOUNT IN WORDS:						