PRICE BID FOR THE INTERIOR FURNISHING WORK OF STATE BANK OF INDIA BRANCH AT ASSAN KALAN

Item	Qty	Units	Rate	Amount
PANELING/PARTITON Note: For the Paneling, Full height partitions and low height partitions the work measurement for costing shall be only of the plain visible surface, no extra cost for extrusions or extra frame work required as per drawing will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured.				
WALL PANELING (1.0mm Th. Laminate) upto 9'-0" high				
Providing and fixing panelling on column/wall. Framing shall consist of Heavy duty Aluminium Box (18 gauge) Sections 50mmx25 mm with maximum spacing of @ 600mm c/c Both ways horizontally and vertically on the column/wall. This framing would be covered by 8mm thk. ISI Marked Ply finished in approved 1.0mm Th. Laminate (Merino / Sunmica / Formica) of desired shade and design. Wooden molding, lipping etc. shall be provided wherever required as per drawing and deco painted in desired shade. The paneling shall have skirting and intermediate bands finished with metallic laminate of desired shade and design. The work shall also include the cost of making cut-outs for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/telephone/Data cabling etc.	81.78	SQ.M		
Makes :-				
Commercial ply: Century, Greenply, Archid ply				
Laminate : Aica, Greenlam, Marino, Formica				
FULL HEIGHT PARTITIONS UPTO 9'-0" HIGH Providing and fixing wooden full height partition with following	28.86	SQ.M		
	PANELING/PARTITON Note: For the Paneling, Full height partitions and low height partitions the work measurement for costing shall be only of the plain visible surface, no extra cost for extrusions or extra frame work required as per drawing will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured. WALL PANELING (1.0mm Th. Laminate) upto 9'-0" high Providing and fixing panelling on column/wall. Framing shall consist of Heavy duty Aluminium Box (18 gauge) Sections 50mmx25 mm with maximum spacing of @ 600mm c/c Both ways horizontally and vertically on the column/wall. This framing would be covered by 8mm thk. ISI Marked Ply finished in approved 1.0mm Th. Laminate (Merino / Sunmica / Formica) of desired shade and design. Wooden molding, lipping etc. shall be provided wherever required as per drawing and deco painted in desired shade. The paneling shall have skirting and intermediate bands finished with metallic laminate of desired shade and design. The work shall also include the cost of making cut-outs for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/telephone/Data cabling etc. Makes:- Commercial ply: Century, Greenply, Archid ply Laminate: Aica, Greenlam, Marino, Formica	PANELING/PARTITON Note: For the Paneling, Full height partitions and low height partitions the work measurement for costing shall be only of the plain visible surface, no extra cost for extrusions or extra frame work required as per drawing will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured. WALL PANELING (1.0mm Th. Laminate) upto 9'-0" high Providing and fixing panelling on column/wall. Framing shall consist of Heavy duty Aluminium Box (18 gauge) Sections 50mmx25 mm with maximum spacing of @ 600mm c/c Both ways horizontally and vertically on the column/wall. This framing would be covered by 8mm thk. ISI Marked Ply finished in approved 1.0mm Th. Laminate (Merino / Sunmica / Formica) of desired shade and design. Wooden molding, lipping etc. shall be provided wherever required as per drawing and deco painted in desired shade. The paneling shall have skirting and intermediate bands finished with metallic laminate of desired shade and design. The work shall also include the cost of making cut-outs for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/telephone/Data cabling etc. Makes:- Commercial ply: Century, Greenply, Archid ply Laminate: Aica, Greenlam, Marino, Formica FULL HEIGHT PARTITIONS UPTO 9'-0" HIGH Providing and fixing wooden full height partition with following	PANELING/PARTITON Note: For the Paneling, Full height partitions and low height partitions the work measurement for costing shall be only of the plain visible surface, no extra cost for extrusions or extra frame work required as per drawing will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured. WALL PANELING (1.0mm Th. Laminate) upto 9'-0" high Providing and fixing panelling on column/wall. Framing shall consist of Heavy duty Aluminium Box (18 gauge) Sections 50mmx25 mm with maximum spacing of @ 600mm c/c Both ways horizontally and vertically on the column/wall. This framing would be covered by 8mm thk. ISI Marked Ply finished in approved 1.0mm Th. Laminate (Merino / Sunmica / Formica) of desired shade and design. Wooden molding, lipping etc. shall be provided wherever required as per drawing and deco painted in desired shade. The paneling shall have skirting and intermediate bands finished with metallic laminate of desired shade and design. The work shall also include the cost of making cut-outs for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/telephone/Data cabling etc. Makes:- Commercial ply: Century, Greenply, Archid ply Laminate: Aica, Greenlam, Marino, Formica FULL HEIGHT PARTITIONS UPTO 9'-0" HIGH Providing and fixing wooden full height partition with following	PANELING/PARTITON Note: For the Paneling, Full height partitions and low height partitions the work measurement for costing shall be only of the plain visible surface, no extra cost for extrusions or extra frame work required as per drawing will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured. WALL PANELING (1.0mm Th. Laminate) upto 9'-0" high Providing and fixing panelling on column/wall. Framing shall consist of Heavy duty Aluminium Box (18 gauge) Sections 50mmx25 mm with maximum spacing of @ 600mm c/c Both ways horizontally and vertically on the column/wall. This framing would be covered by 8mm thk. ISI Marked Ply finished in approved 1.0mm Th. Laminate (Merino / Sunmica / Formica) of desired shade and design. Wooden molding, lipping etc. shall be provided wherever required as per drawing and deco painted in desired shade. The paneling shall have skirting and intermediate bands finished with metallic laminate of desired shade and design. The work shall also include the cost of making cut-outs for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/telephone/Data cabling etc. Makes:- Commercial ply: Century, Greenply, Archid ply Laminate: Aica, Greenlam, Marino, Formica FULL HEIGHT PARTITIONS UPTO 9'-0" HIGH Providing and fixing wooden full height partition with following 28.86 SQ.M

	(a)Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ max. 600mm c/c both horizontally and vertically. The frame shall be fixed rigidly at floor level and ceiling level wherever possible. The rate should also include necessary strengthening with additional members at doors and other openings. (b) The partition shall have 8mm Plywood fixed on both sides with screws for the entire height of the partition and finished with approved 1.0mm Th. Laminate (Merino / Sunmica / Formica) of desired shade and design on both sides. Wooden molding, lipping etc. as directed by Bank / architect shall be provided wherever required. The partition shall have skirting and intermediate bands finshied with metallic laminate of desired shade and design.		
	(c) The full height partition shall be WITH OR WITHOUT 8mm clear float glass with etching fixed as per drawing with 75mm x 12mm Teak wood jamb/chaowkhat around glass opening and 12mm x 12mm teak wood beading for fixing of glass on both sides. As per the direction of Engineer-in-charge and design. (d) The work to include providing and fixing of partly glazed wooden door shutters using 35mm readymade ISI flush door shutter with 1.0mm thick laminate of desired shade and design as per drawing with teak wood frame of 75mm x 40mm. The door shall have 6mm thick teak wood lipping all around the edges. The door shall have vision panels with 8mm thick clear float glass with etching fixed with double 14mmx25mm thick teak wood moulding as per design. The exposed surface of wood shall be deco painted in desired shade. The door shall be complete in all respect with hardware handles, godrej 6-lever lock/night latch lock, door stoppers, 8" tower bolts, hinges etc all in brass.		
	Note: (i) All ply to be sprayed with anty termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.		
	Makes :-		
	Commercial ply: Century, Greenply, Archid ply		
	Laminate : Aica, Greenlam, Marino, Formica		
	, , , ,		
3	LOW HEIGHT PARTITONS:UPTO 4'-6"HT.		

	Providing and fixing wooden low height partition with following	9.83	SQ.M	
	specifications:			
	(a)Providing & fixing partition made of 44 mm X 44 mm X 16			
	Gauge aluminium extruded sections frame @ max. 600mm c/c			
	both horizontally and vertically. The frame shall be fixed rigidly at			
	floor level and ceiling level wherever possible. The rate should			
	also include necessary strengthening with additional members at			
	doors and other openings.			
	(b) The partition shall have 9mm Plywood fixed on both sides with			
	screws for the entire height of the partition and finished with			
	approved 1.0mm Th. Laminate of desired shade and design on			
	both sides. Wooden molding, lipping etc. as directed by Bank /			
	architect shall be provided wherever required. The partition shall			
	have skirting and intermediate bands finished with metallic			
	laminate of desired shade and design.			
	(c) The low height partition shall have 12 mm thick glass with			
	etching as per design fixed with stainless steel wall cladding			
	profile (WCP) of Hettich /Godrej/Dorma/Ozone make at bottom			
	and sides with top surface and other side free. All the edges of the			
	12mm glass shall be duly grinded/bevelled and polished.			
	Makes :-			
	Commercial ply: Century, Greenply, Archid ply			
	Laminate : Aica, Greenlam, Marino, Formica			
4	12MM THICK TOUGHENED GLASS FIXED PARTITIONS WITH			
	ETCHING UPTO 9'-0" HT.			
	Providing and fixing in position 12mm clear float toughened Glass	35.13	SQ.M	
	partition with patch fittings for the full height glass partitions as per			
	the direction of the engineer-in-charge. The work to include			
	making necessary template for all the glasses and then cutting the			
	clear float glass to correct size, making all the necessary holes,			
	cuts etc., then toughen the same.			

	The cost to include all hardware (PATCH FITTINGS etc) required			
	of Hettich /Godrej/Dorma or approved equivalent make viz.,			
	single corner patch, top and bottom corner patch etc. or as per the			
	direction of the engineer-in-charge, along with etching with sand			
	blasting as per design and drawing. The maximum size of each			
	glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per			
	· 1			
	the site requirement. The rate is for a finished item of work etc.,			
	complete as directed.			
	The cost to include the cost of bevelling and smoothening of the			
	exposed edges of the glass.			
5	12MM THICK TOUGHENED GLASS DOORS WITH ETCHING:			
	Providing and fixing in position 12mm clear float toughened Glass	5.86	SQ.M	
	for naked glass door. The work to include making necessary			
	template for all the glasses and then cutting the clear float glass to			
	correct size, making all the necessary holes, cuts etc., and then			
	toughening the same. The cost to include all hardware required			
	viz., Hettich /Godrej/Dorma or approved equivalent make floor			
	spring with its accessories, top pivot, center lock, 450mm glass			
	door handles etc., along with etching with sand blasting as per			
	design and drawing. The maximum size of each glass shall be as			
	per the drawing or the direction of the Engineer-in-charge. The			
	rate is for a finished item of work etc., complete as directed.			
	·			
6	12mm thick Toughen glass for transaction partition	6.97	SQ.M	
	Providing and fixing 12 mm thick, clear plain toughened glass of			
	approved pattern fixed in vertical position at counter front and as			
	curved glass extension of low height partition as per drawing, fixed			
	on wooden partitions with superior quality stainless steel patch			
	fittings of Hettich /Godrej/ozone . An opening as per the drawing			
	at the bottom for transaction shall be provided in case of glass in			
	from of the transaction counter. All the edges of the glass shall be			
	grinded/bevelled and polished. The glass shall also be etched as			
	per the design. Glass area with maximum height shall be			
	measured for the purpose of payment. The work shall be carried			
	out as per drawings.			
	SWO COUNTERS FOR THE FRONT EXTENSION WITH			
1	JOVO COUNTLIS FOR THE FRONT EXTENSION WITH			
1	CLIDVED CLASS			
	CURVED GLASS			
	CURVED GLASS ATM SEPARATION TOTAL QUANTITY		SFT	

	TOTAL QUANTITY		SQ.M	
7	12MM TOUGHENED GLASS FOR FRONT:	3.72	SQ.M	
	Providing and fixing 12 mm thick, clear plain toughened glass of			
	approved pattern fixed in vertical position at counter front and as			
	curved glass extension of low height partition as per drawing, fixed			
	on wooden partitions with superior quality stainless steel patch			
	fittings of Hettich / Godrej /ozone. An opening as per the drawing			
	at the bottom for transaction shall be provided in case of glass in			
	from of the transaction counter. All the edges of the glass shall be			
	grinded/bevelled and polished. The glass shall also be etched as			
	per the design. Glass area with maximum height shall be			
	measured for the purpose of payment. The work shall be carried			
	out as per drawings.			
8	OFFICER'S TABLES WITHOUT SIDE CREDENZA			
	(a) Providing and fixing at site Officer's table (10 mm thk. glass on			
	table top with foam) made of 19mm th. commercial block Ply			
	(Green (Eco- Tech) / Century / Archid) with 1mm thick Laminate			
	(Merino / Sunmica / Formica) of desired shade and design on			
	outer visible surfaces; single color on horizontal surface & two			
	color on vertical surfaces. The front of the table top shall be			
	projected and curved as per drawing. Provision for 3" dia.			
	Round/3" square stainless steel of grade 304 cable manager for			
	computer / electrical cables at appropriate place, will be made in			
	the top surface of the table. Esteem Biege wood lipping will be			
	provided on all the edges of the table, including bottom touching			
	the floor and the drawers.			
	The counter shall have a wooden keyboard rest of size 600mm x			
	270mm made with 19mm ply fixed with sliding telescopic channels			
	of Hettich /Godrej/Ozone make. The work shall also include			
	provision of foot rest made with wooden member of section 3" x			
	5" along the leg space.			

	(b) There shall be provision of one storage cabinet 1'3" wide. The frame shall be made with 19mm thick commercial board. The cabinet shall have one lockable drawer running on side mounting			
	drawer slides (channels) of Hettich /Godrej/Ozone make & one			
	cupboard with shutter beneath the drawer, made of 19mm thick			
	commercial block board with 1mm thick laminate of desired shade			
	and design on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides			
	of the drawer shall be made of 12mm thick plywood, bottom of			
	6mm thick plywood & front of 19mm thick block board.			
	All other surfaces i.e. inside / leg space of table, inside of drawer /			
	cupboard shall be provided with 0.8mm thick laminate of desired			
	shade and design, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour.			
	The table shall have a CPU ledge made of 19mm thick block			
	board on one side, complete as per drawing.			
	OFFICER (1.52X0.76X0.76)	2.00	no.	
	BRANCH MANAGER (1.82X0.76X0.76)	1.00	no.	
	Makes :-			
	Commercial ply: Century, Greenply, Archid ply			
	Laminate : Aica, Greenlam, Marino, Formica			
	Telescopic Channels : Godrej, EBCO, Ozone	•		
	Drawer locks : Godrej, EBCO, Ozone			
	Auto lock : Ozone, EBCO			
9	GRAHAK MITRA/CRO COUNTER:			
	GRAHAR WITRACKO COURTER.			

(a) Providing and fixing at site counters (10 mm thk. glass on tab with foam) as per the design and drawings. Table to be made of thick commercial block board with 1mm thick laminate of desired sidesign and gloss on outer visible surfaces; single color on hori surface & two colors on vertical surfaces. Provision for 3" dia. Rou square stainless steel of grade 304 cable manager for compelectrical cables at appropriate place, will be made in the top surfather counter. Teak wood lipping will be provided on all the remedges of the counter, including bottom touching the floor and drawers. The counter shall have wooden keyboard rest of size 60 270mm fixed on sliding telescopic channels of Haffele/hettich/godrej. The work shall also include provision of formade with wooden member of section 3" x 5" along the leg space table to have writing top of toughened glass at 1200mm level a drawing.	19mm shade, izontal und /3" puter / face of faining and the 10mmx Hettich ot rest e. The
(b) The counters shall have three self lockable drawers running of mounting drawer slides (channels) of Haffele/Hettich make, ma 19mm thick commercial block board with 1mm thick laminate of dishade and design on front face & 3 nos. self locking drawer lock provided on one side of the counter as per layout. The sides of drawers shall be made of 12mm thick plywood, bottom of 6mm plywood & front of 19mm thick block board. All other surfaces i.e. in legsapce of table, inside of drawer/Cupboard shall be provided 0.8mm thick laminate of desired shade/design and wood lipp beading shall be PU polished with matching pigment/deco pain desired colour. The drawers shall have partitions for keeping cup notes as per drawing, complete in all respects including the restainless steel hardware like handles, hinges etc. The counter shall a CPU ledge made of 19mm thick commercial block board on one complete as per drawing.	ade of lesired
Note: The contractor to get the sample of the counter app from the Architect/ENGINEER before covering it with lan without any extra cost.	
Makes :-	
Commercial ply: Century, Greenply, Archid ply	
Laminate : Aica, Greenlam, Marino, Formica	
Telescopic Channels : Godrej, EBCO, Ozone	
Drawer locks : Godrej, EBCO, Ozone	
Diawer locks . Godiej, LDCO, Ozone	

	Auto lock : Ozone, EBCO			
10	SWO COUNTERS: (AS PER NEW DESIGN AND			
	SPECIFICATIONS) (5'-0"X3'-0"X2'-6")			
	(a) Providing and fixing at site SWO counters (10 mm thk. glass	4.00	Nos.	
	on table top with foam)as per the new design and drawings.			
	SWO counters to be made of 19mm thick commercial block board			
	with 1mm thick laminate (Merino / Formica / Sunmica) of desired			
	shade and design on outer visible surfaces; single color on			
	horizontal surface & two colors on vertical surfaces. The counter			
	shall have a curved front made with flexible 19mm ply (Green (
	Eco- Tech) / Century / Archid) and provision of kobe lighting as			
	per the drawings. The top with Curvilinear profile shall be made			
	out of 19mm thk. commer block board and finished with 6mm thk.			
	flexi ply as base for acrylic sheet or approved laminate as/design with provision for LED Light in bottom . Provision for 3" dia. Round			
	/3" square stainless steel of grade 304 cable manager for			
	computer / electrical cables at appropriate place, will be made in			
	the top surface of the counter. Teak wood lipping will be provided			
	on all the remaining edges of the counter, including bottom			
	touching the floor and the drawers. The counter shall have wooden			
	keyboard rest of size 600mmx 270mm fixed on sliding telescopic			
	channels of Hettich/Godrej. The work shall also include provision			
	of foot rest made with wooden member of section 3" x 5" along			

	(b) The counters shall have three self lockable drawers running on				
	side mounting drawer slides (channels) of Hettich/Godrej/godrej				
	make, made of 19mm thick commercial ply (Green (Eco- Tech) /				
	Century / Archid) with 1mm thick laminate (Merino / Formica /				
	Sunmica)of desired shade and design on front face & 3 nos. self				
	locking drawer locks be provided on one side of the counter as				
	per layout. The sides of the drawers shall be made of 12mm thick				
	plywood, bottom of 6mm thick plywood & front of 19mm thick				
	block ply (Green (Eco- Tech) / Century / Archid) . All other				
	surfaces i.e. inside / legsapce of table, inside of drawer/Cupboard				
	shall be provided with 0.8mm thick laminate of desired shade and				
	design, and wood lipping / beading shall be PU polished with				
	matching pigment/deco painted in desired colour. The drawers				
	shall have partitions for keeping currency notes as per drawing,				
	complete in all respects including the required stainless steel hardware like handles, hinges etc.The counter shall have a CP				
	touching the floor and the drawers. The counter shall have wooden				
	keyboard rest of size				
	Reyboard rest of size				
	Makes :-				
	Commercial ply: Century, Greenply, Archid ply				
	Laminate : Aica, Greenlam, Marino, Formica				
1				1	
	Telescopic Channels : Godrej, EBCO, Ozone				
	Telescopic Channels : Godrej, EBCO, Ozone Drawer locks : Godrej, EBCO, Ozone				
	Drawer locks : Godrej, EBCO, Ozone				
	Drawer locks : Godrej, EBCO, Ozone				
	Drawer locks : Godrej, EBCO, Ozone Auto lock : Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate				
	Drawer locks : Godrej, EBCO, Ozone Auto lock : Ozone, EBCO Note: The contractor to get the sample of the counter				
	Drawer locks : Godrej, EBCO, Ozone Auto lock : Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost.				
a)	Drawer locks : Godrej, EBCO, Ozone Auto lock : Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost. White acrylic stone (SWO counter top and front)				
a)	Drawer locks : Godrej, EBCO, Ozone Auto lock : Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost. White acrylic stone (SWO counter top and front) Providing and fixing (12mm thick) white acrylic stone	9.29	SQ.M		
a)	Drawer locks: Godrej, EBCO, Ozone Auto lock: Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost. White acrylic stone (SWO counter top and front) Providing and fixing (12mm thick) white acrylic stone (nonabsorbent, non-porous solid surface composite material,	9.29	SQ.M		
a)	Drawer locks : Godrej, EBCO, Ozone Auto lock : Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost. White acrylic stone (SWO counter top and front) Providing and fixing (12mm thick) white acrylic stone (nonabsorbent, non-porous solid surface composite material, belonging to the solid surface category) as per	9.29	SQ.M		
a)	Drawer locks: Godrej, EBCO, Ozone Auto lock: Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost. White acrylic stone (SWO counter top and front) Providing and fixing (12mm thick) white acrylic stone (nonabsorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all	9.29	SQ.M		
a)	Drawer locks: Godrej, EBCO, Ozone Auto lock: Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost. White acrylic stone (SWO counter top and front) Providing and fixing (12mm thick) white acrylic stone (nonabsorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all respect including buffing and wastage. (Make:	9.29	SQ.M		
a)	Drawer locks: Godrej, EBCO, Ozone Auto lock: Ozone, EBCO Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost. White acrylic stone (SWO counter top and front) Providing and fixing (12mm thick) white acrylic stone (nonabsorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all	9.29	SQ.M		

	Side credenza made of 19mm thick commercial ply frame and 6mm thick plywood on back side & 1mm thick laminate on top horizontal surface & one vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer compartment 16" wide outer to outer, containing three drawers vertically running on side mounting drawer slides(channels) of Godrej/hettich make. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block board. The remaining part of the credenza will have cupboard with Overlapped shutters and one shelf. All the internal surfaces shall be finished with 0.8mm thick mica of desired shade and design and the exposed wood shall be deco painted/malamine polished in desired shade.	17.00	RFT	
	Makes :-			
	Commercial ply: Century, Greenply, Archid ply			
	Laminate : Aica, Greenlam, Marino, Formica			
	Telescopic Channels : Godrej, EBCO, Ozone			
	Drawer locks : Godrej, EBCO, Ozone			
	Auto lock : Ozone, EBCO			
12	LOW HEIGHT STORAGE CABINETS/BACK STORAGE: (0.76 HIGH)			
	(a) Providing and fixing storage cabinets of size 2'6" (High) x 16" (Deep) along the walls/partitions, as per interior drawings, using 19mm board for carcase, shutters, vertical and horizontal partitions, 6mm ply for the back and 1mm laminate of approved shade on vertical and horizontal visible surfaces. The shutters shall be overlapped on the carcase and shall be provided with Hettich /Godrej/Ozonehinges. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the board shall be provided with wooden lipping 19mm x 3mm, duly PU polished/deco painted in desired shade. The inner surface shall be provided with 0.8mm thick laminate of desired shade and design. The cabinet shall be complete with handles, knobs, locks and magnet catchers etc. to the satisfaction of the Architect/Engineer.	21.88	RM	

	Makes :-			
	Commercial ply: Century, Greenply, Archid ply			
	Laminate : Aica, Greenlam, Marino, Formica			
	Drawer locks : Godrej, EBCO, Ozone			
	Auto lock : Ozone, EBCO			
13	GYPSUM BOARD FALSE CEILING WITH STEPS:			
	Providing and fixing suspended false ceiling including steps and provision of cope lighting as per design with 12.5mm tapered edge Gypboard / 12mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consisting of a perimeter channel fixed round the perimeter. The intermediate channel at 1200mm c/c in the one direction and the ceiling section at 450mm c/c in the other direction to be connected by a connecting clip. The grid to be suspended with an adjustable strap hanger.	115.06	SQ.M	
	The grid to be suspended with an adjustable strap hanger at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts to be used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers to be screwed to the M/F ceiling sections with Gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge including 2-3 coats of oil bound distemper, over a coat of primer. (Makes:-GYSUM INDIA/Saint Gobain)			
14	GRID FALSE CEILING:			
	Silhouette Grid False Ceiling:- Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries. The suspension system shall be the Armstrong Trulok Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions.	80.30	SQ.M	

	Main runners to be spaced at 120mm c/c fixed by using 2mm perstraightened GI wire. Main tee, rotary stitched at every 1200mm c/c maximum and 1200mm cross tee at every 600mm c/c maximum and 600mm cross tee at every 1200mm c/c maximum and wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm per-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of premier mineral fiber RH-99 Dune tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as per manufacturer's specifications.			
15	Semi glazed wooden doors with frame :- WIDTH (2'-6" TO 3'-6")			
	Providing & fixing of 35mm thick semi glazed flush type doors. Doors shall be finished with 1mm thick laminate of approved colour & make with 35 x 5mm steam beach wood beading on edges of door. The glass shall be 8mm thick clear float glass with edge polishing & round smoothenend exposed edges All accessories like the door stopper, heavy duty brass hinges, latch, handle, lock etc shall be part of the job. All teak wood members to have melamine spray polish finish. Rate to include cost of conveyance of all materials, labour charges etc. complete as directed. As per approved hardware list.	-	NO.	
16	ACP SHEETS AT ENTRANCE			
	Providing and fixing Aluminium Composite Panel (ALSTRONG/ALUCOBOND/ALSTONE) wall cladding with the 4mm thick PVDF coated aluminium composite panel (ACP) (0.25 mm coil thick) with frame of alumimnium channels (25 x 50 x 1.6mm), cleat angle (8 x 18 x 2mm) necessary hardware, backup material and weather sealant to make the joints leak proof. The spacing for the channel along the length and spacing of cleat on the perpendicular shall not be more than 600mm. The rate includes all required shuttering, scaffolding,labor,material.	44.77	SQ.M	
17	WOODEN BOXING FOR ELECTRICAL PANEL 10'-0" X9'-0"X2'-0"			

	Providing & fixing of Electrical panel cabinate, made of 8mm thick commercial ply shutter. External side shall be finished with 1mm thick laminate(Merino / Sunmica / Formica)& internal side shall be finished with backlyte sheet . All accessories like ball catches, ss handle, Fixing MS powder cotted perforeted jali shall be provided in shutter top & bottom etc. All internal frames 50mm x 25mm x 1.6mm thick section at maximum 2'-0" c/c. Complete as directed depth of cup board 1'-6". Measurement shall be based on area of front elevation of cupboard. The rate to include all materials, labour, transport, taxes, etc complete as directed. As per approved hardwere list.	1.00	NO.	
	Makes :-			
	Commercial ply: Century, Greenply, Archid ply			
	Laminate : Aica, Greenlam, Marino, Formica			
18	LOW HT. STORAGE CABINET FOR GENERAL STORAGE-			
	Providing and Fixing of pantry storage cabinet depth 600mm with shutters made in 19 mm thick com. block board and 6mm thick com ply for back side to be fixed on the wall, with 19mm thick com. block board shelves inside placed horizontally with self closing bright finished CP hinges,inside 0.8 mm thk laminate finish and shutters finished with 1 mm thick laminate of approved color and shade .The item includes providing 150mm SS finished handles on front for shutters,including necessary hardware etc. all complete as per drawing and to the instruction of Engineer in charge.		SQ.M	
19	OVER HEAD STORAGE CABINET FOR PANTRY			

	Providing and Fixing of Pantry over head storage cabinet depth 400mm, height 600mm with shutters made in 19 mm thick commercial block board and 6mm thick com ply for back side to be fixed on the wall, with 19mm thick commercial block board shelves inside placed horizontally and vertically with piano hinges. All inside surfaces to be 0.8 mm thk laminate and outer faces of shutters and sides (excluding outer top and bottom faces which are to be enamel painted) to be finished with 1 mm thick laminate of approved color and shade. The item includes providing 150mm brass handles on front for shutters,magnetic catchers, including necessary hardware etc. all complete as per drawing and as per instruction of Engineer in charge.	2.23	SQ.M	
	Makes :-			
	Commercial ply: Century, Greenply, Archid ply			
	Laminate : Aica, Greenlam, Marino, Formica			
20	HYDRAULIC DOOR CLOSER:	2.00	No	
	Providing and fixing silver color (or matching with color scheme as per site) hydraulic door closer Hyper / Ever-rite ISI marked make, to doors complete in all respects.			
	(Makes :- Godrej, Doroma, Ozone)			
<u>21</u>	FIRE PROOF DOOR FRAME: FIRE PROOF DOOR FRAME:- Providing and fixing fire resistant door frame of section 143 x 57 mm having built in rebate made out of 16 SWG G.I. Sheet (zinc coating not less than 120 gm/sqm) duly filled with vermuculite based concrete mix, suitable for mounting 60 minutes fire rated door shutters. The frame is fitted with intumuscent fire seal strip of size 10x4 mm (minimum) alround the frame and fixing with dash fastener of approved size and make, including applying a coat of approved brand fire resistant primer etc. complete as per direction of Engineer-incharge (including Dash fastener).			

	FIRE PROOF SHUTTER :- Providing and fixing 50 mm thick			
	glazed fire resistant door shutters conforming to IS:3614 (Part-II),			
	tested and certified as per laboratory approved by Engineer-in-			
	charge, with suitable mounting on door frame, consisting of			
	vertical styles, lock rail, top rail 100 mm wide, bottom rail 200 mm			
	wide, made out of 16 SWG G.I. sheet (zinc coating not less than			
	120 gm/ m2) duly filled FR insulation material and fixing with			
	necessary stainless steel ball bearing hinges of approved make,			
	including applying a coat of approved fire resistant primer etc. all			
	complete as per direction of Engineer-in- charge (paneling to be			
	paid for separately)			
	FIRE PROOF GLASS PANEL :- Providing and fixing glazing in			
	fire resistant door shutters, fixed panels, ventilators and partitions			
	etc., with G.I. beading of appropriate size, made out of 20 SWG			
	G.I. Sheet (zinc coating not less than 120 gm/ m2), fire resistant			
	sealant, including applying a coat of approved fire resistant primer			
	on G.I. beading etc., complete all as per direction of Engineer-in-			
	charge.			
	With clear fire resistant glass panes 6 mm thick of approved			
	brand, having minimum 60 minutes fire resistance			
	3'-0" X 7'-0"	1.00	NOS.	
22	RECTANGULAR WRITING DESK WITH STORAGE WITH			
	CUSTOMER AND COMPLAINT BOX AS PER DRGS.			
	Providing & fixing of Rectangular writing desk with provision of	1.00	NO.	
	complaint and suggestion box, made of 18mm thick commercial			
	plywood finished with 1 mm thick laminate on all sides including			
	inside divisions. 12mm thick toughen glass Shelf shall be fixed of			
	desk with bevelled and polished edges making different divisions			
	by 12mm thick toughen glass for slips or forms as per detail			
	drawing directed complete. The rate to include all materials,			
	labour, transport, taxes, etc complete as directed. (Size: 4'-0" X 1'-			
	0" X 3'-6"ht.)			
	Makes :-			
	Commercial ply: Century, Greenply, Archid ply			
	Laminate : Aica, Greenlam, Marino, Formica			
	TROPHY CASE OF OUR LICEL FOR PRANCIL MANAGER AS DER			
1 22	TROPHY CASE 9'-0" HIGH FOR BRANCH MANAGER AS PER			
23	DRAWING. (10'-0"X1'-6" /2'-0"X 9'-0"			

	Providing and fixing trophy case using 18mm commercial Ply bottom, behind, Sides and top (Green (Eco-Tech) / Century / Archid) finished in 1.0 mm thick laminate of approved Shade, Max height of the case upto false ceiling bottom, behind, Sides and top and bottom out of commercial Ply (Green (Eco-Tech) / Century / Archid) and Laminate. 15" width of glass or wooden shelves of the case to be done using 10 mm thk. R polished glass in shelves (The Glass fixed with u brackets). Complete with closing of all joints and accessories complete in all respect as per direction of Engineer-In-Charge.	1.00	NO.	
	Commercial ply: Century, Greenply, Archid ply			
	Laminate : Aica, Greenlam, Marino, Formica			
24	SBI LOGO (SIZE 2'-0" DIA)			
	Providing and making SBI logo using acrylic signage	2.00	NO.	
	logo with light . Complete in all respect as per direction			
	of Engineer-In-Charge.			
25	PAINT			
	TEXTURE PAINT (Madrasi Dana) including applying average 12mm to 15mm thick POP Punning over cement plaster in line & plumb finished smooth to receive paint. (Internal surfaces of walls).as per approved. Suggested Brand Asian Paints.	10.00	SQ.M	
26	MDF JALI ON COLUMNS			
26	Making and fixing in position (as per approved sample) Laser Cut	5.00	SQ.M	
	Jaali partition to be made out of MDF board of 8mm. thickness and make. All exposed surfaces to be finish with Duco paint in desired colour. All complete as/ designto the entire satisfaction of Architect/ Engineer in charge (Elevation area to measure).	5.00	3Q.M	
	Total Value of Works			
	NOTE: GST SHALL BE PAID EXTRA			