

**BILL OF QUANTITIES FOR ELECTRICAL, LIGHTING & DATA NETWORKING WORKS AT STATE BANK OF INDIA, MORSHINGI Branch at MORSHINGI, Distt. BILASPUR ( H.P)**

| S.No.  | Item / Specifications  | Qty. | Units | Rate | Amount |
|--|--|------|-------|------|--------|
| <b>PART-I : COMPUTER POINTS &amp; DISTRIBUTION</b> |  |      |       |      |        |
| 1.1  | Supply all material, storing, handling, fixing and laying of 3X2.5 Sq. mm. of PVC insulated PVC sheathed armoured cable of 1100 V (IS 1554, Part 1) and fixing of cable on wall with suitable size of clamps /saddles or laid in floor/recess wall including cutting of wall /floor and making good the damages etc for computer points in suitable size of box fabricated with 16 G MS sheet including providing <b>3 nos 5 amps 3 pin sockets controlled by 1 no 5 A modular type switch, indicator and fuse mounted on 3 mm thick ISI marked hylam sheet and painting of box etc complete as required Note; max. two computer points are to be provided on one circuit.</b> | 16   | each  |      |        |
| 1.2  | As per item 1 above but with 1 Nos. 15 A 5 pin socket controlled by 1 no 15 A switch and indicator.( ON RAW POWER)   | 2    | each  |      |        |
| 1.3  | As per item 1 above but with 2 Nos. 15 A 5 pin socket controlled by 1 no 15 A switch and indicator.( ON UPS POWER)   | 6    | each  |      |        |
| 1.4  | Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.  |      |       |      |        |
| a)   | 2 X 6 sq. mm + 1 X 2.5 sq. mm earth wire   | 30   | Mtr   |      |        |
| 1.5  | Wiring for light point/ Ceiling fan point/ exhaust fan point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. <u>including circuit wiring with 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire</u> as required.(Ht. upto 4.5mtrs from floor)   |      |       |      |        |
| A  | 1 no. light controlled by 1 no. switch   | 15   | no    |      |        |
| B  | 2 no. light controlled by 1 no. switch   | 20   | no    |      |        |
| C  | 5/6 pin 6 amp plug point with 6 amp switch   | 8    | no.   |      |        |
| D  | Primary Wall fan point controlled by 5 AMP socket controlled by 5amp switch  | 8    | no.   |      |        |
| 1.6  | Supply installation testing and commissioning of 3 pin 20/25 A 3 pin metal clad industrial type plug and socket arrangement with plug top, cap and chain controlled by 1 no 32 A SP MCB.( 1.5 TR Acs) Note; Independent circuit for AC point is to be provided starting from distribution system.  | 6    | each  |      |        |
| 1.7  | Supply, installation testing and commissioning of factory fabricated distribution board rust inhibited   |      |       |      |        |
|  | powder coated sheet fabricated comprising of incoming and outgoing isolator & MCBs neutral link or neutral bus, top and bottom detachable entry earthing bolts interconnection and grouting bolts etc complete as required as per details below  |      |       |      |        |
| a)   | 8-way SPN MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 63 A DP Isolator and 6 Nos. 6/10 A MCBS etc complete as required.   | 1    | no.   |      |        |
| b)   | 6-way SPN MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 40 A DP Isolator and 4 Nos. 6/10 A MCBS etc complete as required.   | 1    | no.   |      |        |
| c)   | 4 way SPDB comprising 1 no 63 A Four Pole TPNMCB ( for UPS).   | 1    | no.   |      |        |
| d)   | 4 way SPDB comprising of 2 nos 63A DP MCB ( for UPS).  | 2    | no.   |      |        |

|                                      |   |      |      |  |  |
|--------------------------------------|---|------|------|--|--|
| e)                                   | 4 Way TP MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 100 A 4P Isolator and 6 Nos. 32 A DPMCBS etc complete as required. (AC DB)  | 1    | no.  |  |  |
| f)                                   | 4 Way TP MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 100 A 4P Isolator and 12 Nos. 6-32 A SPMCBS etc complete as required.(LIGHT /POWER Dbs)   | 1    | no.  |  |  |
| 1.8                                  | Supply installation testing and commissioning of following 3 pin metal clad industrial type plug and socket arrangement with plug top, cap and chain controlled by 1 No MCB   |      |      |  |  |
| (a)                                  | 20 Amps. with 20 Amp. SP MCB.   | 4    | no.  |  |  |
| (b)                                  | 30 Amps. with 32 Amp. SP MCB.   | 3    | no.  |  |  |
| 1.90                                 | Providing and fixing of suitable size MS box fabricated with 16 G MS sheet either in recess wall or on surface to accommodate dedicated earth from earth electrode and further distribution of earth to computer points including providing of 5 mm bakelite on base connector strip and painting of box etc as required.                   | 1    | job  |  |  |
| <b>TOTAL OF PART -I</b>              |   |      |      |  |  |
| <b>PART-II : PANELS &amp; CABLES</b> |   |      |      |  |  |
| 2.1                                  | Providing and fixing of 03 no 100 Amps KITKAT with 1 no neutral link on suitable size of Bakelite sheet of thickness not less than 12 mm complete as required   | 1.00 | job  |  |  |
| 2.2                                  | Supply & Installation of TPN vertical distribution board with provision for 4 pole MCCB as incomer with copper bus bar,earth and neutral bus. With 125Amp 4 Pole 25 K MCCB Incomer and for Outgoing 4 no 63 A TP MCB .  | 1    | Set  |  |  |
| 2.3                                  | Supply, Installation, testing & commissioning of PVC insulated PVC sheathed armoured cable of 1100 V ( IS 1554 Part 1) and fixing of cable on wall with suitable size of clamps /saddles or laid in floor/recess wall including cutting of wall /floor and making good the damages etc complete as required of following sizes (ISI marked) |      |      |  |  |
| a)                                   | 4 x 16 sq. mm aluminium conductors with two Nos. 8 SWG GI wire.   | 50   | mtr. |  |  |
| b)                                   | 4X10 sq. mm aluminum conductor with one no 8 SWG GI wire.   | 50   | mtr. |  |  |
| c)                                   | 3X6 sq. mm copper conductor armoured .  | 40   | mtr. |  |  |
| d)                                   | 3X2.5 sq. mm copper conductor armoured for ACS  | 30   | mtr. |  |  |
| 2.4                                  | End termination with brass compression glands including providing of lugs/ferrules and making necessary connection etc complete as required of the following sizes:   |      |      |  |  |
| a)                                   | 4 x 16 sq. mm aluminum conductors   | 7    | no.  |  |  |
| b)                                   | 4X10sq.mm aluminum conductor  | 10   | no.  |  |  |
| c)                                   | 3X6 sq. mm copper conductor   | 4    | no.  |  |  |
| d)                                   | 3X2.5 sq. mm copper conductor   | 12   | no.  |  |  |
| 2.5                                  | Providing and fixing the following switch on suitable size of MS base and angle iron frame of suitable size and strength for installation on wall /floor including grouting of frame & painting etc. complete as required .   |      |      |  |  |
| a)                                   | 1 no.4 pole 160 Amps capacity change over switch with adaptor box   | 1    | no.  |  |  |
| 2.6                                  | Providing and fixing 16 G MS sheet adopter box and also base frame for installation of MCB DBs plug and socket arrangements and to cover cables in system room including painting etc complete as required.   |      |      |  |  |

|  |  |     |      |  |  |
|--|--|-----|------|--|--|
|  | for UPS input/output distribution  | 1   | no.  |  |  |
|  | <b>TOTAL OF PART -II</b>   |     |      |  |  |
| <b>PART-III : EARTHING</b>                                   |  |     |      |  |  |
| 3.1 (a)  | Supply and fix copper plate earth station with 600X600X3mm copper plate including all accessories such as watering pipe and funnel and providing masonry enclosure at top with cover plate i.e excavation of pit, supplying and filling of salt charcoal, refilling of pit etc complete as required as per IS 3043-1987. The voltage between neutral and earth must be below 1 V.  | 1   | set  |  |  |
| (b)  | Supply and fix GI plate earth station with 600X600X6mm GI plate including all accessories such as watering pipe and funnel and providing masonry enclosure at top with cover plate i.e excavation of pit, supplying and filling of salt charcoal, refilling of pit etc complete as required as per IS 3043-1987.   | 2   | set  |  |  |
| 3.2 (a)  | Supply fixing and termination of 20X3 mm copper strip with earth station below ground level etc as required.   | 3   | mtr. |  |  |
| (b)  | Supply fixing and termination of 32x6 mm G.I. strip with earth station below ground level etc as required.   | 6   | mtr. |  |  |
| 3.3 (a)  | Providing and fixing of 8 SWG copper earth wire in the recess for loop earthing etc. as required.  | 25  | mtr. |  |  |
| (b)  | Providing and fixing of 8 SWG GI earth wire in the recess for loop earthing etc. as required.  | 20  | mtr. |  |  |
| 3.4 a)   | Supply and laying following dia 3.38 mm( Confirming to ASTM D1785 Standard) in thickness heavy duty PVC pipe under floor or in recessed walls for AC drains. including bends Tees Etc. making good the damages etc. wherever required..  |     |      |  |  |
|  | 25mm   | 45  | mtr. |  |  |
| b)   | Supply and laying following dia 2 mm in thickness PVC pipe under floor or in recessed walls from earth electrode to UPS room for computer dedicated earthing including bends Tees Etc. making good the damages etc. wherever required..  |     |      |  |  |
|  | 25 mm diameter   | 40  | mtr. |  |  |
|  | <b>TOTAL OF PART -III</b>  |     |      |  |  |
| <b>PART-IV : AC PROVISIONING (COPPER PIPE, WIRING ETC)</b>   |  |     |      |  |  |
| 4.1  | Supply, Installation, testing & commissioning of refrigeration pipe including cutting of wall & fixing with suitable saddles or clamps, providing suitable sizes of sleeves for passing refrigerant pipe from indoor to outdoor unit including making necessary arrangement etc. complete as required.   |     |      |  |  |
| a)   | Hi Wall Split AC (1.0 & 1.5TR), copper pipe size (1/2" & 1/4")   | 50  | mtr. |  |  |
| 4.2  | Supply & laying of 3 core 2.5sq.mm. FRLS copper flexible cable for HWS AC, Make - FINOLEX / POLYCAB / HAVELLS / PYEMEN / ECKO  | 110 | mtr  |  |  |
|  | <b>TOTAL OF PART - IV</b>  |     |      |  |  |
| <b>PART-V : TELEPHONE , CCTV &amp; SMOKE DETECTOR WIRING</b> |  |     |      |  |  |
| 5.1  | Wiring for telephone points with 0.6 mm dia 2 pair insulated annealed tinned electrolytic copper conductor in 2 mm thick 25 mm dia ISI marked PVC conduit complete with accessories such as bends, junction boxes etc. with suitable size of G.I. box modular plate and cover in front on surface or in recess including providing and fixing modular type telephone socket outlet and making necessary connections etc. complete as reqd. | 5   | no.  |  |  |
| 5.2  | Supply installation and testing of Tag Block 20 pair for telephone connections   | 1   | no.  |  |  |
| 5.3  | Supply and fixing 20 Pair Telephone Cable  | 30  | mtr  |  |  |
|  | <b>TOTAL OF PART - V</b>   |     |      |  |  |

|   |  |       |         |  |  |
|---|--|-------|---------|--|--|
| <b>PART-VI : NETWORKING</b>   |  |       |         |  |  |
| 6.1   | Wiring for computer net working starting from mounting rack with UTP Cat 6 cable in 2 mm thick 25 mm dia ISI marked PVC conduit pipe with accessories such as bends, junction boxes including providing and fixing I/O plates and SMB complete with all networking accessories etc complete as required  | 14    | No      |  |  |
| 6.2   | Removal & Re-installation of existing Switch as per approved layout  | 1.00  | no.     |  |  |
| 6.3   | supply, installation, testing and commissioning of 16-port Patch Panel   | 1.00  | no.     |  |  |
| 6.4   | Supply and installation, testing and commissioning of mounted rack 12" hight made of powder coated MS sheet  | 1.00  | no.     |  |  |
| 6.5   | Supply Fixing and commissioning of Patch cable cat 6 of complete with 2 nos of connectors etc complete as required.( factory manufactured)   |       |         |  |  |
|   | (a) 1 meter long   | 14    | No      |  |  |
|   | (b) 2 meter long   | 10    | No      |  |  |
| 6.6   | Supply and laying of CAT 6 cable in PVC conduit of suitable size with connectors as required., complete in all respects.   | 30.00 | mtr     |  |  |
| <b>TOTAL OF PART - VI</b>   |  |       |         |  |  |
| <b>PART-VII : SITC OF FANS &amp; FIXTURES</b>   |  |       |         |  |  |
| 7.1   | SITC of 2'-0" x2'-0" Ceiling grid 33-36 watt LED panel fixtures with essential driver in <b>false ceiling including making necessary arrangement for mounting the fixtures</b> and connection with 2 x 1.5 sq.mm insulated copper cable from adjacent point in PVC flexible pipe etc Complete as reqd. Make Philips cat. RC 380 B- LED-30-6500PSE OD WH or equivalent of Wipro / Bajaj / Crompton. <b>Note: No additional payment will be made for providing frame for light fixing in Gypsum ceiling.</b> | 7     | no.     |  |  |
| 7.2   | SITC of 15 watt recess mounted <b>LED down light</b> with assembly complete with including making necessary connections etc. Complete as reqd. ( M/s Crompton Cat No. Or equivalent of Philips/Wipro/ Bajaj)   | 30    | no.     |  |  |
| 7.3   | Supply of 450 mmm sweep metal body wall fan complete as reqd. Model turbo 180, USHA Make or equivalent of Crompton/Havells/Bajaj<br><br>(M/s Crompton Hi-Flo or equivalent of Khaitan / Bajaj)   | 6     | no.     |  |  |
| 7.4   | SITC of Exhaust Fan 12inch dia, m etal body of CROMPTON / BAJAJ /KHAITAN   | 2     | no.     |  |  |
| 7.5   | Supply Installation, testing & commissioning of LED STRIP light with driver and Accessories complete as required ( MS CROMPTON or equivalent of WIPRO , PHILLIPS, BAJAJ etc.   | 15    | mtr     |  |  |
| 7.6   | SITC of 18 /20 watt of T5 LED fixtures directly on ceiling / wall including making necessary connections with 2x1.5 sq.mm insulated copper cable conductor wire etc. complete as reqd Make Phillips cat no. DN - 192 - 1000 or equivalent of Wipro / Bajaj.  | 3     | no.     |  |  |
| 7.7   | SITC of 30 watt Street light /Flood light for lighting the front side of the branch(M/s Crompton Cat No. LSTS-30-CDL or equivalent of Philips/Wipro .  | 2     | no.     |  |  |
| <b>TOTAL OF PART -VII</b>   |  |       |         |  |  |
| <b>PART-VIII : CREDIT OF OLD MATERIAL</b>   |  |       |         |  |  |
| 8.1   | Existing old wiring including old tube lights,Switches, computer point Sockets,MCB DBs Cables and wires (work also includes removal from the premises).  | 1     | Lumpsum |  |  |
| <b>No LED Light Fittings &amp; fans are part of Credit Item (all lights to be re-used in Branch)</b>  |  |       |         |  |  |
| The work includes removing of complete old wiring as directed, ensuring there is no hindrance to branch working and removing the old stuff to contractors own dump. |  |       |         |  |  |

|              |   |  |  |  |  |
|--------------|---|--|--|--|--|
|              | No electrical/data/telephone point shall be removed prior to Branch Head approval. NO CCTV/Smoke Detectoes/fire alarms to be removed  |  |  |  |  |
| <b>NOTE:</b> | <b>Dismantaaling of existing connections, temporary re-arrangements of UPS points /Data Points/Light Points/Tel Points for smooth working of branch during renovation works will have to be done by the executing agency.</b> |  |  |  |  |
|              | <b>TOTAL OF PART -VIII</b>  |  |  |  |  |
|              | <b><u>SUMMARY</u></b>   |  |  |  |  |
|              |   |  |  |  |  |
|              | <b>TOTAL OF PART I-VI(A)</b>  |  |  |  |  |
|              | <b>TOTAL OF PART - VII (B)</b>  |  |  |  |  |
|              | <b>TOTAL OF PART - VIII (C)</b>   |  |  |  |  |
|              | <b>TOTAL (A+B-C)</b>  |  |  |  |  |
|              |   |  |  |  |  |